

# tinytable

Easy, beautiful, and customizable tables in R

## Table of contents

<b>1</b>	<b>Tiny Tables</b>	<b>4</b>
1.1	Width . . . . .	4
1.2	Footnotes . . . . .	6
1.3	Captions and cross-references . . . . .	8
1.4	Line breaks and text wrapping . . . . .	9
1.5	Output formats . . . . .	9
1.6	Combination and exploration . . . . .	11
1.7	Renaming columns . . . . .	14
<b>2</b>	<b>Formatting</b>	<b>15</b>
2.1	Numbers, dates, strings, etc. . . . .	15
2.2	Significant digits and decimals . . . . .	17
2.3	Math . . . . .	18
2.4	Replacement . . . . .	20
2.5	Escape special characters . . . . .	21
2.6	Markdown . . . . .	22
2.7	Custom functions . . . . .	23
<b>3</b>	<b>Style</b>	<b>25</b>
3.1	Cells, rows, columns . . . . .	26
3.2	Colors . . . . .	29
3.3	Alignment . . . . .	30
3.4	Font size . . . . .	31
3.5	Spanning cells (merging cells) . . . . .	31
3.6	Headers . . . . .	34
3.7	Conditional styling . . . . .	35
3.8	Vectorized styling (heatmaps) . . . . .	36
3.9	Lines (borders) . . . . .	37
3.10	Cell padding (height and width) . . . . .	39

3.11	Markdown and Word . . . . .	40
<b>4</b>	<b>Groups and labels</b>	<b>41</b>
4.1	Rows . . . . .	41
4.1.1	Automatic row groups . . . . .	44
4.2	Columns . . . . .	45
<b>5</b>	<b>Themes</b>	<b>47</b>
5.1	Visual themes . . . . .	48
5.2	Custom themes . . . . .	49
5.3	Tabular . . . . .	51
5.4	Resize . . . . .	51
5.5	Placement . . . . .	52
5.6	Rotate . . . . .	52
5.7	Multipage . . . . .	52
5.8	User-written themes . . . . .	56
5.8.1	<code>theme_mitex()</code> . . . . .	56
<b>6</b>	<b>Plots and images</b>	<b>57</b>
6.1	Inserting images in tables . . . . .	57
6.2	Inline plots . . . . .	58
6.2.1	Built-in plots . . . . .	58
6.2.2	Custom plots: Base R . . . . .	59
6.2.3	Custom plots: <code>ggplot2</code> . . . . .	59
<b>7</b>	<b>Customization</b>	<b>61</b>
7.1	HTML . . . . .	61
7.1.1	Bootstrap classes . . . . .	62
7.1.2	CSS declarations . . . . .	62
7.1.3	CSS rules . . . . .	62
7.2	LaTeX / PDF . . . . .	62
7.2.1	Preamble . . . . .	62
7.2.2	Introduction to <code>tabularray</code> . . . . .	62
7.2.3	<code>tabularray</code> keys . . . . .	64
7.3	Shiny . . . . .	67
<b>8</b>	<b>FAQ</b>	<b>67</b>
8.1	HTML . . . . .	67
8.2	LaTeX . . . . .	68
8.2.1	Preamble . . . . .	68
8.2.2	<code>setspace</code> . . . . .	68
8.2.3	Global styles . . . . .	70
8.2.4	Beamer . . . . .	70

8.3	Typst . . . . .	71
8.3.1	Captions and labels . . . . .	71
8.3.2	Multi-page long tables . . . . .	71
8.4	Markdown . . . . .	72
8.4.1	<code>style_tt()</code> does not apply to row headers . . . . .	72
8.4.2	<code>rowspan</code> and <code>colspan</code> . . . . .	72
8.5	Quarto . . . . .	72
8.5.1	Custom crossref styles . . . . .	72
8.5.2	Sub-captions . . . . .	73
8.5.3	Same table, different styles . . . . .	74

# 1 Tiny Tables

`tinytable` is a small but powerful R package to draw HTML, LaTeX, Word, PDF, Markdown, and Typst tables. The interface is minimalist, but it gives users direct and convenient access to powerful frameworks to create endlessly customizable tables.

Install the latest version from R-Universe or CRAN:

```
install.packages("tinytable",  
  repos = c("https://vincentarelbundock.r-universe.dev", "https://cran.r-project.org"))
```

This tutorial introduces the main functions of the package. It is also [available as a single PDF document](#).

Load the library and set some global options:

```
library(tinytable)  
options(tinytable_tt_digits = 3)  
options(tinytable_theme_placement_latex_float = "H")
```

Draw a first table:

```
x <- mtcars[1:4, 1:5]  
tt(x)
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

## 1.1 Width

The `width` arguments indicating what proportion of the line width the table should cover. This argument accepts a number between 0 and 1 to control the whole table width, or a vector of numeric values between 0 and 1, representing each column.

```
tt(x, width = 0.5)
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

```
tt(x, width = 1)
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

We can control individual columns by supplying a vector. In that case, the sum of `width` elements determines the full table width. For example, this table takes 70% of available width, with the first column 3 times as large as the other ones.

```
tt(x, width = c(.3, .1, .1, .1, .1))
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

When the sum of the `width` vector exceeds 1, it is automatically normalized to full-width. This is convenient when we only want to specify column width in relative terms:

```
tt(x, width = c(3, 2, 1, 1, 1))
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

When specifying a table `width`, the text is automatically wrapped to appropriate size:

```
lorem <- data.frame(
  Lorem = "Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo.",
  Ipsum = "Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui placeat aut tempora ratione ut qui sunt aut voluptas et dignissimos laborum accusantium doloribus accusantium doloribus accusantium."
)

tt(lorem, width = 3/4)
```

Lorem	Ipsum
Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo.	Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos.

## 1.2 Footnotes

The `notes` argument accepts single strings or named lists of strings:

```
n <- "Fusce id ipsum consequat ante pellentesque iaculis eu a ipsum. Mauris id ex in nulla congue."
tt(lorem, notes = n, width = 1)
```

Table 1: A full-width table with wrapped text in cells and a footnote.

Lorem	Ipsum
Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo.	Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos.

Fusce id ipsum consequat ante pellentesque iaculis eu a ipsum. Mauris id ex in nulla consectetur aliquam. In nec tempus diam. Aliquam arcu nibh, dapibus id ex vestibulum, feugiat consequat erat. Morbi feugiat dapibus malesuada. Quisque vel ullamcorper felis. Aenean a sem at nisi tempor pretium sit amet quis lacus.

When `notes` is a named list, the names are used as identifiers and displayed as superscripts:

```
tt(x, notes = list(a = "Blah.", b = "Blah blah.))
```

mpg	cyl	disp	hp	drat
21	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

<sup>a</sup> Blah.

<sup>b</sup> Blah blah.

We can also add markers in individual cells by providing coordinates:

```
tt(x, notes = list(
  a = list(i = 0:1, j = 1, text = "Blah."),
  b = "Blah blah."
))
```

Table 2: Blah blah blah

mpg	cyl	disp	hp
21	6	160	110
21	6	160	110
22.8	4	108	93
21.4	6	258	110

mpg <sup>a</sup>	cyl	disp	hp	drat
21 <sup>a</sup>	6	160	110	3.9
21	6	160	110	3.9
22.8	4	108	93	3.85
21.4	6	258	110	3.08

<sup>a</sup> Blah.

<sup>b</sup> Blah blah.

### 1.3 Captions and cross-references

In Quarto, one should always specify captions cross-references using chunk options, and should *not* use the `caption` argument. This is because Quarto automatically post-processes tables, and may introduce conflict with the captions inserted by `tinytable`. For example:

```
@tbl-blah shows that...
```

```
```{r}
#| label: tbl-blah
#| tbl-cap: "Blah blah blah"
library(tinytable)
tt(mtcars[1:4, 1:4])
```
```

And here is the rendered version of the code chunk above:

Table 2 shows that...

```
library(tinytable)
tt(mtcars[1:4, 1:4])
```



One exception to the injunction above is when rendering a Quarto document to LaTeX using `theme_tt("multipage")`. In that case, one must *avoid* using the Quarto chunk option, because these options trigger Quarto post-processing that will conflict with the `longtblr` environment used to split long tables across multiple pages.

The alternative is to use to refer to tables using standard LaTeX syntax: `\ref{tbl-ex-multipage}`. Then, use the `caption` argument in `tt()` to specify both the label and the caption:

```
tt(iris, caption = "Example table.\\label{tbl-ex-multipage}") |>
  theme_tt("multipage")
```

For standalone tables in any format (i.e., outside Quarto), you can use the `caption` argument like so:

```
tt(x, caption = "Blah blah.\\label{tbl-blah}")
```

## 1.4 Line breaks and text wrapping

Manual line breaks work slightly different in LaTeX (PDF) or HTML. This table shows the two strategies. For HTML, we insert a `<br>` tag. For LaTeX, we wrap the string in curly braces `{}`, and then insert two (escaped) backslashes: `\\`

```
d <- data.frame(
  "{Sed ut \\ \\ \\ perspiciatis unde}",
  "dicta sunt<br> explicabo. Nemo"
) |> setNames(c("LaTeX line break", "HTML line break"))
tt(d, width = 1)
```

---

| LaTeX line break            | HTML line break                |
|-----------------------------|--------------------------------|
| Sed ut<br>perspiciatis unde | dicta sunt<br> explicabo. Nemo |

---

## 1.5 Output formats

`tinytable` can produce tables in HTML, Word, Markdown, LaTeX, Typst, PDF, or PNG format. An appropriate output format for printing is automatically selected based on (1) whether the function is called interactively, (2) is called within RStudio, and (3) the output format of the Rmarkdown or Quarto document, if applicable. Alternatively, users can specify the print format in `print()` or by setting a global option:

```

tt(x) |> print("markdown")
tt(x) |> print("html")
tt(x) |> print("latex")

options(tinytable_print_output = "markdown")

```

With the `save_tt()` function, users can also save tables directly to PNG (images), PDF or Word documents, and to any of the basic formats. All we need to do is supply a valid file name with the appropriate extension (ex: `.png`, `.html`, `.pdf`, etc.):

```

tt(x) |> save_tt("path/to/file.png")
tt(x) |> save_tt("path/to/file.pdf")
tt(x) |> save_tt("path/to/file.docx")
tt(x) |> save_tt("path/to/file.html")
tt(x) |> save_tt("path/to/file.tex")
tt(x) |> save_tt("path/to/file.md")

```

`save_tt()` can also return a string with the table in it, for further processing in R. In the first case, the table is printed to console with `cat()`. In the second case, it returns as a single string as an R object.

```

tt(mtcars[1:10, 1:5]) |>
  group_tt(
    i = list(
      "Hello" = 3,
      "World" = 8),
    j = list(
      "Foo" = 2:3,
      "Bar" = 4:5)) |>
  print("markdown")

```

```

+-----+-----+-----+-----+-----+
|      | Foo      | Bar      |      |      |
+-----+-----+-----+-----+-----+
| mpg  | cyl  | disp  | hp   | drat |
+=====+=====+=====+=====+=====+
| 21   | 6    | 160   | 110  | 3.9  |
+-----+-----+-----+-----+-----+
| 21   | 6    | 160   | 110  | 3.9  |
+-----+-----+-----+-----+-----+
| Hello |      |      |      |      |

```

```

+-----+-----+-----+-----+-----+
| 22.8 | 4   | 108 | 93 | 3.85 |
+-----+-----+-----+-----+
| 21.4 | 6   | 258 | 110 | 3.08 |
+-----+-----+-----+-----+
| 18.7 | 8   | 360 | 175 | 3.15 |
+-----+-----+-----+-----+
| 18.1 | 6   | 225 | 105 | 2.76 |
+-----+-----+-----+-----+
| 14.3 | 8   | 360 | 245 | 3.21 |
+-----+-----+-----+-----+
| World |
+-----+-----+-----+-----+
| 24.4 | 4   | 147 | 62 | 3.69 |
+-----+-----+-----+-----+
| 22.8 | 4   | 141 | 95 | 3.92 |
+-----+-----+-----+-----+
| 19.2 | 6   | 168 | 123 | 3.92 |
+-----+-----+-----+-----+

```

```

tt(mtcars[1:10, 1:5]) |>
  group_tt(
    i = list(
      "Hello" = 3,
      "World" = 8),
    j = list(
      "Foo" = 2:3,
      "Bar" = 4:5)) |>
  save_tt("markdown")

```

```
[1] "+-----+-----+-----+-----+-----+\n|           | Foo           | Bar           |\n+-----+-----+-----+-----+-----+"

```

## 1.6 Combination and exploration

Tables can be explored, modified, and combined using many of the usual base R functions:

```

a <- tt(mtcars[1:2, 1:2])
a

```

| mpg | cyl |
|-----|-----|
| 21  | 6   |
| 21  | 6   |

```
dim(a)
```

```
[1] 2 2
```

```
ncol(a)
```

```
[1] 2
```

```
nrow(a)
```

```
[1] 2
```

```
colnames(a)
```

```
[1] "mpg" "cyl"
```

Tables can be combined with the usual `rbind()` function:

```
a <- tt(mtcars[1:3, 1:2], caption = "Combine two tiny tables.")
b <- tt(mtcars[4:5, 8:10])

rbind(a, b)
```

Table 3: Combine two tiny tables.

| mpg  | cyl | vs | am | gear |
|------|-----|----|----|------|
| 21   | 6   |    |    |      |
| 21   | 6   |    |    |      |
| 22.8 | 4   |    |    |      |
|      |     | vs | am | gear |
|      |     | 1  | 0  | 3    |
|      |     | 0  | 0  | 3    |

```
rbind(a, b) |> format_tt(replace = "")
```

Table 4: Combine two tiny tables.

| mpg  | cyl | vs | am | gear |
|------|-----|----|----|------|
| 21   | 6   |    |    |      |
| 21   | 6   |    |    |      |
| 22.8 | 4   |    |    |      |
|      |     | vs | am | gear |
|      |     | 1  | 0  | 3    |
|      |     | 0  | 0  | 3    |

The `rbind2()` S4 method is slightly more flexible than `rbind()`, as it supports arguments `headers` and `use.names`.

Omit y header:

```
rbind2(a, b, headers = FALSE)
```

Table 5: Combine two tiny tables.

| mpg  | cyl | vs | am | gear |
|------|-----|----|----|------|
| 21   | 6   |    |    |      |
| 21   | 6   |    |    |      |
| 22.8 | 4   |    |    |      |
|      |     | 1  | 0  | 3    |
|      |     | 0  | 0  | 3    |

Bind tables by position rather than column names:

```
rbind2(a, b, use_names = FALSE)
```

Table 6: Combine two tiny tables.

| mpg  | cyl | gear |
|------|-----|------|
| 21   | 6   |      |
| 21   | 6   |      |
| 22.8 | 4   |      |
| vs   | am  | gear |
| 1    | 0   | 3    |
| 0    | 0   | 3    |

## 1.7 Renaming columns

As noted above, `tinytable` tries to be standards-compliant, by defining methods for many base R functions. The benefit of this approach is that instead of having to learn a `tinytable`-specific syntax, users can rename columns using all the tools they already know:

```
a <- tt(mtcars[1:2, 1:2])
colnames(a) <- c("a", "b")
a
```

| a  | b |
|----|---|
| 21 | 6 |
| 21 | 6 |

In a pipe-based workflow, we can use the `setNames()` function from base R:

```
mtcars[1:2, 1:2] |>
  tt() |>
  setNames(c("a", "b"))
```

| a  | b |
|----|---|
| 21 | 6 |
| 21 | 6 |

## 2 Formatting

```
library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]
```

### 2.1 Numbers, dates, strings, etc.

The `tt()` function is minimalist; its intended purpose is simply to draw nice tables. Users who want to format numbers, dates, strings, and other variables in different ways should process their data *before* supplying it to the `tt()` table-drawing function. To do so, we can use the `format_tt()` function supplied by the `tinytable`.

In a very simple case—such as printing 2 significant digits of all numeric variables—we can use the `digits` argument of `tt()`:

```
dat <- data.frame(
  w = c(143002.2092, 201399.181, 100188.3883),
  x = c(1.43402, 201.399, 0.134588),
  y = as.Date(sample(1:1000, 3), origin = "1970-01-01"),
  z = c(TRUE, TRUE, FALSE))

tt(dat, digits = 2)
```

| w      | x     | y          | z     |
|--------|-------|------------|-------|
| 143002 | 1.43  | 1971-10-16 | True  |
| 201399 | 201.4 | 1971-04-05 | True  |
| 100188 | 0.13  | 1970-12-20 | False |

We can get more fine-grained control over formatting by calling `format_tt()` after `tt()`, optionally by specifying the columns to format with `j`:

```
tt(dat) |>
  format_tt(
    j = 2:4,
    digits = 1,
    date = "%B %d %Y") |>
```

```
format_tt(
  j = 1,
  digits = 2,
  num_mark_big = " ",
  num_mark_dec = ",",
  num_fmt = "decimal")
```

| w          | x     | y                | z     |
|------------|-------|------------------|-------|
| 143 002,21 | 1.4   | October 16 1971  | True  |
| 201 399,18 | 201.4 | April 05 1971    | True  |
| 100 188,39 | 0.1   | December 20 1970 | False |

We can use a regular expression in `j` to select columns, and the `?sprintf` function to format strings, numbers, and to do [string interpolation](#) (similar to the `glue` package, but using Base R):

```
dat <- data.frame(
  a = c("Burger", "Halloumi", "Tofu", "Beans"),
  b = c(1.43202, 201.399, 0.146188, 0.0031),
  c = c(98938272783457, 7288839482, 29111727, 93945))
tt(dat) |>
  format_tt(j = "a", sprintf = "Food: %s") |>
  format_tt(j = 2, digits = 1) |>
  format_tt(j = "c", digits = 2, num_suffix = TRUE)
```

| a              | b       | c    |
|----------------|---------|------|
| Food: Burger   | 1.432   | 99T  |
| Food: Halloumi | 201.399 | 7.3B |
| Food: Tofu     | 0.146   | 29M  |
| Food: Beans    | 0.003   | 94K  |

Finally, if you like the `format_tt()` interface, you can use it directly with numbers, vectors, or data frames:

```
format_tt(pi, digits = 1)
```

```
[1] "3"
```



```
format_tt(dat, digits = 1, num_suffix = TRUE)
```

```
      a      b      c
1 Burger    1 99T
2 Halloumi 201 7B
3 Tofu    0.1 29M
4 Beans 0.003 94K
```

## 2.2 Significant digits and decimals

By default, `format_tt()` formats numbers to ensure that the smallest value in a vector (column) has at least a certain number of significant digits. For example,

```
k <- data.frame(x = c(0.000123456789, 12.4356789))
tt(k, digits = 2)
```

```
-----
x
-----
0.00012
12.43568
-----
```

We can alter this behavior to ensure to round significant digits on a per-cell basis, using the `num_fmt` argument in `format_tt()`:

```
tt(k) |> format_tt(digits = 2, num_fmt = "significant_cell")
```

```
-----
x
-----
0.00012
12
-----
```

The numeric formatting options in `format_tt()` can also be controlled using global options:

```
options("tinytable_tt_digits" = 2)
options("tinytable_format_num_fmt" = "significant_cell")
tt(k)
```

$$\frac{x}{0.00012} = 12$$

## 2.3 Math

To insert LaTeX-style mathematical expressions in a `tinytable`, we enclose the expression in dollar signs: `$. . . $`. Note that you must double backslashes in mathematical expressions in R strings.

In LaTeX, expression enclosed between `$$` will automatically rendered as a mathematical expression.

In HTML, users must first load the MathJax JavaScript library to render math. This can be done in two ways. First, one can use a global option. This will insert MathJax scripts alongside every table, which is convenient, but could enter in conflict with other scripts if the user (or notebook) has already inserted MathJax code:

```
options(tinytable_html_mathjax = TRUE)
```

Alternatively, users can load MathJax explicitly in their HTML file. In a Quarto notebook, this can be done by using a code chunk like this:

```
```{=html}
<script id="MathJax-script" async src="https://cdn.jsdelivr.net/npm/mathjax@3/es5/tex-mml-ch
</script>
MathJax = {
  tex: {
    inlineMath: [['$', '$'], ['\\(', '\\)']]
  },
  svg: {
    fontCache: 'global'
  }
};
</script>
```
```

Then, we can do:

```
dat <- data.frame(Math = c(
  "$x^2 + y^2 = z^2$",
  "$\\frac{1}{2}$"
))
tt(dat) |> style_tt(j = 1, align = "c")
```

$$\begin{array}{c} \hline \text{Math} \\ \hline x^2 + y^2 = z^2 \\ \frac{1}{2} \\ \hline \end{array}$$

To avoid inserting  $\$...\$$  in every cell manually, we can use the `math` argument of `format_tt()`:

```
options(tinytable_html_mathjax = TRUE)

dat <- data.frame("y^2 = e^x" = c(-2, -pi), check.names = FALSE)

tt(dat, digits = 3) |> format_tt(math = TRUE)
```

$$\begin{array}{c} \hline y^2 = e^x \\ \hline -2 \\ -3.14 \\ \hline \end{array}$$

In LaTeX (PDF), you can also use the `mode` inner setting from `tabularray` to render math in tables without delimiters (see Section 7.2 for details on `tabularray`):

```
dat <- data.frame(Math = c("x^2 + y^2 = z^2", "\\frac{1}{2}"))
tt(dat) |>
  style_tt(j = 1, align = "c", tabularray_inner = "column{1}={mode=math},")
```

$$\begin{array}{c} \hline \textit{Math} \\ \hline x^2 + y^2 = z^2 \\ \frac{1}{2} \\ \hline \end{array}$$

## 2.4 Replacement

Missing values can be replaced by a custom string using the `replace` argument (default `""`):

```
tab <- data.frame(a = c(NA, 1, 2), b = c(3, NA, 5))  
tt(tab)
```

| a  | b  |
|----|----|
| NA | 3  |
| 1  | NA |
| 2  | 5  |

```
tt(tab) |> format_tt()
```

| a | b |
|---|---|
|   | 3 |
| 1 |   |
| 2 | 5 |

```
tt(tab) |> format_tt(replace = "-")
```

| a | b |
|---|---|
| - | 3 |
| 1 | - |
| 2 | 5 |

We can also specify multiple value replacements at once using a named list of vectors:

```
tmp <- data.frame(x = 1:5, y = c(pi, NA, NaN, -Inf, Inf))  
dict <- list("-" = c(NA, NaN), "-∞" = -Inf, "∞" = Inf)  
tt(tmp) |> format_tt(replace = dict, digits = 2)
```

| x | y         |
|---|-----------|
| 1 | 3.1       |
| 2 | -         |
| 3 | -         |
| 4 | $-\infty$ |
| 5 | $\infty$  |

## 2.5 Escape special characters

LaTeX and HTML use special characters to indicate strings which should be interpreted rather than displayed as text. For example, including underscores or dollar signs in LaTeX can cause compilation errors in some documents. To display those special characters, we need to substitute or escape them with backslashes, depending on the output format. The `escape` argument of `format_tt()` can be used to do this automatically:

```
dat <- data.frame(
  "LaTeX" = c("Dollars $", "Percent %", "Underscore _"),
  "HTML" = c("<br>", "<sup>4</sup>", "<emph>blah</emph>")
)

tt(dat) |> format_tt(escape = TRUE)
```

| LaTeX        | HTML              |
|--------------|-------------------|
| Dollars \$   | <br>              |
| Percent %    | <sup>4</sup>      |
| Underscore _ | <emph>blah</emph> |

When applied to a `tt()` table, `format_tt()` will determine the type of escaping to do automatically. When applied to a string or vector, we must specify the type of escaping to apply:

```
format_tt("_ Dollars $", escape = "latex")
```

```
[1] "\\_ Dollars \\$"
```

## 2.6 Markdown

Markdown can be rendered in cells by using the `markdown` argument of the `format_tt()` function (note: this requires installing the `markdown` as an optional dependency).

```
dat <- data.frame( markdown = c(
  "This is italic text.",
  "This sentence ends with a superscript.2"
)

tt(dat) |>
  format_tt(j = 1, markdown = TRUE) |>
  style_tt(j = 1, align = "c")
```

| markdown  |
|---|
| This is <i>italic</i> text.                         |
| This sentence ends with a superscript. <sup>2</sup> |

Markdown syntax can be particularly useful when formatting URLs in a table:

```
dat <- data.frame(
  `Package (link)` = c(
    "[`marginaleffects`](https://www.marginaleffects.com/)",
    "[`modelsummary`](https://www.modelsummary.com/)",
    "[`tinytable`](https://vincentarelbundock.github.io/tinytable/)",
    "[`countrycode`](https://vincentarelbundock.github.io/countrycode/)",
    "[`WDI`](https://vincentarelbundock.github.io/WDI/)",
    "[`softbib`](https://vincentarelbundock.github.io/softbib/)",
    "[`tinysnapshot`](https://vincentarelbundock.github.io/tinysnapshot/)",
    "[`altdoc`](https://etiennebacher.github.io/altdoc/)",
    "[`tinyplot`](https://grantmcdermott.com/tinyplot/)",
    "[`parameters`](https://easystats.github.io/parameters/)",
    "[`insight`](https://easystats.github.io/insight/)"
  ),
  Purpose = c(
    "Interpreting statistical models",
    "Data and model summaries",
    "Draw beautiful tables easily",
    "Convert country codes and names",
    "Download data from the World Bank",
```

```

"Software bibliographies in R",
"Snapshots for unit tests using `tinytest`",
"Create documentation website for R packages",
"Extension of base R plot functions",
"Extract from model objects",
"Extract information from model objects"
),
check.names = FALSE
)

tt(dat) |> format_tt(j = 1, markdown = TRUE)

```

Table 7: Vincent sometimes contributes to these R packages.

| Package (link)                  | Purpose                                     |
|---------------------------------|---|
| <a href="#">marginaleffects</a> | Interpreting statistical models             |
| <a href="#">modelsummary</a>    | Data and model summaries                    |
| <a href="#">tinytable</a>       | Draw beautiful tables easily                |
| <a href="#">countrycode</a>     | Convert country codes and names             |
| <a href="#">WDI</a>             | Download data from the World Bank           |
| <a href="#">softbib</a>         | Software bibliographies in R                |
| <a href="#">tinysnapshot</a>    | Snapshots for unit tests using ‘tinytest’   |
| <a href="#">altdoc</a>          | Create documentation website for R packages |
| <a href="#">tinyplot</a>        | Extension of base R plot functions          |
| <a href="#">parameters</a>      | Extract from model objects                  |
| <a href="#">insight</a>         | Extract information from model objects      |

## 2.7 Custom functions

On top of the built-in features of `format_tt`, a custom formatting function can be specified via the `fn` argument. The `fn` argument takes a function that accepts a single vector and returns a string (or something that coerces to a string like a number).

```

tt(x) |>
  format_tt(j = "mpg", fn = function(x) paste0(x, " mpg")) |>
  format_tt(j = "drat", fn = \(x) signif(x, 2))

```

| mpg      | cyl | disp | hp  | drat |
|----------|-----|------|-----|------|
| 21 mpg   | 6   | 160  | 110 | 3.9  |
| 21 mpg   | 6   | 160  | 110 | 3.9  |
| 22.8 mpg | 4   | 108  | 93  | 3.8  |
| 21.4 mpg | 6   | 258  | 110 | 3.1  |

For example, the [scales package](#) which is used internally by `ggplot2` provides a bunch of useful tools for formatting (e.g. dates, numbers, percents, logs, currencies, etc.). The `label_*()` functions can be passed to the `fn` argument.

Note that we call `format_tt(escape = TRUE)` at the end of the pipeline because the column names and cells include characters that need to be escaped in LaTeX: `_`, `%`, and `$`. This last call is superfluous in HTML.

```
thumbdrives <- data.frame(
  date_lookup = as.Date(c("2024-01-15", "2024-01-18", "2024-01-14", "2024-01-16")),
  price = c(18.49, 19.99, 24.99, 24.99),
  price_rank = c(1, 2, 3, 3),
  memory = c(16e9, 12e9, 10e9, 8e9),
  speed_benchmark = c(0.6, 0.73, 0.82, 0.99)
)

tt(thumbdrives) |>
  format_tt(j = 1, fn = scales::label_date("%e %b", locale = "fr")) |>
  format_tt(j = 2, fn = scales::label_currency()) |>
  format_tt(j = 3, fn = scales::label_ordinal()) |>
  format_tt(j = 4, fn = scales::label_bytes()) |>
  format_tt(j = 5, fn = scales::label_percent()) |>
  format_tt(escape = TRUE)
```

| date_lookup | price   | price_rank | memory | speed_benchmark |
|-------------|---------|------------|--------|-----------------|
| 2024-01-15  | \$18.49 | 1st        | 16 GB  | 60%             |
| 2024-01-18  | \$19.99 | 2nd        | 12 GB  | 73%             |
| 2024-01-14  | \$24.99 | 3rd        | 10 GB  | 82%             |
| 2024-01-16  | \$24.99 | 3rd        | 8 GB   | 99%             |



### 3 Style

The main styling function for the `tinytable` package is `style_tt()`. Via this function, you can access three main interfaces to customize tables:

1. A general interface to frequently used style choices which works for both HTML and LaTeX (PDF): colors, font style and size, row and column spans, etc. This is accessed through several distinct arguments in the `style_tt()` function, such as `italic`, `color`, etc.
2. A specialized interface which allows users to use the [powerful `tabularray` package](#) to customize LaTeX tables. This is accessed by passing `tabularray` settings as strings to the `tabularray_inner` and `tabularray_outer` arguments of `style_tt()`.
3. A specialized interface which allows users to use the [powerful `Bootstrap framework`](#) to customize HTML tables. This is accessed by passing CSS declarations and rules to the `bootstrap_css` and `bootstrap_css_rule` arguments of `style_tt()`.

These functions can be used to customize rows, columns, or individual cells. They control many features, including:

- Text color
- Background color
- Widths
- Heights
- Alignment
- Text Wrapping
- Column and Row Spacing
- Cell Merging
- Multi-row or column spans
- Border Styling
- Font Styling: size, underline, italic, bold, strikethrough, etc.
- Header Customization

The `style_*()` functions can modify individual cells, or entire columns and rows. The portion of the table that is styled is determined by the `i` (rows) and `j` (columns) arguments.

```
library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]
```

### 3.1 Cells, rows, columns

To style individual cells, we use the `style_cell()` function. The first two arguments—`i` and `j`—identify the cells of interest, by row and column numbers respectively. To style a cell in the 2nd row and 3rd column, we can do:

```
tt(x) |>
  style_tt(
    i = 2,
    j = 3,
    background = "black",
    color = "white")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

The `i` and `j` accept vectors of integers to modify several cells at once:

```
tt(x) |>
  style_tt(
    i = 2:3,
    j = c(1, 3, 4),
    italic = TRUE,
    color = "orange")
```

| mpg         | cyl | disp       | hp         | drat |
|-------------|-----|------------|------------|------|
| 21          | 6   | 160        | 110        | 3.9  |
| <i>21</i>   | 6   | <i>160</i> | <i>110</i> | 3.9  |
| <i>22.8</i> | 4   | <i>108</i> | <i>93</i>  | 3.85 |
| 21.4        | 6   | 258        | 110        | 3.08 |

We can style all cells in a table by omitting both the `i` and `j` arguments:

```
tt(x) |> style_tt(color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

We can style entire rows by omitting the `j` argument:

```
tt(x) |> style_tt(i = 1:2, color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

We can style entire columns by omitting the `i` argument:

```
tt(x) |> style_tt(j = c(2, 4), bold = TRUE)
```

| mpg  | <b>cyl</b> | disp | <b>hp</b>  | drat |
|------|------------|------|------------|------|
| 21   | <b>6</b>   | 160  | <b>110</b> | 3.9  |
| 21   | <b>6</b>   | 160  | <b>110</b> | 3.9  |
| 22.8 | <b>4</b>   | 108  | <b>93</b>  | 3.85 |
| 21.4 | <b>6</b>   | 258  | <b>110</b> | 3.08 |

The `j` argument accepts integer vectors, character vectors, but also a string with a Perl-style regular expression, which makes it easier to select columns by name:

```
tt(x) |> style_tt(j = c("mpg", "drat"), color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
tt(x) |> style_tt(j = "mpg|drat", color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

Here we use a “negative lookahead” to exclude certain columns:

```
tt(x) |> style_tt(j = "^(?!drat|mpg)", color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

Of course, we can also call the `style_tt()` function several times to apply different styles to different parts of the table:

```
tt(x) |>
  style_tt(i = 1, j = 1:2, color = "orange") |>
  style_tt(i = 1, j = 3:4, color = "green")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

## 3.2 Colors

The `color` and `background` arguments in the `style_tt()` function are used for specifying the text color and the background color for cells of a table created by the `tt()` function. This argument plays a crucial role in enhancing the visual appeal and readability of the table, whether it's rendered in LaTeX or HTML format. The way we specify colors differs slightly between the two formats:

For HTML Output:

- Hex Codes: You can specify colors using hexadecimal codes, which consist of a # followed by 6 characters (e.g., #CC79A7). This allows for a wide range of colors.
- Keywords: There's also the option to use color keywords for convenience. The supported keywords are basic color names like `black`, `red`, `blue`, etc.

For LaTeX Output:

- Hexadecimal Codes: Similar to HTML, you can use hexadecimal codes. However, in LaTeX, you need to include these codes as strings (e.g., "#CC79A7").
- Keywords: LaTeX supports a different set of color keywords, which include standard colors like `black`, `red`, `blue`, as well as additional ones like `cyan`, `darkgray`, `lightgray`, etc.
- Color Blending: An advanced feature in LaTeX is color blending, which can be achieved using the `xcolor` package. You can blend colors by specifying ratios (e.g., `white!80!blue` or `green!20!red`).
- Luminance Levels: [The `ninecolors` package in LaTeX](#) offers colors with predefined luminance levels, allowing for more nuanced color choices (e.g., "azure4", "magenta8").

Note that the keywords used in LaTeX and HTML are slightly different.

```
tt(x) |> style_tt(i = 1:4, j = 1, color = "#FF5733")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

Note that when using Hex codes in a LaTeX table, we need extra declarations in the LaTeX preamble. See `?tt` for details.

### 3.3 Alignment

To align columns, we use a single character, or a string where each letter represents a column:

```
dat <- data.frame(
  a = c("a", "aa", "aaa"),
  b = c("b", "bb", "bbb"),
  c = c("c", "cc", "ccc"))

tt(dat) |> style_tt(j = 1:3, align = "c")
```

| a   | b   | c   |
|-----|-----|-----|
| a   | b   | c   |
| aa  | bb  | cc  |
| aaa | bbb | ccc |

```
tt(dat) |> style_tt(j = 1:3, align = "lcr")
```

| a   | b   | c   |
|-----|-----|-----|
| a   | b   | c   |
| aa  | bb  | cc  |
| aaa | bbb | ccc |

In LaTeX documents (only), we can use decimal-alignment:

```
z <- data.frame(pi = c(pi * 100, pi * 1000, pi * 10000, pi * 100000))
tt(z) |>
  format_tt(j = 1, digits = 8, num_fmt = "significant_cell") |>
  style_tt(j = 1, align = "d")
```

| pi         |
|------------|
| 314.159 27 |
| 3141.5927  |
| 31 415.927 |
| 314 159.27 |

### 3.4 Font size

The font size is specified in em units.

```
tt(x) |> style_tt(j = "mpg|hp|qsec", fontsize = 1.5)
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

### 3.5 Spanning cells (merging cells)

Sometimes, it can be useful to make a cell stretch across multiple columns or rows, for example when we want to insert a label. To achieve this, we can use the `colspan` argument. Here, we make the 2nd cell of the 2nd row stretch across three columns and two rows:

```
tt(x) |> style_tt(
  i = 2, j = 2,
  colspan = 3,
  rowspan = 2,
  align = "c",
  alignv = "m",
```

```
color = "white",
background = "black",
bold = TRUE)
```

| mpg  | cyl      | disp | hp  | drat |
|------|----------|------|-----|------|
| 21   | 6        | 160  | 110 | 3.9  |
| 21   | <b>6</b> |      |     | 3.9  |
| 22.8 |          |      |     | 3.85 |
| 21.4 | 6        | 258  | 110 | 3.08 |

Here is the original table for comparison:

```
tt(x)
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

Spanning cells can be particularly useful when we want to suppress redundant labels:

```
tab <- aggregate(mpg ~ cyl + am, FUN = mean, data = mtcars)
tab <- tab[order(tab$cyl, tab$am),]
tab
```

```
  cyl am      mpg
1   4  0 22.90000
4   4  1 28.07500
2   6  0 19.12500
5   6  1 20.56667
3   8  0 15.05000
6   8  1 15.40000
```



```
tt(tab, digits = 2) |>
  style_tt(i = c(1, 3, 5), j = 1, rowspan = 2, alignv = "t")
```

| cyl | am | mpg |
|-----|----|-----|
| 4   | 0  | 23  |
|     | 1  | 28  |
| 6   | 0  | 19  |
|     | 1  | 21  |
| 8   | 0  | 15  |
|     | 1  | 15  |

The `rowspan` feature is also useful to create multi-row labels. For example, in this table there is a linebreak, but all the text fits in a single cell:

```
tab <- data.frame(Letters = c("A<br>B", ""), Numbers = c("First", "Second"))
tt(tab) |>
  style_tt(bootstrap_class = "table-bordered")
```

| Letters | Numbers |
|---------|---------|
| A<br>B  | First   |
|         | Second  |

Now, we use `colspan` to ensure that that cells in the first column take up less space and are combined into one:

```
tt(tab) |>
  style_tt(bootstrap_class = "table-bordered") |>
  style_tt(1, 1, rowspan = 2)
```

| Letters | Numbers |
|---------|---------|
| A<br>B  | First   |
|         | Second  |

### 3.6 Headers

The header can be omitted from the table by deleting the column names in the `x` data frame:

```
k <- x
colnames(k) <- NULL
tt(k)
```

|      |   |     |     |      |
|------|---|-----|-----|------|
| 21.0 | 6 | 160 | 110 | 3.90 |
| 21.0 | 6 | 160 | 110 | 3.90 |
| 22.8 | 4 | 108 | 93  | 3.85 |
| 21.4 | 6 | 258 | 110 | 3.08 |

The first is row 0, and higher level headers (ex: column spanning labels) have negative indices like -1. They can be styled as expected:

```
tt(x) |> style_tt(i = 0, color = "white", background = "black")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

When styling columns without specifying `i`, the headers are styled in accordance with the rest of the column:

```
tt(x) |> style_tt(j = 2:3, color = "white", background = "black")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

### 3.7 Conditional styling

We can use the standard `which` function from Base R to create indices and apply conditional styling on rows. And we can use a regular expression in `j` to apply conditional styling on columns:

```
k <- mtcars[1:10, c("mpg", "am", "vs")]  
  
tt(k) |>  
  style_tt(  
    i = which(k$am == k$vs),  
    background = "teal",  
    color = "white")
```

| mpg  | am | vs |
|------|----|----|
| 21   | 1  | 0  |
| 21   | 1  | 0  |
| 22.8 | 1  | 1  |
| 21.4 | 0  | 1  |
| 18.7 | 0  | 0  |
| 18.1 | 0  | 1  |
| 14.3 | 0  | 0  |
| 24.4 | 0  | 1  |
| 22.8 | 0  | 1  |
| 19.2 | 0  | 1  |

In versions *above* 0.4.0 of `tinytable`, users can also supply a logical matrix of the same size as `x` to indicate which cell should be styled. For example, we can change the colors of certain entries in a correlation matrix as follows:

```
cormat <- data.frame(cor(mtcars[1:5]))  
tt(cormat, digits = 2) |>  
  style_tt(i = abs(cormat) > .8, background = "black", color = "white")
```

| mpg   | cyl   | disp  | hp    | drat  |
|-------|-------|-------|-------|-------|
| 1     | -0.85 | -0.85 | -0.78 | 0.68  |
| -0.85 | 1     | 0.9   | 0.83  | -0.7  |
| -0.85 | 0.9   | 1     | 0.79  | -0.71 |
| -0.78 | 0.83  | 0.79  | 1     | -0.45 |
| 0.68  | -0.7  | -0.71 | -0.45 | 1     |

### 3.8 Vectorized styling (heatmaps)

The `color`, `background`, and `fontsize` arguments are vectorized. This allows easy specification of different colors in a single call:

```
tt(x) |>
  style_tt(
    i = 1:4,
    color = c("red", "blue", "green", "orange"))
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

When using a single value for a vectorized argument, it gets applied to all values:

```
tt(x) |>
  style_tt(
    j = 2:3,
    color = c("orange", "green"),
    background = "black")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

We can also produce more complex heatmap-like tables to illustrate different font sizes in em units:

```
# font sizes
fs <- seq(.1, 2, length.out = 20)

# headless table
k <- data.frame(matrix(fs, ncol = 5))
colnames(k) <- NULL

# colors
bg <- hcl.colors(20, "Inferno")
fg <- ifelse(as.matrix(k) < 1.7, tail(bg, 1), head(bg, 1))

# table
tt(k, width = .7, theme = "void") |>
  style_tt(j = 1:5, align = "ccccc") |>
  style_tt(
    i = 1:4,
    j = 1:5,
    color = fg,
    background = bg,
    fontsize = fs)
```

|     |     |     |     |     |
|-----|-----|-----|-----|-----|
| 0.1 | 0.5 | 0.9 | 1.3 | 1.7 |
| 0.2 | 0.6 | 1.0 | 1.4 | 1.8 |
| 0.3 | 0.7 | 1.1 | 1.5 | 1.9 |
| 0.4 | 0.8 | 1.2 | 1.6 | 2.0 |

### 3.9 Lines (borders)

The `style_tt` function allows us to customize the borders that surround each cell of a table, as well horizontal and vertical rules. To control these lines, we use the `line`, `line_width`, and `line_color` arguments. Here's a brief overview of each of these arguments:

- **line**: This argument specifies where solid lines should be drawn. It is a string that can consist of the following characters:
  - "t": Draw a line at the top of the cell, row, or column.
  - "b": Draw a line at the bottom of the cell, row, or column.

- "l": Draw a line at the left side of the cell, row, or column.
  - "r": Draw a line at the right side of the cell, row, or column.
  - You can combine these characters to draw lines on multiple sides, such as "tblr" to draw lines at the top, bottom, and left sides of a cell.
- `line_width`: This argument controls the width of the solid lines in em units (default: 0.1 em). You can adjust this value to make the lines thicker or thinner.
  - `line_color`: Specifies the color of the solid lines. You can use color names, hexadecimal codes, or other color specifications to define the line color.

Here is an example where we draw lines around every border ("t", "b", "l", and "r") of specified cells.

```
tt(x, theme = "void") |>
  style_tt(
    i = 0:3,
    j = 1:3,
    line = "tblr",
    line_width = 0.4,
    line_color = "orange")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

And here is an example with horizontal rules:

```
tt(x, theme = "void") |>
  style_tt(i = 0, line = "t", line_color = "orange", line_width = 0.4) |>
  style_tt(i = 0, line = "b", line_color = "purple", line_width = 0.2) |>
  style_tt(i = 4, line = "b", line_color = "orange", line_width = 0.4)
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
dat <- data.frame(1:2, 3:4, 5:6, 7:8)
colnames(dat) <- NULL

tt(dat, theme = "void") |>
  style_tt(
    line = "tblr", line_color = "white", line_width = 0.5,
    background = "blue", color = "white")
```

|   |   |   |   |
|---|---|---|---|
| 1 | 3 | 5 | 7 |
| 2 | 4 | 6 | 8 |

### 3.10 Cell padding (height and width)

There is no argument in `style_tt()` to control the padding of cells. Thankfully, this is easy to control using CSS and `tabularray` options:

```
tt(x) |> style_tt(
  bootstrap_css = "padding-right: .2em; padding-top: 2em;",
  tabularray_inner = "rowsep={2em}, colsep = {.2em}"
)
```

---

| mpg | cyl | disp | hp | drat |
|-----|-----|------|----|------|
|-----|-----|------|----|------|

---

|    |   |     |     |     |
|----|---|-----|-----|-----|
| 21 | 6 | 160 | 110 | 3.9 |
|----|---|-----|-----|-----|

|    |   |     |     |     |
|----|---|-----|-----|-----|
| 21 | 6 | 160 | 110 | 3.9 |
|----|---|-----|-----|-----|

|      |   |     |    |      |
|------|---|-----|----|------|
| 22.8 | 4 | 108 | 93 | 3.85 |
|------|---|-----|----|------|

|      |   |     |     |      |
|------|---|-----|-----|------|
| 21.4 | 6 | 258 | 110 | 3.08 |
|------|---|-----|-----|------|

---

### 3.11 Markdown and Word

Styling for Markdown and Word tables is more limited than for the other formats. In particular:

- The only supported arguments are: **bold**, *italic*, and ~~strikeout~~.
- Headers inserted by `group_tt()` cannot be styled using the `style_tt()` function.

These limitations are due to the fact that there is no markdown syntax for the other options (ex: colors and background), and that we create Word documents by converting a markdown table to .docx via the Pandoc software.

One workaround is to style the group headers directly in their definition by using markdown syntax:

```
mtcars[1:4, 1:4] |>
  tt() |>
  group_tt(i = list("*Hello*" = 1, "__World__" = 3)) |>
  print("markdown")
```



```

+-----+-----+-----+-----+
| mpg  | cyl  | disp | hp  |
+=====+=====+=====+=====+
| *Hello*                |
+-----+-----+-----+-----+
| 21   | 6    | 160  | 110 |
+-----+-----+-----+-----+
| 21   | 6    | 160  | 110 |
+-----+-----+-----+-----+
| __World__              |
+-----+-----+-----+-----+
| 22.8 | 4    | 108  | 93  |
+-----+-----+-----+-----+
| 21.4 | 6    | 258  | 110 |
+-----+-----+-----+-----+

```

## 4 Groups and labels

```

library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]

```

The `group_tt()` function can label groups of rows (*i*) or columns (*j*).

### 4.1 Rows

The *i* argument accepts a named list of integers. The numbers identify the positions where row group labels are to be inserted. The names includes the text that should be inserted:

```

dat <- mtcars[1:9, 1:8]

tt(dat) |>
  group_tt(i = list(
    "I like (fake) hamburgers" = 3,
    "She prefers halloumi" = 4,
    "They love tofu" = 7))

```

| mpg                      | cyl | disp | hp  | drat | wt   | qsec | vs |
|--------------------------|-----|------|-----|------|------|------|----|
| 21                       | 6   | 160  | 110 | 3.9  | 2.62 | 16.5 | 0  |
| 21                       | 6   | 160  | 110 | 3.9  | 2.88 | 17   | 0  |
| I like (fake) hamburgers |     |      |     |      |      |      |    |
| 22.8                     | 4   | 108  | 93  | 3.85 | 2.32 | 18.6 | 1  |
| She prefers halloumi     |     |      |     |      |      |      |    |
| 21.4                     | 6   | 258  | 110 | 3.08 | 3.21 | 19.4 | 1  |
| 18.7                     | 8   | 360  | 175 | 3.15 | 3.44 | 17   | 0  |
| 18.1                     | 6   | 225  | 105 | 2.76 | 3.46 | 20.2 | 1  |
| They love tofu           |     |      |     |      |      |      |    |
| 14.3                     | 8   | 360  | 245 | 3.21 | 3.57 | 15.8 | 0  |
| 24.4                     | 4   | 147  | 62  | 3.69 | 3.19 | 20   | 1  |
| 22.8                     | 4   | 141  | 95  | 3.92 | 3.15 | 22.9 | 1  |

The numbers in the `i` list indicate that a label must be inserted at position `#` in the original table (without row groups). For example,

```
tt(head(iris)) |>
  group_tt(i = list("After 1" = 2, "After 2" = 3, "After 3" = 4, "After 5" = 6))
```

| Sepal.Length | Sepal.Width | Petal.Length | Petal.Width | Species |
|--------------|-------------|--------------|-------------|---------|
| 5.1          | 3.5         | 1.4          | 0.2         | setosa  |
| After 1      |             |              |             |         |
| 4.9          | 3           | 1.4          | 0.2         | setosa  |
| After 2      |             |              |             |         |
| 4.7          | 3.2         | 1.3          | 0.2         | setosa  |
| After 3      |             |              |             |         |
| 4.6          | 3.1         | 1.5          | 0.2         | setosa  |
| 5            | 3.6         | 1.4          | 0.2         | setosa  |
| After 5      |             |              |             |         |
| 5.4          | 3.9         | 1.7          | 0.4         | setosa  |

```
tt(head(iris)) |>
  group_tt(i = list("After 1a" = 2, "After 1b" = 2, "After 5" = 6))
```

| Sepal.Length | Sepal.Width | Petal.Length | Petal.Width | Species |
|--------------|-------------|--------------|-------------|---------|
| 5.1          | 3.5         | 1.4          | 0.2         | setosa  |
| After 1a     |             |              |             |         |
| After 1b     |             |              |             |         |
| 4.9          | 3           | 1.4          | 0.2         | setosa  |
| 4.7          | 3.2         | 1.3          | 0.2         | setosa  |
| 4.6          | 3.1         | 1.5          | 0.2         | setosa  |
| 5            | 3.6         | 1.4          | 0.2         | setosa  |
| After 5      |             |              |             |         |
| 5.4          | 3.9         | 1.7          | 0.4         | setosa  |

```
tt(head(iris)) |>
  group_tt(i = list("After 0" = 1))
```

| Sepal.Length | Sepal.Width | Petal.Length | Petal.Width | Species |
|--------------|-------------|--------------|-------------|---------|
| After 0      |             |              |             |         |
| 5.1          | 3.5         | 1.4          | 0.2         | setosa  |
| 4.9          | 3           | 1.4          | 0.2         | setosa  |
| 4.7          | 3.2         | 1.3          | 0.2         | setosa  |
| 4.6          | 3.1         | 1.5          | 0.2         | setosa  |
| 5            | 3.6         | 1.4          | 0.2         | setosa  |
| 5.4          | 3.9         | 1.7          | 0.4         | setosa  |

We can style group rows in the same way as regular rows:

```
tt(dat) |>
  group_tt(
    i = list(
      "I like (fake) hamburgers" = 3,
      "She prefers halloumi" = 4,
      "They love tofu" = 7)) |>
```

```

style_tt(
  i = c(3, 5, 9),
  align = "c",
  color = "white",
  background = "gray",
  bold = TRUE)

```

| mpg                      | cyl | disp | hp  | drat | wt   | qsec | vs |
|--------------------------|-----|------|-----|------|------|------|----|
| 21                       | 6   | 160  | 110 | 3.9  | 2.62 | 16.5 | 0  |
| 21                       | 6   | 160  | 110 | 3.9  | 2.88 | 17   | 0  |
| I like (fake) hamburgers |     |      |     |      |      |      |    |
| 22.8                     | 4   | 108  | 93  | 3.85 | 2.32 | 18.6 | 1  |
| She prefers halloumi     |     |      |     |      |      |      |    |
| 21.4                     | 6   | 258  | 110 | 3.08 | 3.21 | 19.4 | 1  |
| 18.7                     | 8   | 360  | 175 | 3.15 | 3.44 | 17   | 0  |
| 18.1                     | 6   | 225  | 105 | 2.76 | 3.46 | 20.2 | 1  |
| They love tofu           |     |      |     |      |      |      |    |
| 14.3                     | 8   | 360  | 245 | 3.21 | 3.57 | 15.8 | 0  |
| 24.4                     | 4   | 147  | 62  | 3.69 | 3.19 | 20   | 1  |
| 22.8                     | 4   | 141  | 95  | 3.92 | 3.15 | 22.9 | 1  |

#### 4.1.1 Automatic row groups

We can use the `group_tt()` function to group rows and label them using spanners (almost) automatically. For example,

```

# subset and sort data
df <- mtcars |> head(10) |> sort_by(~ am)

# identify row indices
indices <- tapply(1:nrow(df), df$am, \(x) x[1], simplify = FALSE)

# draw table
tt(df) |> group_tt(i = indices)

```

| mpg  | cyl | disp | hp  | drat | wt   | qsec | vs | am | gear | carb |
|------|-----|------|-----|------|------|------|----|----|------|------|
| 0    |     |      |     |      |      |      |    |    |      |      |
| 21.4 | 6   | 258  | 110 | 3.08 | 3.21 | 19.4 | 1  | 0  | 3    | 1    |
| 18.7 | 8   | 360  | 175 | 3.15 | 3.44 | 17   | 0  | 0  | 3    | 2    |
| 18.1 | 6   | 225  | 105 | 2.76 | 3.46 | 20.2 | 1  | 0  | 3    | 1    |
| 14.3 | 8   | 360  | 245 | 3.21 | 3.57 | 15.8 | 0  | 0  | 3    | 4    |
| 24.4 | 4   | 147  | 62  | 3.69 | 3.19 | 20   | 1  | 0  | 4    | 2    |
| 22.8 | 4   | 141  | 95  | 3.92 | 3.15 | 22.9 | 1  | 0  | 4    | 2    |
| 19.2 | 6   | 168  | 123 | 3.92 | 3.44 | 18.3 | 1  | 0  | 4    | 4    |
| 1    |     |      |     |      |      |      |    |    |      |      |
| 21   | 6   | 160  | 110 | 3.9  | 2.62 | 16.5 | 0  | 1  | 4    | 4    |
| 21   | 6   | 160  | 110 | 3.9  | 2.88 | 17   | 0  | 1  | 4    | 4    |
| 22.8 | 4   | 108  | 93  | 3.85 | 2.32 | 18.6 | 1  | 1  | 4    | 1    |

## 4.2 Columns

The syntax for column groups is very similar, but we use the `j` argument instead. The named list specifies the labels to appear in column-spanning labels, and the values must be a vector of consecutive and non-overlapping integers that indicate which columns are associated to which labels:

```
tt(dat) |>
  group_tt(
    j = list(
      "Hamburgers" = 1:3,
      "Halloumi" = 4:5,
      "Tofu" = 7))
```

| Hamburgers |     |      | Halloumi |      | Tofu |      |    |
|------------|-----|------|----------|------|------|------|----|
| mpg        | cyl | disp | hp       | drat | wt   | qsec | vs |
| 21         | 6   | 160  | 110      | 3.9  | 2.62 | 16.5 | 0  |
| 21         | 6   | 160  | 110      | 3.9  | 2.88 | 17   | 0  |
| 22.8       | 4   | 108  | 93       | 3.85 | 2.32 | 18.6 | 1  |
| 21.4       | 6   | 258  | 110      | 3.08 | 3.21 | 19.4 | 1  |
| 18.7       | 8   | 360  | 175      | 3.15 | 3.44 | 17   | 0  |
| 18.1       | 6   | 225  | 105      | 2.76 | 3.46 | 20.2 | 1  |
| 14.3       | 8   | 360  | 245      | 3.21 | 3.57 | 15.8 | 0  |
| 24.4       | 4   | 147  | 62       | 3.69 | 3.19 | 20   | 1  |
| 22.8       | 4   | 141  | 95       | 3.92 | 3.15 | 22.9 | 1  |

Here is a table with both row and column headers, as well as some styling:

```
dat <- mtcars[1:9, 1:8]
tt(dat) |>
  group_tt(
    i = list("I like (fake) hamburgers" = 3,
             "She prefers halloumi" = 4,
             "They love tofu" = 7),
    j = list("Hamburgers" = 1:3,
             "Halloumi" = 4:5,
             "Tofu" = 7)) |>
  style_tt(
    i = c(3, 5, 9),
    align = "c",
    background = "teal",
    color = "white") |>
  style_tt(i = -1, color = "teal")
```

| Hamburgers               |     |      | Halloumi |      | Tofu |      |    | vs |
|--------------------------|-----|------|----------|------|------|------|----|----|
| mpg                      | cyl | disp | hp       | drat | wt   | qsec | vs |    |
| 21                       | 6   | 160  | 110      | 3.9  | 2.62 | 16.5 | 0  |    |
| 21                       | 6   | 160  | 110      | 3.9  | 2.88 | 17   | 0  |    |
| I like (fake) hamburgers |     |      |          |      |      |      |    |    |
| 22.8                     | 4   | 108  | 93       | 3.85 | 2.32 | 18.6 | 1  |    |
| She prefers halloumi     |     |      |          |      |      |      |    |    |
| 21.4                     | 6   | 258  | 110      | 3.08 | 3.21 | 19.4 | 1  |    |
| 18.7                     | 8   | 360  | 175      | 3.15 | 3.44 | 17   | 0  |    |
| 18.1                     | 6   | 225  | 105      | 2.76 | 3.46 | 20.2 | 1  |    |
| They love tofu           |     |      |          |      |      |      |    |    |
| 14.3                     | 8   | 360  | 245      | 3.21 | 3.57 | 15.8 | 0  |    |
| 24.4                     | 4   | 147  | 62       | 3.69 | 3.19 | 20   | 1  |    |
| 22.8                     | 4   | 141  | 95       | 3.92 | 3.15 | 22.9 | 1  |    |

We can also stack several extra headers on top of one another:

```
tt(x) |>
  group_tt(j = list("Foo" = 2:3, "Bar" = 5)) |>
  group_tt(j = list("Hello" = 1:2, "World" = 4:5))
```

| Hello |     |      | World |      |
|-------|-----|------|-------|------|
| mpg   | Foo |      | hp    | Bar  |
|       | cyl | disp |       | drat |
| 21    | 6   | 160  | 110   | 3.9  |
| 21    | 6   | 160  | 110   | 3.9  |
| 22.8  | 4   | 108  | 93    | 3.85 |
| 21.4  | 6   | 258  | 110   | 3.08 |

## 5 Themes

`tinytable` offers a very flexible theming framework, which includes a few basic visual looks, as well as other functions to apply collections of transformations to `tinytable` objects in a

repeatable way. These themes can be applied by supplying a string or function to the `theme` argument in `tt()`. Alternatively, users can call the `theme_tt()` function.

The main difference between `theme_tt()` and the other options in package, is that whereas `style_tt()` and `format_tt()` aim to be output agnostic, `theme_tt()` supplies transformations that can be output-specific, and which can have their own sets of distinct arguments. See below for a few examples.

```
library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]
```

## 5.1 Visual themes

To begin, let's explore a few of the basic looks supplied by themes:

```
tt(x, theme = "striped")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
tt(x) |> theme_tt("striped")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
tt(x, theme = "grid")
```



| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
tt(x, theme = "bootstrap")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

```
tt(x, theme = "void")
```

| mpg  | cyl | disp | hp  | drat |
|------|-----|------|-----|------|
| 21   | 6   | 160  | 110 | 3.9  |
| 21   | 6   | 160  | 110 | 3.9  |
| 22.8 | 4   | 108  | 93  | 3.85 |
| 21.4 | 6   | 258  | 110 | 3.08 |

## 5.2 Custom themes

Users can also define their own themes to apply consistent visual tweaks to tables. For example, this defines a themeing function and sets a global option to apply it to all tables consistently:

```
theme_vincent <- function(x, ...) {
  out <- x |>
  style_tt(color = "teal") |>
  theme_tt("placement")
  out@caption <- "Always use the same caption."
  out@width <- .5
  return(out)
}
```

```
options(tinytable_tt_theme = theme_vincent)

tt(mtcars[1:2, 1:2])
```

Table 8: Always use the same caption.

| mpg | cyl |
|-----|-----|
| 21  | 6   |
| 21  | 6   |

```
tt(mtcars[1:3, 1:3])
```

Table 9: Always use the same caption.

| mpg  | cyl | disp |
|------|-----|------|
| 21   | 6   | 160  |
| 21   | 6   | 160  |
| 22.8 | 4   | 108  |

```
options(tinytable_tt_theme = NULL)
```

Here is a slightly more complex example. The benefit of this approach is that we apply a function via the `style_tt()` function and its `finalize` argument, so we can leverage some of the object components that are only available at the printing stage:

```
theme_slides <- function(x, ...) {
  fn <- function(table) {
    if (isTRUE(table@output == "typst")) {
      table@table_string <- paste0("#figure([\n", table@table_string, "\n])")
    }
    return(table)
  }
  x <- style_tt(x, finalize = fn)
  x <- theme_tt(x, theme = "default")
  return(x)
}

tt(head(iris), theme = theme_slides)
```

### 5.3 Tabular

The `tabular` theme is designed to provide a more “raw” table, without a floating table environment in LaTeX, and without CSS or Javascript in HTML.

```
tt(x) |> theme_tt("tabular") |> print("latex")
```

```
\begin{tabular}{llllll}
\hline
mpg & cyl & disp & hp & drat & \ \ \hline
21 & 6 & 160 & 110 & 3.9 & \ \
21 & 6 & 160 & 110 & 3.9 & \ \
22.8 & 4 & 108 & 93 & 3.85 & \ \
21.4 & 6 & 258 & 110 & 3.08 & \ \
\hline
\end{tabular}
```

### 5.4 Resize

The `resize` theme allows you to adjust the size of the table in LaTeX outputs, making it fit within a specified width of the page. This is useful for large tables that need to be scaled down to fit the document layout. This table will be scaled to 90% of the available line width, ensuring it fits nicely within the document.

```
tmp <- cbind(mtcars, mtcars)[1:10,]
tt(tmp) |> theme_tt("resize", width = .9)
```

| mpg  | cyl | disp | hp  | drat | wt   | qsec | vs | am | gear | carb | mpg  | cyl | disp | hp  | drat | wt   | qsec | vs | am | gear | carb |
|------|-----|------|-----|------|------|------|----|----|------|------|------|-----|------|-----|------|------|------|----|----|------|------|
| 21   | 6   | 160  | 110 | 3.9  | 2.62 | 16.5 | 0  | 1  | 4    | 4    | 21   | 6   | 160  | 110 | 3.9  | 2.62 | 16.5 | 0  | 1  | 4    | 4    |
| 21   | 6   | 160  | 110 | 3.9  | 2.88 | 17   | 0  | 1  | 4    | 4    | 21   | 6   | 160  | 110 | 3.9  | 2.88 | 17   | 0  | 1  | 4    | 4    |
| 22.8 | 4   | 108  | 93  | 3.85 | 2.32 | 18.6 | 1  | 1  | 4    | 1    | 22.8 | 4   | 108  | 93  | 3.85 | 2.32 | 18.6 | 1  | 1  | 4    | 1    |
| 21.4 | 6   | 258  | 110 | 3.08 | 3.21 | 19.4 | 1  | 0  | 3    | 1    | 21.4 | 6   | 258  | 110 | 3.08 | 3.21 | 19.4 | 1  | 0  | 3    | 1    |
| 18.7 | 8   | 360  | 175 | 3.15 | 3.44 | 17   | 0  | 0  | 3    | 2    | 18.7 | 8   | 360  | 175 | 3.15 | 3.44 | 17   | 0  | 0  | 3    | 2    |
| 18.1 | 6   | 225  | 105 | 2.76 | 3.46 | 20.2 | 1  | 0  | 3    | 1    | 18.1 | 6   | 225  | 105 | 2.76 | 3.46 | 20.2 | 1  | 0  | 3    | 1    |
| 14.3 | 8   | 360  | 245 | 3.21 | 3.57 | 15.8 | 0  | 0  | 3    | 4    | 14.3 | 8   | 360  | 245 | 3.21 | 3.57 | 15.8 | 0  | 0  | 3    | 4    |
| 24.4 | 4   | 147  | 62  | 3.69 | 3.19 | 20   | 1  | 0  | 4    | 2    | 24.4 | 4   | 147  | 62  | 3.69 | 3.19 | 20   | 1  | 0  | 4    | 2    |
| 22.8 | 4   | 141  | 95  | 3.92 | 3.15 | 22.9 | 1  | 0  | 4    | 2    | 22.8 | 4   | 141  | 95  | 3.92 | 3.15 | 22.9 | 1  | 0  | 4    | 2    |
| 19.2 | 6   | 168  | 123 | 3.92 | 3.44 | 18.3 | 1  | 0  | 4    | 4    | 19.2 | 6   | 168  | 123 | 3.92 | 3.44 | 18.3 | 1  | 0  | 4    | 4    |

## 5.5 Placement

The `placement` theme offers control over the positioning of the table in LaTeX documents, using floating parameters like `H` (from the `float` LaTeX package) to specify where the table should appear.

```
options(tinytable_theme_placement_latex_float = NULL)
tt(x) |>
  theme_tt("placement", latex_float = "H") |>
  print(output = "latex")
```

```
\begin{table}[H]
\centering
\begin{tblr}[          %% tabulararray outer open
]                    %% tabulararray outer close
{                    %% tabulararray inner open
colspec={Q[]Q[]Q[]Q[]Q[]},
}                    %% tabulararray inner close
\toprule
mpg & cyl & disp & hp & drat \\\ \midrule %% TinyTableHeader
21  & 6 & 160 & 110 & 3.9 \\\
21  & 6 & 160 & 110 & 3.9 \\\
22.8 & 4 & 108 & 93 & 3.85 \\\
21.4 & 6 & 258 & 110 & 3.08 \\\
\bottomrule
\end{tblr}
\end{table}
```

## 5.6 Rotate

```
tt(head(iris), caption = "Rotated table.") |>
  theme_tt("rotate", angle = 45)
```

## 5.7 Multipage

The `multipage` theme is designed for LaTeX documents to allow long tables to continue across multiple pages. This theme ensures that tables are not truncated and that all data is presented clearly.

Table 10: Rotated table.

| Sepal.Length | Sepal.Width | Petal.Length | Petal.Width | Species |
|--------------|-------------|--------------|-------------|---------|
| 5.1          | 3.5         | 1.4          | 0.2         | setosa  |
| 4.9          | 3           | 1.4          | 0.2         | setosa  |
| 4.7          | 3.2         | 1.3          | 0.2         | setosa  |
| 4.6          | 3.1         | 1.5          | 0.2         | setosa  |
| 5            | 3.6         | 1.4          | 0.2         | setosa  |
| 5.4          | 3.9         | 1.7          | 0.4         | setosa  |

```
tmp <- rbind(mtcars, mtcars)[, 1:6]

cap <- "A long 80\\% width table with repeating headers."

tt(tmp, width = .8, caption = cap) |>
  theme_tt("multipage", rowhead = 1)
```

Table 11: A long 80% width table with repeating headers.

| mpg  | cyl | disp  | hp  | drat | wt   |
|------|-----|-------|-----|------|------|
| 21   | 6   | 160   | 110 | 3.9  | 2.62 |
| 21   | 6   | 160   | 110 | 3.9  | 2.88 |
| 22.8 | 4   | 108   | 93  | 3.85 | 2.32 |
| 21.4 | 6   | 258   | 110 | 3.08 | 3.21 |
| 18.7 | 8   | 360   | 175 | 3.15 | 3.44 |
| 18.1 | 6   | 225   | 105 | 2.76 | 3.46 |
| 14.3 | 8   | 360   | 245 | 3.21 | 3.57 |
| 24.4 | 4   | 146.7 | 62  | 3.69 | 3.19 |
| 22.8 | 4   | 140.8 | 95  | 3.92 | 3.15 |
| 19.2 | 6   | 167.6 | 123 | 3.92 | 3.44 |
| 17.8 | 6   | 167.6 | 123 | 3.92 | 3.44 |
| 16.4 | 8   | 275.8 | 180 | 3.07 | 4.07 |
| 17.3 | 8   | 275.8 | 180 | 3.07 | 3.73 |
| 15.2 | 8   | 275.8 | 180 | 3.07 | 3.78 |
| 10.4 | 8   | 472   | 205 | 2.93 | 5.25 |
| 10.4 | 8   | 460   | 215 | 3    | 5.42 |
| 14.7 | 8   | 440   | 230 | 3.23 | 5.34 |
| 32.4 | 4   | 78.7  | 66  | 4.08 | 2.2  |
| 30.4 | 4   | 75.7  | 52  | 4.93 | 1.61 |
| 33.9 | 4   | 71.1  | 65  | 4.22 | 1.83 |
| 21.5 | 4   | 120.1 | 97  | 3.7  | 2.46 |
| 15.5 | 8   | 318   | 150 | 2.76 | 3.52 |
| 15.2 | 8   | 304   | 150 | 3.15 | 3.44 |

Continued on next page

Table 11: A long 80% width table with repeating headers. (Continued)

| mpg  | cyl | disp  | hp  | drat | wt   |
|------|-----|-------|-----|------|------|
| 13.3 | 8   | 350   | 245 | 3.73 | 3.84 |
| 19.2 | 8   | 400   | 175 | 3.08 | 3.85 |
| 27.3 | 4   | 79    | 66  | 4.08 | 1.94 |
| 26   | 4   | 120.3 | 91  | 4.43 | 2.14 |
| 30.4 | 4   | 95.1  | 113 | 3.77 | 1.51 |
| 15.8 | 8   | 351   | 264 | 4.22 | 3.17 |
| 19.7 | 6   | 145   | 175 | 3.62 | 2.77 |
| 15   | 8   | 301   | 335 | 3.54 | 3.57 |
| 21.4 | 4   | 121   | 109 | 4.11 | 2.78 |
| 21   | 6   | 160   | 110 | 3.9  | 2.62 |
| 21   | 6   | 160   | 110 | 3.9  | 2.88 |
| 22.8 | 4   | 108   | 93  | 3.85 | 2.32 |
| 21.4 | 6   | 258   | 110 | 3.08 | 3.21 |
| 18.7 | 8   | 360   | 175 | 3.15 | 3.44 |
| 18.1 | 6   | 225   | 105 | 2.76 | 3.46 |
| 14.3 | 8   | 360   | 245 | 3.21 | 3.57 |
| 24.4 | 4   | 146.7 | 62  | 3.69 | 3.19 |
| 22.8 | 4   | 140.8 | 95  | 3.92 | 3.15 |
| 19.2 | 6   | 167.6 | 123 | 3.92 | 3.44 |
| 17.8 | 6   | 167.6 | 123 | 3.92 | 3.44 |
| 16.4 | 8   | 275.8 | 180 | 3.07 | 4.07 |
| 17.3 | 8   | 275.8 | 180 | 3.07 | 3.73 |
| 15.2 | 8   | 275.8 | 180 | 3.07 | 3.78 |
| 10.4 | 8   | 472   | 205 | 2.93 | 5.25 |
| 10.4 | 8   | 460   | 215 | 3    | 5.42 |
| 14.7 | 8   | 440   | 230 | 3.23 | 5.34 |
| 32.4 | 4   | 78.7  | 66  | 4.08 | 2.2  |
| 30.4 | 4   | 75.7  | 52  | 4.93 | 1.61 |
| 33.9 | 4   | 71.1  | 65  | 4.22 | 1.83 |
| 21.5 | 4   | 120.1 | 97  | 3.7  | 2.46 |

Continued on next page

Table 11: A long 80% width table with repeating headers. (Continued)

| mpg  | cyl | disp  | hp  | drat | wt   |
|------|-----|-------|-----|------|------|
| 15.5 | 8   | 318   | 150 | 2.76 | 3.52 |
| 15.2 | 8   | 304   | 150 | 3.15 | 3.44 |
| 13.3 | 8   | 350   | 245 | 3.73 | 3.84 |
| 19.2 | 8   | 400   | 175 | 3.08 | 3.85 |
| 27.3 | 4   | 79    | 66  | 4.08 | 1.94 |
| 26   | 4   | 120.3 | 91  | 4.43 | 2.14 |
| 30.4 | 4   | 95.1  | 113 | 3.77 | 1.51 |
| 15.8 | 8   | 351   | 264 | 4.22 | 3.17 |
| 19.7 | 6   | 145   | 175 | 3.62 | 2.77 |
| 15   | 8   | 301   | 335 | 3.54 | 3.57 |
| 21.4 | 4   | 121   | 109 | 4.11 | 2.78 |

## 5.8 User-written themes

### 5.8.1 theme\_mitex()

This theme was written by Kazuharu Yanagimoto. Thanks for your contribution!

The [MiTeX project](#) aims to bring LaTeX support to Typst documents. This theme replace every instance of matching pairs of dollars signs  $$..$$  by a MiTeX function call: `#mitex(...)`. This allows you to use LaTeX math in Typst documents.

Warning: The substitution code is very simple and it may not work properly when there are unmatched  $\$$  symbols in the document.

```
theme_mitex <- function(x, ...) {
  fn <- function(table) {
    if (isTRUE(table@output == "typst")) {
      table@table_string <- gsub("\\\\$(.*?)\\$", "#mitex(`\\1`)", table@table_string)
    }
    return(table)
  }
  x <- style_tt(x, finalize = fn)
  x <- theme_tt(x, theme = "default")
  return(x)
}
```



## 6 Plots and images

The `plot_tt()` function can embed images and plots in a `tinytable`. We can insert images by specifying their paths and positions (`i/j`).

```
library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]
```



### 6.1 Inserting images in tables

To insert images in a table, we use the `plot_tt()` function. The `path_img` values must be relative to the main document saved by `save_tt()` or to the Quarto (or Rmarkdown) document in which the code is executed.

```
dat <- data.frame(
  Species = c("Spider", "Squirrel"),
  Image = ""
)

img <- c(
  "../figures/spider.png",
  "../figures/squirrel.png"
)

tt(dat) |>
  plot_tt(j = 2, images = img, height = 3)
```

| Species  | Image   |
|----------|---|
| Spider   |  |
| Squirrel |  |

In HTML tables, it is possible to insert tables directly from a web address, but not in LaTeX.

## 6.2 Inline plots

We can draw inline plots three ways, with

1. Built-in templates for histograms, density plots, and bar plots
2. Custom plots using base R plots.
3. Custom plots using `ggplot2`.

To draw custom plots, one simply has to define a custom function, whose structure we illustrate below.

### 6.2.1 Built-in plots

There are several types of inline plots available by default. For example,

```
plot_data <- list(mtcars$mpg, mtcars$hp, mtcars$qsec)

dat <- data.frame(
  Variables = c("mpg", "hp", "qsec"),
  Histogram = "",
  Density = "",
  Bar = "",
  Line = ""
)

# random data for sparklines
lines <- lapply(1:3, \(x) data.frame(x = 1:10, y = rnorm(10)))

tt(dat) |>
  plot_tt(j = 2, fun = "histogram", data = plot_data) |>
  plot_tt(j = 3, fun = "density", data = plot_data, color = "darkgreen") |>
  plot_tt(j = 4, fun = "bar", data = list(2, 3, 6), color = "orange") |>
  plot_tt(j = 5, fun = "line", data = lines, color = "blue") |>
  style_tt(j = 2:5, align = "c")
```

| Variables | Histogram | Density | Bar | Line |
|-----------|-----------|---------|-----|------|
| mpg       |           |         |     |      |
| hp        |           |         |     |      |
| qsec      |           |         |     |      |




## 6.2.2 Custom plots: Base R

Important: Custom functions must have ... as an argument.

To create a custom inline plot using Base R plotting functions, we create a function that returns another function. `tinytable` will then call that second function internally to generate the plot.

This is easier than it sounds! For example:

```
f <- function(d, ...) {  
  function() hist(d, axes = FALSE, ann = FALSE, col = "lightblue")  
}  
  
plot_data <- list(mtcars$mpg, mtcars$hp, mtcars$qsec)  
  
dat <- data.frame(Variables = c("mpg", "hp", "qsec"), Histogram = "")  
  
tt(dat) |>  
  plot_tt(j = 2, fun = f, data = plot_data)
```

| Variables | Histogram   |
|-----------|---|
| mpg       |   |
| hp        |  |
| qsec      |  |

## 6.2.3 Custom plots: ggplot2

Important: Custom functions must have ... as an argument.

To create a custom inline plot using `ggplot2`, we create a function that returns a `ggplot` object:

```
library(ggplot2)  
  
f <- function(d, color = "black", ...) {  
  d <- data.frame(x = d)  
  ggplot(d, aes(x = x)) +  
    geom_histogram(bins = 30, color = color, fill = color) +  
    scale_x_continuous(expand=c(0,0)) +  
    scale_y_continuous(expand=c(0,0)) +
```




```

  theme_void()
}

plot_data <- list(mtcars$mpg, mtcars$hp, mtcars$qsec)

tt(dat) |>
  plot_tt(j = 2, fun = f, data = plot_data, color = "pink")

```

| Variables | Histogram   |
|-----------|---|
| mpg       |  |
| hp        |  |
| qsec      |  |

We can insert arbitrarily complex plots by customizing the `ggplot2` call:

```

penguins <- read.csv(
  "https://vincentarelbundock.github.io/Rdatasets/csv/palmerpenguins/penguins.csv",
  na.strings = "") |> na.omit()

# split data by species
dat <- split(penguins, penguins$species)
body <- lapply(dat, \(x) x$body_mass_g)
flip <- lapply(dat, \(x) x$flipper_length_mm)

# create nearly empty table
tab <- data.frame(
  "Species" = names(dat),
  "Body Mass" = "",
  "Flipper Length" = "",
  "Body vs. Flipper" = "",
  check.names = FALSE
)

# custom ggplot2 function to create inline plot
f <- function(d, ...) {
  ggplot(d, aes(x = flipper_length_mm, y = body_mass_g, color = sex)) +
    geom_point(size = .2) +
    scale_x_continuous(expand=c(0,0)) +
    scale_y_continuous(expand=c(0,0)) +


```

```

scale_color_manual(values = c("#E69F00", "#56B4E9")) +
theme_void() +
theme(legend.position = "none")
}

# `tinytable` calls
tt(tab) |>
  plot_tt(j = 2, fun = "histogram", data = body, height = 2) |>
  plot_tt(j = 3, fun = "density", data = flip, height = 2) |>
  plot_tt(j = 4, fun = f, data = dat, height = 2) |>
  style_tt(j = 2:4, align = "c")

```



## 7 Customization

```

library(tinytable)
options(tinytable_tt_digits = 3)
options(tinytable_theme_placement_latex_float = "H")
x <- mtcars[1:4, 1:5]

```

### 7.1 HTML

The HTML customization options described in this section are not available for LaTeX (or PDF) documents. Please refer to the web documentation to read this part of the tutorial.

### 7.1.1 Bootstrap classes

### 7.1.2 CSS declarations

### 7.1.3 CSS rules

## 7.2 LaTeX / PDF

### 7.2.1 Preamble

*Warning:* Some of the features of this package may require a recent version of the `tabularray` package. Please update your local LaTeX distribution before using `tinytable`.

In Rmarkdown and Quarto documents, `tinytable` will automatically populate your LaTeX preamble with the necessary packages and commands. When creating your own LaTeX documents, you should insert these commands in the preamble:

```
\usepackage{tabularray}
\usepackage{float}
\usepackage{graphicx}
\usepackage{rotating}
\usepackage[normalem]{ulem}
\UseTblrLibrary{booktabs}
\NewTableCommand{\tinytableDefineColor}[3]{\definecolor{#1}{#2}{#3}}
\newcommand{\tinytableTabularrayUnderline}[1]{\underline{#1}}
\newcommand{\tinytableTabularrayStrikeout}[1]{\sout{#1}}
```

### 7.2.2 Introduction to `tabularray`

`tabularray` offers a robust solution for creating and managing tables in LaTeX, standing out for its flexibility and ease of use. It excels in handling complex table layouts and offers enhanced functionality compared to traditional LaTeX table environments. This package is particularly useful for users requiring advanced table features, such as complex cell formatting, color management, and versatile table structures.

A key feature of `Tabularray` is its separation of style from content. This approach allows users to define the look and feel of their tables (such as color, borders, and text alignment) independently from the actual data within the table. This separation simplifies the process of formatting tables and enhances the clarity and maintainability of LaTeX code. The `tabularray` documentation is fantastic. It will teach you how to customize virtually every aspect of your tables: <https://ctan.org/pkg/tabularray?lang=en>

Tabularray introduces a streamlined interface for specifying table settings. It employs two types of settings blocks: Inner and Outer. The Outer block is used for settings that apply to the entire table, like overall alignment, while the Inner block handles settings for specific elements like columns, rows, and cells. The `style_tt()` function includes `tabularray_inner` and `tabularray_outer` arguments to set these respective features.

Consider this `tabularray` example, which illustrates the use of inner settings:

```
\begin{table}
\centering
\begin{tblr}[          %% tabularray outer open
]                    %% tabularray outer close
{                    %% tabularray inner open
column{1-4}={halign=c},
hlines = {bg=white},
vlines = {bg=white},
cell{1,6}{odd} = {bg=teal7},
cell{1,6}{even} = {bg=green7},
cell{2,4}{1,4} = {bg=red7},
cell{3,5}{1,4} = {bg=purple7},
cell{2}{2} = {r=4,c=2}{bg=azure7},
}                    %% tabularray inner close
mpg & cyl & disp & hp \\
21 & 6 & 160 & 110 \\
21 & 6 & 160 & 110 \\
22.8 & 4 & 108 & 93 \\
21.4 & 6 & 258 & 110 \\
18.7 & 8 & 360 & 175 \\
\end{tblr}
\end{table}
```

The Inner block, enclosed in `{}`, defines specific styles like column formats (`column{1-4}={halign=c}`), horizontal and vertical line colors (`hlines={fg=white}`, `vlines={fg=white}`), and cell colorations (`cell{1,6}{odd}={bg=teal7}`, etc.). The last line of the inner block also specifies that the second cell of row 2 (`cell{2}{2}`) should span 4 rows and 2 columns (`{r=4,c=3}`), be centered (`halign=c`), and with a background color with the 7th luminance level of the azure color (`bg=azure7`).

We can create this code easily by passing a string to the `tabularray_inner` argument of the `style_tt()` function:

```
##/ tbl-cap: "\LaTeX{} table with colors and a spanning cell."
inner <- "
```

```

column{1-4}={halign=c},
hlines = {fg=white},
vlines = {fg=white},
cell{1,6}{odd} = {bg=teal7},
cell{1,6}{even} = {bg=green7},
cell{2,4}{1,4} = {bg=red7},
cell{3,5}{1,4} = {bg=purple7},
cell{2}{2} = {r=4,c=2}{bg=azure7},
"
mtcars[1:5, 1:4] |>
  tt(theme = "void") |>
  style_tt(tabularray_inner = inner)

```

| mpg  | cyl | disp | hp  |
|------|-----|------|-----|
| 21   | 6   | 360  | 110 |
| 21   |     |      | 110 |
| 22.8 |     |      | 93  |
| 21.4 |     |      | 110 |
| 18.7 | 8   | 360  | 175 |

### 7.2.3 tabularray keys

Inner specifications:

| Key                   | Description and Values  | Initial Value        |
|-----------------------|---|----------------------|
| <code>rulesep</code>  | space between two hlines or vlines  | 2pt                  |
| <code>stretch</code>  | stretch ratio for struts added to cell text   | 1                    |
| <code>abovesep</code> | set vertical space above every row  | 2pt                  |
| <code>belowsep</code> | set vertical space below every row  | 2pt                  |
| <code>rowsep</code>   | set vertical space above and below every row  | 2pt                  |
| <code>leftsep</code>  | set horizontal space to the left of every column  | 6pt                  |
| <code>rightsep</code> | set horizontal space to the right of every column   | 6pt                  |
| <code>colsep</code>   | set horizontal space to both sides of every column  | 6pt                  |
| <code>hspan</code>    | horizontal span algorithm: <code>default</code> , <code>even</code> , or <code>minimal</code> | <code>default</code> |
| <code>vspan</code>    | vertical span algorithm: <code>default</code> or <code>even</code>                            | <code>default</code> |
| <code>baseline</code> | set the baseline of the table   | <code>m</code>       |

Outer specifications:



| Key             | Description and Values                 | Initial Value |
|-----------------|--|---------------|
| <b>baseline</b> | set the baseline of the table          | <b>m</b>      |
| <b>long</b>     | change the table to a long table       | None          |
| <b>tall</b>     | change the table to a tall table       | None          |
| <b>expand</b>   | you need this key to use verb commands | None          |

Cells:

| Key           | Description and Values   | Initial Value |
|---------------|--|---------------|
| <b>halign</b> | horizontal alignment: <b>l</b> (left), <b>c</b> (center), <b>r</b> (right) or <b>j</b> (justify)             | <b>j</b>      |
| <b>valign</b> | vertical alignment: <b>t</b> (top), <b>m</b> (middle), <b>b</b> (bottom), <b>h</b> (head) or <b>f</b> (foot) | <b>t</b>      |
| <b>wd</b>     | width dimension  | None          |
| <b>bg</b>     | background color name  | None          |
| <b>fg</b>     | foreground color name  | None          |
| <b>font</b>   | font commands  | None          |
| <b>mode</b>   | set cell mode: <b>math</b> , <b>imath</b> , <b>dmath</b> or <b>text</b>                                      | None          |
| <b>cmd</b>    | execute command for the cell text  | None          |
| <b>preto</b>  | prepend text to the cell   | None          |
| <b>appto</b>  | append text to the cell  | None          |
| <b>r</b>      | number of rows the cell spans  | <b>1</b>      |
| <b>c</b>      | number of columns the cell spans   | <b>1</b>      |

Rows:

| Key             | Description and Values   | Initial Value |
|-----------------|--|---------------|
| <b>halign</b>   | horizontal alignment: <b>l</b> (left), <b>c</b> (center), <b>r</b> (right) or <b>j</b> (justify)             | <b>j</b>      |
| <b>valign</b>   | vertical alignment: <b>t</b> (top), <b>m</b> (middle), <b>b</b> (bottom), <b>h</b> (head) or <b>f</b> (foot) | <b>t</b>      |
| <b>ht</b>       | height dimension   | None          |
| <b>bg</b>       | background color name  | None          |
| <b>fg</b>       | foreground color name  | None          |
| <b>font</b>     | font commands  | None          |
| <b>mode</b>     | set mode for row cells: <b>math</b> , <b>imath</b> , <b>dmath</b> or <b>text</b>                             | None          |
| <b>cmd</b>      | execute command for every cell text  | None          |
| <b>abovesep</b> | set vertical space above the row   | <b>2pt</b>    |
| <b>belowsep</b> | set vertical space below the row   | <b>2pt</b>    |
| <b>rowsep</b>   | set vertical space above and below the row   | <b>2pt</b>    |
| <b>preto</b>    | prepend text to every cell (like <b>&gt;</b> specifier in <b>rowspec</b> )                                   | None          |

| Key                | Description and Values  | Initial Value |
|--------------------|---|---------------|
| <code>appto</code> | append text to every cell (like <code>&lt;</code> specifier in <code>rowspec</code> ) | None          |

Columns:

| Key                   | Description and Values   | Initial Value    |
|-----------------------|--|------------------|
| <code>halign</code>   | horizontal alignment: <code>l</code> (left), <code>c</code> (center), <code>r</code> (right) or <code>j</code> (justify)                   | <code>j</code>   |
| <code>valign</code>   | vertical alignment: <code>t</code> (top), <code>m</code> (middle), <code>b</code> (bottom), <code>h</code> (head) or <code>f</code> (foot) | <code>t</code>   |
| <code>wd</code>       | width dimension  | None             |
| <code>co</code>       | coefficient for the extendable column ( <code>X</code> column)   | None             |
| <code>bg</code>       | background color name  | None             |
| <code>fg</code>       | foreground color name  | None             |
| <code>font</code>     | font commands  | None             |
| <code>mode</code>     | set mode for column cells: <code>math</code> , <code>imath</code> , <code>dmath</code> or <code>text</code>                                | None             |
| <code>cmd</code>      | execute command for every cell text  | None             |
| <code>leftsep</code>  | set horizontal space to the left of the column   | <code>6pt</code> |
| <code>rightsep</code> | set horizontal space to the right of the column  | <code>6pt</code> |
| <code>colsep</code>   | set horizontal space to both sides of the column   | <code>6pt</code> |
| <code>preto</code>    | prepend text to every cell (like <code>&gt;</code> specifier in <code>colspec</code> )   | None             |
| <code>appto</code>    | append text to every cell (like <code>&lt;</code> specifier in <code>colspec</code> )  | None             |

hlines:

| Key                   | Description and Values   | Initial Value      |
|-----------------------|--|--------------------|
| <code>dash</code>     | dash style: <code>solid</code> , <code>dashed</code> or <code>dotted</code>                | <code>solid</code> |
| <code>text</code>     | replace hline with text (like <code>!</code> specifier in <code>rowspec</code> )           | None               |
| <code>wd</code>       | rule width dimension   | <code>0.4pt</code> |
| <code>fg</code>       | rule color name  | None               |
| <code>leftpos</code>  | crossing or trimming position at the left side   | <code>1</code>     |
| <code>rightpos</code> | crossing or trimming position at the right side  | <code>1</code>     |
| <code>endpos</code>   | adjust <code>leftpos</code> / <code>rightpos</code> for only the leftmost/rightmost column | <code>false</code> |

vlines:

| Key                   | Description and Values  | Initial Value      |
|-----------------------|---|--------------------|
| <code>dash</code>     | dash style: <code>solid</code> , <code>dashed</code> or <code>dotted</code> | <code>solid</code> |
| <code>text</code>     | replace vline with text (like ! specifier in <code>colspec</code> )         | None               |
| <code>wd</code>       | rule width dimension  | <code>0.4pt</code> |
| <code>fg</code>       | rule color name   | None               |
| <code>abovepos</code> | crossing or trimming position at the above side                             | <code>0</code>     |
| <code>belowpos</code> | crossing or trimming position at the below side                             | <code>0</code>     |

## 7.3 Shiny

`tinytable` is a great complement to Shiny for displaying HTML tables in a web app. The styling in a `tinytable` is applied by JavaScript functions and CSS. Thus, to ensure that this styling is preserved in a Shiny app, one strategy is to bake the entire page, save it in a temporary file, and load it using the `includeHTML` function from the `shiny` package. This approach is illustrated in this minimal example:

```
library("shiny")
library("tinytable")

fn <- paste(tempfile(), ".html")
tab <- tt(mtcars[1:5, 1:4]) |>
  style_tt(i = 0:5, color = "orange", background = "black") |>
  save_tt(fn)

shinyApp(
  ui = fluidPage(
    fluidRow(column(12, h1("This is test of tinytable"),
      shiny::includeHTML(fn))),
    server = function(input, output) {
    }
  )
)
```

## 8 FAQ

### 8.1 HTML

- [Relative widths tables: table-layout: fixed vs auto.](#)

## 8.2 LaTeX

### 8.2.1 Preamble

`tinytable` uses the `tabularray` package from your LaTeX distribution to draw tables. `tabularray`, in turn, provides special `tblr`, `talltblr`, and `longtblr` environments to display tabular data.

When rendering a document from Quarto or Rmarkdown directly to PDF, `tinytable` will populate the LaTeX preamble automatically with all the required packages (except when code chunks are cached). For standalone LaTeX documents, these commands should be inserted in the preamble manually:

```
\usepackage{tabularray}
\usepackage{float}
\usepackage{graphicx}
\usepackage{rotating}
\usepackage[normalem]{ulem}
\UseTblrLibrary{booktabs}
\UseTblrLibrary{siunitx}
\newcommand{\tinytableTabularrayUnderline}[1]{\underline{#1}}
\newcommand{\tinytableTabularrayStrikeout}[1]{\sout{#1}}
\NewTableCommand{\tinytableDefineColor}[3]{\definecolor{#1}{#2}{#3}}
```

### 8.2.2 setspace

Some users have encountered unexpected spacing behavior when generating tables that are *not* wrapped in a `\begin{table}` environment (ex: `multipage` or `raw tblr`).

One issue stems from the fact that the `\begin{table}` environment resets any spacing commands in the preamble or body by default, such as:

```
\usepackage{setspace}
\doublespacing
```

This means that when using `theme_tt("multipage")` —which does not wrap the table in a `table` environment— the spacing is *not* reset, and tables are double spaced. This is not a bug, since double-spacing is in fact what the user requested. Nevertheless, the behavior can seem surprising for those used to the automagical `table` environment spacing reset.

One workaround is to add the following to the document preamble when using `multipage/longtblr`:

```

\usepackage{etoolbox}
\AtBeginEnvironment{longtblr}{\begin{singlespacing}}
\AtEndEnvironment{longtblr}{\end{singlespacing}}

```

Example Quarto doc:

```

---
title: longtblr and setspacing
format:
  pdf:
    include-in-header:
      - text: |
          % Tinytable preamble
          \usepackage{tabularray}
          \usepackage{float}
          \usepackage{graphicx}
          \usepackage{codehigh}
          \usepackage[normalem]{ulem}
          \UseTblrLibrary{booktabs}
          \UseTblrLibrary{siunitx}
          \newcommand{\tinytableTabularrayUnderline}[1]{\underline{#1}}
          \newcommand{\tinytableTabularrayStrikeout}[1]{\sout{#1}}
          \NewTableCommand{\tinytableDefineColor}[3]{\definecolor{#1}{#2}{#3}}
          % Spacing Commands
          \usepackage{setspace}
          \doublespacing
          % Fix Spacing in longtblr
          \usepackage{etoolbox}
          \AtBeginEnvironment{longtblr}{\begin{singlespacing}}
          \AtEndEnvironment{longtblr}{\end{singlespacing}}
---

```{=latex}
\begin{longtblr}[           %% tabularray outer open
]                           %% tabularray outer close
{                             %% tabularray inner open
colspec={Q[]Q[]Q[]Q[]},
}                             %% tabularray inner close
\toprule
foo & bar & baz \\

```

```

foo & bar & baz \\
foo & bar & baz \\
\bottomrule
\end{longtblr}
...

```

### 8.2.3 Global styles

`tabularray` allows very powerful styling and themeing options. See [the reference manual](#) for more information.

For example, you can change the size of footnotes in all tables of a document with:

```

---
format:
  pdf:
    keep-tex: true
    header-includes: |
      \SetTblrStyle{foot}{font=\LARGE}
---

...{r}
library(tinytable)
library(magrittr)
tt(head(iris), notes = "Blah blah")
...

```

### 8.2.4 Beamer

Due to a [bug in the upstream package rmarkdown](#), Quarto or Rmarkdown presentations compiled to Beamer cannot include adequate package loading commands in the preamble automatically. This bug prevents `tinytable::usepackage_latex()` from modifying the preamble. Here's a workaround.

Save this LaTeX code as `preamble.tex`:

```

\RequirePackage{tabularray}
\RequirePackage{booktabs}
\RequirePackage{float}
\usepackage[normalem]{ulem}
\usepackage{graphicx}
\UseTblrLibrary{booktabs}

```

```

\UseTblrLibrary{siunitx}
\NewTableCommand{\tinytableDefineColor}[3]{\definecolor{#1}{#2}{#3}}
\newcommand{\tinytableTabulararrayUnderline}[1]{\underline{#1}}
\newcommand{\tinytableTabulararrayStrikeout}[1]{\sout{#1}}

```

Then, load `preamble.tex` in your YAML header:

```

---
output:
  beamer_presentation:
    includes:
      in_header: preamble.tex
---

```

With these changes, the table should appear with colors as expected.

## 8.3 Typst

### 8.3.1 Captions and labels

Due to a quirk in Quarto [reported here](#), captions in Typst and Quarto documents need to be specified using *both* the `tbl-cap` and the `label` chunk option:

```

```{r}
#| tbl-cap: "blah blah blah"
#| label: tbl-blah
tinytable::tt(head(iris, 5))
```

```

### 8.3.2 Multi-page long tables

The Typst tables created by `tinytable` are automatically broken across pages with repeated headers. However, in Quarto documents, the Quarto software wraps tables in an non-breakable `#figure` environment. This can break the display of long tables. One solution is to use a raw Typst code block to set Figures to be breakable:

```

---
format: typst
---

```

```

````{=typst}
#show figure: set block(breakable: true)
```

````{r}
#| tbl-cap: "blah blah blah"
#| label: tbl-blah
library(tinytable)
tt(head(iris, 50))
```

```

## 8.4 Markdown

### 8.4.1 `style_tt()` does not apply to row headers

This is an important limitation, but it is difficult to get around. See this issue for discussion: <https://github.com/vincentarelbundock/tinytable/issues/125>

Users can use markdown styling directly in `group_tt()` to circumvent this. This is documented in the tutorial.

### 8.4.2 `rowspan` and `colspan`

These arguments are already implemented in the form of “pseudo-spans”, meaning that we flush the content of adjacent cells, but do not modify the row or column borders. This is probably adequate for most needs.

One alternative would be to remove line segments in `finalize_grid()`. I tried this but it is tricky and the results were brittle, so I rolled it back. I’m open to considering a PR if someone wants to contribute code, but please discuss the feature design in an issue with me before working on this.

## 8.5 Quarto

### 8.5.1 Custom crossref styles

In Quarto, it is possible to create a custom crossref type for things like appendix tables. One challenge, is that LaTeX will not allow users to nest a `tblr` environment, inside a `table` environment, inside the new environment that Quarto creates for the crossref. Therefore, when rendering a table to LaTeX/PDF, it is important to drop the `\begin{table}` environment. This can be done using the `theme_tt()` function.



In the example below, we call `theme_tt()` explicitly for a single table, but the [themes vignette](#) shows how to set a global theme using the `tinytable_tt_theme` option.

```
---
title: "Crossref Example"
format:
  pdf: default
  html: default
crossref:
  custom:
    - kind: float
      key: apptbl
      latex-env: apptbl
      reference-prefix: Table A
      space-before-numbering: false
      latex-list-of-description: Appendix Table
apptbl-cap-location: top
---

See @apptbl-testing

::: {#apptbl-testing}

```{r}
library(tinytable)

tt(mtcars[1:5,]) |> theme_tt("tabular", style = "tabularray")
```

Caption goes here.

:::
```

### 8.5.2 Sub-captions

With version 0.4.0 of `tinytable` and versions above 1.6 of Quarto—only available [as a pre-release build at the time of writing](#)—users can specify sub-captions for tables. This is done by adding a `tbl-subcap` chunk option to the table chunk. We also need to use a `tinytable` theme to remove built-in table structure and let Quarto handle the table construction. Here is a simple example document:

```

----
format: pdf
----

See @tbl-example, @tbl-example-1, or @tbl-example-2.

```{r}
#| label: tbl-example
#| tbl-cap: "Example"
#| tbl-subcap:
#|   - "Cars"
#|   - "Pressure"
#| layout-ncol: 2

library(tinytable)
tt(head(cars)) |> theme_tt("tabular", style = "tabularray")
tt(head(pressure)) |> theme_tt("tabular", style = "tabularray")
```

```

### 8.5.3 Same table, different styles

In some cases, the user wants to print a single table multiple times with different styles in a single HTML document. This will sometimes cause issues, because the `style_tt()` function inserts several javascript functions to modify the same table, thus creating conflicts. A simple solution is to change the unique ID of the table object manually.

Consider this RevealJS slideshow in which we sequentially highlight different rows of the data frame:

```

----
format: revealjs
----

## Page 1

```{r}
library(tinytable)

tab <- tt(head(iris))
tab
```

```

```
## Page 2

```{r}
tab@id <- "table_01"
tab |> style_tt(i = 3, background = "skyblue")
```

## Page 3

```{r}
tab@id <- "table_02"
tab |> style_tt(i = 5, background = "orange")
```
```