User Guide

Historical Note

In the preface to his *A History of the Giza Necropolis*, Volume I (Cambridge, Mass: Harvard University Press, 1942, p. ix), Egyptologist George A. Reisner (1867–1942) described his plan for forthcoming additional chapters and volumes in the *Giza Necropolis* series. Upon his death at Giza in June 1942, 4,000 typewritten manuscript pages for these *Giza Necropolis* volumes lay in various stages of preparation. At the closing of "Harvard Camp" on the Giza Plateau in 1947, these pages, along with other Harvard University—Boston Museum of Fine Arts Expedition archives, were shipped to the MFA in Boston. While the chapters and pages are not "clean" enough for traditional printed publication, they nevertheless contain critical information on the Giza excavations not available elsewhere. Hundreds of mastaba tombs are described in detail, accompanied by interpretative chapters on funerary architecture, Old Kingdom royal and private family genealogies, burial equipment, and other topics.

This digital document contains scanned images of one chapter from A History of the Giza Necropolis, Volume II, written by Reisner and edited by him and his staff during the 1930s and 1940s. The original manuscript pages remain in the archives of the Egyptian Section of the Art of the Ancient World Department of the MFA. After Reisner's death, his assistant and successor, William Stevenson Smith (1907–1969), published a much shorter volume with the same name, focusing on the shaft tomb of Queen Hetepheres I (G 7000 X), and ceramic and stone vessel typologies. Thus, the published Giza Necropolis II (Hetepheres) is completely different from the pages contained in this previously unpublished Giza Necropolis II (interpretive chapters). See below for preferred citation information.

Navigating the Manuscript

Two identical manuscripts for *Giza Necropolis* II were created (1 typed original, 1 carbon copy) and *edited differently* from each other. One page was selected to represent both versions in the PDF reconstruction. Choosing the best representative page means that some PDF page images are from one version and some are from the alternate version. (Very occasionally, both versions of a page will appear in the PDF.) By using the markup tools available in Adobe Acrobat 7.0, selected pages were annotated as follows:

Symbol Key

A Blue square in the upper left corner of a page indicates that it is from the alternate version of the manuscript (used instead of the primary). The version designated as <i>primary</i> and the version designated as <i>alternate</i> is arbitrary. There is no clear evidence as to which was the intended, final version. Generally, the copy with more handwritten notations was selected as primary.
Green squares with black text duplicate significant handwritten notes found on the alternate version of the manuscript that are different or missing from the page chosen for the PDF.
Yellow squares with black text are used to clarify a handwritten note that is difficult to read, or to explain something about the page.
or to explain something about the page.

Printing

The original manuscript pages measure 25 cm. by 35 cm. (9.75" x 13.65"). In the U.S., this is closest to modern legal size paper (8.5" x 14"). Note: Paper size is an option under "Page Setup" under the "File" menu in Adobe Acrobat. To print correctly, in the Adobe Acrobat Printing Options, under "Comments and Forms" choose "*Document and Markup*" and under "Page Scaling" choose "*Fit to Printer Margins*." The legibility of handwritten margin notes will depend on the resolution of your printer. The higher the resolution, the better the reproduction.

Searching

The PDF pages are partially searchable. All the pages were put through an optical character reader (OCR). However, the character recognition of old-fashioned typewritten text is not perfect, especially on pages with numerous handwritten notes, hieroglyphic transliteration, and editing marks. The text that the program (Adobe Capture 3.0) generated *was not corrected*. It exists in an invisible layer behind the scanned page image as "dirty OCR." This means that a word search through the manuscript will not always return perfect results. If your search was unsuccessful, try searching for *part* of the word.

Alternatively, search the *Giza Archives Project* database (<u>www.gizapyramids.org</u> or <u>www.mfa.org/giza</u>) to find single pages (from both versions) that contain specific references (see list below).

Understanding References

Tomb number examples: G 2110, G 7000 X, G 4940, Lepsius 23, D 20 (spaces are

necessary when searching the database for tomb references)

Ancient name examples: Seshemnefer, Nefer, Ankh-haf, Iasen (alternate spellings have been

included in the database)

Modern name examples: Junker, Fisher, Smith, Floroff, Quibell

Photo negative number examples: A4935, B8301, C13953, D60 (no spaces are used when searching

the database for photo numbers)

Object Register number examples: 12-11-54 (this means: in 1912, month of November, this is the

54th object logged), 27-2-294 (this means: in 1927, month of

February, this is the 294th object logged)

MFA accession number examples: 13.3144, 37.1311, 12.1483 (this means: in 1912 this was the

1483rd object accessioned to the MFA)

Preferred Citation

Reisner, George Andrew (1867–1942). "Chapter Title." *A History of the Giza Necropolis* II, *Unpublished 1942 Manuscript.* July, 2006. The Giza Archives Project, Museum of Fine Arts, Boston. Access date <URL>.

Additional Information

Omissions

Unimportant editor's marks, corrections of typographical errors, word insertions, text crossed out in blue pencil, and other notations found on the *duplicate* manuscript were not annotated in the PDF reconstruction. Some references to plate or figure numbers found on the duplicate manuscript were also omitted because no plates or figures exist with those specific designations. Plate and figure numbers that refer to the published, *A History of the Giza Necropolis* Volume I (1942) *are* included in the annotations. (Note: All expedition photographs and drawings relating to individual tombs can be examined in detail using the Giza Archive Project website search engine at www.gizapyramids.org.) Margin notes with handwritten transliterations of hieroglyphic inscriptions found on the duplicate manuscript were omitted from the annotations in most cases. Pages of notes left within the original manuscript by other authors using Reisner's material for research were not included in the PDF.

A third, early draft of Appendix A (concerning Cemetery en Echelon) was omitted from the PDF and the searchable pages in the database because most of its margin notes were included in the retyped final versions. Three pages from this early draft *were* included at the end of the PDF and database versions of Appendix A because the material covered was missing from the final draft.

Imaging

The original paper pages are yellow with age and contain red and blue-pencil editing marks. In order to minimize file sizes for the PDF, color information was discarded and the brightness, contrast, and sharpness were enhanced for each scan to make it more legible to the optical character reader.

The optical character reader (Adobe Acrobat 3.0) was set up to create a digital stand-in for the paper page. The digital page usually displays handwritten notations in grayscale and typewritten text in black and white. Occasionally, the OCR interpreted a handwritten notation as black and white text, and typewritten text as grayscale (sometimes as both). If the OCR program encountered something it could not read, it left that part of the page in grayscale. Grayscale can appear fuzzy and is occasionally difficult to read when printed.

Linking

The hyperlink in the bookmarks at the end of each chapter is intended to link to the next chapter, but you will have to download the next chapter to the same folder on your desktop for the hyperlink to function. Each Chapter and Appendix for Volume II is a separate downloadable PDF file.

Catherine Pate, Project Archivist Peter Der Manuelian, Project Director Giza Archives Project Museum of Fine Arts, Boston June 19, 2006

Appendix B = 7 2 7000 X 3 GIza GI-b GI c: Queen Henutsen 7210+20: Hondedef _____ 7310+20:Ra-bauf? ___ 7410+20: Meresankh II 7130+40: Khubuwikhaf ___ 32 7430+ 40 : Minkhaf -7510: Ankhhaf -7650 : Neutyetes. 7520+7530+7540 7530+40 7530 Steet E y 7530+40 7560 88 89 Hondadof 7690-122 7810 7820

APPENDIX B. P.1.

The cemetery of the Eastern Field presents the following

component parts set out in the approximate order of construction:-

- 1) The unfinished pyramid G I-x: begun in the first half of the reign of Cheops, but abandoned when the Hetep-heres burial was made: afterwards replaced by pyramid G I-a. See Vel. I, p.70, Fig. 18.
- 2) The secret tomb of Queen Hetep-heres I, mother of Cheops: a reburial with empty sarcophagus: made about the middle of the reign of Cheops.
- 3) The queen's pyramid G I-a: placed in the angle between the entrance hall of the pyramid temple and the great court of that temple: after the final plan of the pyramid had been partially or wholey carried out.
- 4) The queen's pyramid G I-b south of and in alignment with G I-a: pyrobably built about the same time as G I-a.
- 5) Nucleus cemetery of twelve mastaba cores of type IV-i: in three E-W rows and four N-S lines: see Nos. 7-8 below.
- 6) The queen's pyramid G I-c(Queen Henutsen?): placed south of G I-b smaller and set back to west.
- 7) The construction of the cores of the eight twin mastabasi the four northern twin mastabas enclosing each two cores of the nucleus cemetery of twelve (the northern and middle rows) with massive masonry joining the two old cores: the four cores of the southern row of twelve increased in length by addition of massive corework of type IV-iii on the south: mastaba field prolonged to cover front of pyramid G I-c.
- 8) Casing of the four northern twin mastabas with two interior chapels.
- 9) Casing of the western mastaba of the southern row with two interior chapels: beginning of the casing of the second mastaba from the west: third and fourth mastabas from the west, uncased at this time.

 7450,7350
- 10) Construction of the five massive cores and mastaba G 7050 of type V: G 7510, 7650, 7530+40; the casing of the eighth twin mastaba $\frac{(G.7430+40)}{(G.7430+7440)}$ and G 7050.
- 11) The construction of the eight nummulitic mastabas of the second addition to Cem. G 7000: 755,7660,7750,7810,7810,7820,7060,7070
- 12) Period Mycerinus to end of Dyn. IV: three mastabas added to lines 5 and 6 on the south: a few structures subsidiary to the eight twin mastabas: a few of the earliest of the rock cut tombs.
 - 13) Dyn.V: mastabas of the secondary cemetery: intruded in the streets of the nucleus cemetery and in the vacant spaces S, E and N: continuations of the rock cut tombs.
 - 14) Dyn.VI: continuation of the secondary cemetery and of the cemetery of rock-cut tombs.
 - 15) In XXII Dyn: chapel of pyramid G I-c, reconstructed and enlarged as Temple of Isis, mistress of the pyramids: intrusion of private chapels and burial shafts in eastward extendion of the Isis Temple in the Saite Period.
 - 16) Extension of the intrusive cemetery centered on the Isis Temple eastwards over Cem. G 7000: re-use of old burial shafts and the re-cutting of some to form great communal or family burial places: new shafts also excavated: supperstructures of crude brick: Ptolemaic and Roman times.

indudi)
intext
anior

APPENDIX B. p.2.

The description of these monuments will be given in the following The Three Queens' Pyramins order, the unfinished pyramids and G 7000 X, then the mastabas of the nucleus cemetery in numerical order, the mastabas of the first and second additions in numerical order, and finally the mastabas and rock cut tombs of the secondary cemeteries also in numerical order.

1) Unfinished Pyramid G I-x: 7.5 m. from east face of G I-a: 10.0 m. from west

Pl34 and

face of the twin mastaba G 7110+20: 12.7 m. south of G 7000 X (Hetep-heres tomb): cutting consists of the upper end of a sloping passage, 3.75 m. long (N-S) and 0.85 m. wide, and a transverse cutting 6.35 m. wide (E-W) for two courses of masonry: see [Volt, p. 70, Fig. 118 Let, plane and section: the emplacement was smeared with plaster and the two courses of masonry had been set and later removed: the cuttings and the emplacement indicate The the design to have been like that of G I-a, with sloping rock cut passage descending southwards to a burial chamber continued upwards and outwards by masonry to the projected face of the finished pyramid; the pyramid was to be built over the nucleus of masonry

Plan and sect published in Vol. I

2) G 7000 X: the secret tomb of Hetep-heres I, mother of Cheops: see Bulletin of the Boston Museum of Fine Arts, Vol.XXV, special number, May 1927, "The Tomb of Queen Hetep-heres" Vol.XXVI, No.157, October, 1928, "The Empty Sarcophagus of the Mother of Cheops": Vol.XXVII, No.164, December 1929, "The Household Furniture of Queen Hetep-heres I": Vol.XXX, No.180, August 1930, "The Bed Canopy of the Mother of Cheops": text of final publication in preparation. Secret Tomb: without superstructure or offering place: found intact under the packing of the street in front of the

also add 1939 Buch and and curtain box and Smith Sc. 8 P. pp. 144-148

pyramid G I-a and the Pyramid Temple of Cheops. Shaft: rectangular shaft with mouth measuring 1.65 x 2.45 m., with horizontal grooves for beams used in lowering coffin: descends to 19 m. where there is a shelf on the E side and a shift to the west: gradually contracts to 1.16 x 1.3 m. at the bottom a depth of ca.28 m. from the top.

Stairway and Tunnel:

descending from the N is stairway, 2.675 x 0.585 m(N) and 0.75 m(S) 12 steps descending into rock-tunnel: tunnel, 1.135 m. long, 0.75 m. wide with sloping roof: height of tunnel inside of shaft, 1.1 m.: length of stairway and tunnel, 3.81 m.: opening of tunnel in shaft with roof at 2.05 m. from top, and floor 3.15 m.: stairway and tunnel packed with white limestone blocks set in plaster and covered with heavy layer of plaster.

Blocking of shaft and Chamber:

thus designed (see G. I-a):

At mouth of shaft (1.65 x 2.45 m.) a trick course of irregular blocks of nummulitic limestone, with a depth of 0.8-0.85 m.: under this trick course were 9 courses of well laid white limestone small blocks laid in plaster: with a depth of 3.22 m total depth 0.8+ 3.22 m. = 4.02 m.; this white masonry covers the inner end of the tunnel, at -2.05 (roof) to -3.125(floor).

At depth of 7.47 m. appeared the top of a niche in the west wall: descending to 9.295 m.: walled off with well built masonry of small blocks of white limestone built on shelf on shaft side of niche: irregular floor of niche, 0.725-0.925 x 1.8 m. with an area of 1.48 sq.m.: height, 1.825 m.: capacity about 2.7 cu.m.: thickness of blocking wall, 0.45 m.: space between blocking wall and west wall of niche, 0.91 x 0.7 m.: with area of 0.63 sq.m.: in this space was deposited a food offering consisting of ox bones wrapped in a mat, two jars for wine or beer: charcoal and two fragments of basalt (accidentally intrusive); the ox bones had been broken by the fall of a stone but included a skull with horns and two or three legs: the two jars are registered as follows:-

APPENDIX B. p.3.

25-2-1095: WSR with slip colored pinkish: type A-II b: h.,37.0 cm.: d.rim, 10.3 cm.: d.max., 22.0 cm.

25-2-1096: WSR, with drab slip: type A-II b: h., 34.1 cm.: d.max., 22.0 cm.: with pot-mark, h-t w;d(?): not complete.

25-3-51, 161: charcoal: two lots of small bits of charcoal.

From a depth of 4.03 m., the shaft descends in bad rock and is packed with stones and plaster down to the blocking of the doorway of the burial chamber.

At -12.0 m., were found fragments of RP basin and white limestone block inscribed with a star and a cross.

At -17 m., were fragments of copper.

25-3-258: copper plate: attachments in oval or knife shape.

(a) 9.44 x 3.4 cm. (b) 9.6 x 3.6 cm.

25-3-259: copper: attachment of unknown use: h., 5.6 cm.: width

base, 6.9 cm.: width top, 6.4 cm. 25-3-260: copper and wood: several fragments of fluted column or stem: apparently gilded; inside was decayed wood:

h., 3.1 cm.: d., 2.0 cm.: thickness of copper, 2 mm.

At -22 m., fragments of RP bowl with spout.

Between -22 and -25 m., great quantities of potsherds of different types of vessels, including type D-LXXI, frags of white limestone coffin, limestone sockets for holding canopy poles (5 complete and several incomplete), flint flake, mud jar stoppers without seal impressions.

At -25 m. course of well laid masonry: shaft growing more narrow in N-S direction: between 25 m. and the bottom ten courses blocking the entrance to the chamber, reaching an irregular floor at about -29 m.

Chamber: type 6 b(1): on S: 6.0 x 3.0 m. and 1.8 m. high: area, 18.0 sqmr capacity, 32.4 cu.m.: unfinished cuttings in floor in NW corner, in E wall and in W wall: cutting in W wall, blocked with masonry and plaster and contained the slabaster canopic chest.

Deposit in chamber:

curtain box empty alabaster sarcophagus, bed, bed canopy, carrying chair, two arm-chairs, jewel-box containing inlaid silver anklets, toilet box, implements, stone vessels and pottery: large pieces of furniture and boxes containing vessels and small

objects brought from the original tomb of the queen probably at Dahshur: inscriptions with titles of name of Hetep-heres Hand the king's mother on articles made by Cheops: the bed canopy and the curtain box bear the titles and names of Sneferuw.

3) G I-a: pyramid, 49.5 m. square: stepped core constructed over nucleus structure which carried the sloping passage out to the face of pyramid casing; stages filled but with masonry; the casing of fine white limestone laid in courses sloping downwards from face inwards; on east face of the lower edge of the casing is cut in the native rock with sloping emplacement on top to take masonry; at corners of pyramid, casing laid horizontally

Chapel: in middle of E face: totally destroyed: dressed emplacement of foundation of chapel: probably N > S offering room:

enclosing wall of c.b. along N face of mastaba with length of 42.0 m.; and 1.15 m. thick. @ 34

Burial apartment: sloping passage, descending from north, anteroom with sloping passage prolonged by ramp (as shaft type 2): large E-W burial chamber lined with fine white limestone: see/Chapter VI, p.134: see fig.63.

Boat-grave: rock cut receptacle to receive a wooden sun-bark: cut in space between G I-a and G I-b but close to G I-a: a heavy rebate cut in the edge to take a roofing of heavy limestone slabs of which, one was found in place: slab pierced by a large hole (0.4-6=5 m. in diam.) roughly out by plunderers: bottom cutting takes the form of a flat-bottomed boat; Pl. 36

VOLI,

at (set loop dianty)

A.F. 27-2-40

Length of inner cutting, 2000. m.: rebate, 2000. m.
Width of W end, inner cutting, 2000. m.: rebate, 2000. m.
Width in middle: inner cutting, 2000 m.: rebate, 2000. m.
Width of E end: inner cutting, 2000 m.: rebate, 2000. m.
Depth of inner cutting, at W end, 1000 m.: in middle, 3000. m.
Depth of rebate 2000 m.

Depth of rebate, 0.30.. m.

At .0.1. m., from E end of grave, a rectangular pit, probably connected with boat grave, measuring .1.90 x 1.0. m. and .0.70 m. deep: the c.b. enclosing wall between G I-a and G I-b, passed over the southern side of the boat grave and was constructed after it had been most roofed over. Queens name not preserved

He William of boat grave, plan and section.

De At

These processor 4) G I-b: Pyramid, 49.0 m. square: stepped core as G I-a: but casing set horizont-aly except on N side around the entrance to the sloping passage: casing at NE corner on dressed emplacement on rock: at SE corner founded on foundation platform two courses high to equalize slope of rock: casing dressed to floor level of enclosure.

Chapel: cruciform chapels of type (6a): built against middle of

east face: (a) two niched N-S offering room, 10.5 x 2.05 m.: area, 21.52 sq.m.: prop.1/5.14: fragments of relief show decoration: and (b) E-W vestibule corridor with doorjambs at each end, 1.1 x 3.9 m.: area, 4.29 sq.m. total floor area, 25.81 sq.m.: see Chapter VII, p.217 and Fig. 120.

exterior c.b. court greatly destroyed by c.b. magazines and bins belonging to the Isis Temple: at NE corner of the pyramid, remains of two c.b. walls at right angles forming the NE corner of the pyramid enclosure: thickness of c.b. wall, 1.05 m., length of E-W wall, 14.4 m. with only the beginning of the N-S wall: the east wall appears to have followed the outline of the chapel front and contained a large limestone tank, 2.15 x 1.0 m. and 0.6.8. m. high, walls about 0.1 m. thick sunk in floor debris so that top is about level with floor of chapel. Pl. 34

Burial Apartment: sloping passage: antercom (with modification of ramp in lower end of sloping passage), and E-W burial

chamber lin

Chapel reliefs:

Space chamber lined with white limestone: see Chapter VI, PL.136 Fig.
el reliefs: the chapel had been decorated with
scenes in very low relief of the finest quality.

These had been broken into very small fragments of which only a few were preserved, but some of these could be fitted together:

1) Perhaps from architrave over one of the false doors: 24-11-286 b: horizontal inscription in large hieroglyphs reading ... [nswt] sit wrt hts....
Fig...... Smith, Soulpture, Pl. 38.

2) Probably from tablet of one of two false-doors, two

- fragments with offering list: a) 24-11-242 a has the ewer and basin, and on right one of the registers of offerings, beginning with the tall water jar on a stand. Above appears to be part of the queen's title: wrt hts. b) is part of the list on horizontal lines on right and contains the name of green eye-paint: widt. (24-11-286 e).
- 3) 24-11-286 c could be placed on the back of the outer niche (on the right side) of either of the doors, or on the space north of the northern false-door.

 The wide border on the left has traces of green and blue, evidently from some kind of alternating block pattern. On the right is an offering bearer who evidently held up two jars on each side of him(that on right destroyed). Over him: int.... Fig..... Cf. similar Figure on thickness of niche in 7560, Pl. 77.
 - 4) Group of fragments numbered 24-11-242 and 286 which have been restored to form a river boat being paddled towards the right. Fig.....; see also Smith, Sculpture, P1. 38. In the mastabas of the end of the Fourth Dynasty thingsenant similar boats are shown making the journey to the holy cities and to

Pl. 34 and

h is evidently

the rields of the stand. I would suggest that this is a fragment of the earliest known occurrence of such a fragment of the earliest known occurrence of such a fragment scene. It is probably to be placed over the doorway on the entrance wall, from the analogy of the mastaba scenes. Fig.... and Smith, Sculpture, Pl. 38

5) Two groups of fragments which seem to belong together. Per-

- 5) Two groups of fragments which seem to belong together. Perhaps from the west wall between the two niches. a)

 Fragments forming parts of three registers of figures proceeding to the right, probably twward a large seated figure of the queen. Of the first register there is preserved only the feet of a single figure. In the second, a dwarf(legs only preserved) and a woman in a green dress whose shoulder is distorted somewhat like that in G 4940, on Pl. 15. These figures are approaching a low dais which may be the base of the queen's chair. In that case the lowest register would run under the highest large figure. It shows the horn of a large ox, over which is written rn lw; . b) it is very likely that the man formed by the second group of fragments is leading this ox, or another similar animal in the same register. Over his head is an unintelligble shape which may be the tail of a bird hieroglyph, and on the right is a an object which cannot be identified. See. Fig...... and Smith, Sculpture, Pl. 38. Compare also the very similar attendants with a dwarf on the north wall of the chapel of G 7540, Pl. 57.
- 6) From one of the walls comes a fragment showing the legs of an estate figure. In front of it is written....w determined by a city sign, and behind the legend of a second estate:....w.
- 7) 24-11-286 k fragment of a vertical inscription:hmt nswt?.... Fig......
- 8) 24-11-242 e: probably from same inscription: ... fisw t bity
- 9) 24-11-242 f hieroglyphs of same size as above two:

 [H]wf[w]...b. Fig.....

There were at least five more unintelligible fragments, one of which had a base line and a newt sign(24-11-286 m). See Fig....

The above fragments present ma clear unity of style and cutting. Moreover they were all found near the floor level in the debris of the chapel of G I b under circumstances which make it unlikely that they could have been intrusive. Another group of reliefs was found in the debris of STreet 7000, east of the three Queens' pyramids and in the Isis Temple. A few of these pieces came from the boat grave south of G I a, and another group came from the Cheops causeway. Certain of these pieces are of such a character that they can only be assigned to the chapel of a queen or to a royal temple. It is impossible to tell from which chapel they came, as it is to be presumed that all three pyramids had decorated chapels. It is now certain from Selim Hassan's excavations that at least a portion of the Cheops temple was decorated. A group of small fragments from the causeway are almost certainly from these royal decorations, and these are listed first below. Second are grouped pieces personal third a group of uncertain reliefs which are probably from undetermined private mastabas. It should be noted that several fragments have been assigned to G 7130, the wife of Mhufuw-khaf (p.37...), and one piece from the Queen's boat grave was found to join with a piece from the facade of G 7320 (see p.22.ff).

a) Decoration of the temple of the Cheops Pyramid. In the season of 1938-1939, Selim Bey Hassan found two large blocks and some smaller fragments of limestone reliefs from the decoration of an undetermined part of the Cheops temple, perhaps the causeway corridor. In addition to these were some Fragments of granite with inscriptions. One because block had the upper part of a large figure of the king carved in very fine low relief, but badly weathered. The king stands facing to the left, wearing the red crown(possibly the double crown), and a wavy edged scarff thrown over his right shoulder. Above him is the sn sign probably held by a protecting vulture. Behind him stood attracts a small attendant, probably the uppermost of several such figures.

The second large block shows a figure of Cheops, seated, facing to the right, wearing a heb-sed clack and holding the fixt flail. The throne is probably surmounted by a canopy and in front of it on the right are the bases of the two standards which ordinarily sergest that accompany the Heb-sed pavilion. To the right of this is probably

- are carved in a bolder style of high relief than that of the above pieces.
 - 24-11-548: Red granite fragment with legs of hawk in suhk relief. Must have formed part of the bird surmounting the frame containing the king's Horus name. Evidently from one of the large inscriptions with name and titles of Cheops on the granite casing of the temple walls. Perhaps from a door frame as in Chephren temple. Found in debris north of
 - Queen's pyramid G I b. See Pl. 35 a, Fig.....
 37-3-4 d: Similar Horus hawk on white limestone fragment. Evidently from a large inscription. See Pl. 35 e, Fig....
 - 37-3-4 c: Leg and wing feathers of a large vulture, evidently from a protecting bird above the figure of the king, such as has been suggested above for the first Selim Hassan block. Tike the following, fairly high relief in white limestone. See Pl. 35 3, Fig.....
 - 37-3-4h: Small figure apparently carrying on his shoulder one of the door-bolts of the temple. See Pl.35 e, Fig....
 - 37-3-4 i: hand of small figure holding a staff: See Pl. 35 e, Fig..

 - 37-3-4 b: Head of a goat: See Pl. 35 e , Fig....
 37-3-4 g: Possibly to be interpreted as the hand of a figure holding up an opened papyrus roll, as in the case of scribe's presenting lists of offerings. See Pl. 35 e, Fig...
 37-3-4 f, e: two unintelligible fragments: See Pl. 35 e, Fig....

 - 24-11-889: A fragment showing the oars of a large boat. This was found in the debris of Pyramid G I a, but resembles the bold reliefs of the above fragments more than it does the fine low reliefs of Pyramid G I b. Both types of relief seem to have existed what in different parts of the Cheops temple. This piece seems to belong with the reliefs of that temple rather than with the fragments showing boats from the Queens' reliefs.
- b) Fragments probably from one of the Queens' chapels. It is possible, of course that these may also come from the Cheops temple. Their fine low relief in white limestone is indistinguishable from that on the Selim Hassan blocks mentioned above, but they also resemble the reliefs of G I b. Only two chapels in the Eastern Cemetery are

prince's decorated with reliefs of this particular quality. These are G 7510 and G 7650.

24-12-545: Above a border line of stars such as are found only in royal reliefs are two unintelligible objects which suggest the rigging of a boat. They are made of rope and resemble somewhat a badly battered block in Weserkaf temple which may represent a shrine being dragged along. There also seems to be a remote connection with one of the Cheops blocks in the Metropolitan Museum (No. 09-180-6). The explanation of what these three blocks represents will have to await the discovery of further Old Kingdom royal reliefs. Beneath the

- star border line is a hieroglyph which may be ssp. See Pl. 35b, Fig..... Found between Pyramids Ia and I b.
- 24-12-14: Fragment of water with two paddles from a boat. Found north of G I a: See Fig....
- 24-12-97: Fragment with parts of two vertical columns of Queen's titles: 1)m:! Hr (Sth) 2)(wrt) hts....
 Found in debris of G I a. See Pl. 35 a, Fig....
- 24-11-922: Head of aleph hieroglyph. Found in debris mr east of G I a: See Pl. 35 a, Fig....
- 24-11-473: Small male head. Found in debris north of G I b: See Fig...
- 24-12-57: Fragment with two small figures, a moreocontested girl and boy, evidently with finger to mouth. In front of leach girl is name: Hwfw...; In front of boy is name Hr....

 The relief is coarser than that on other fragments, but it is possible that the boy's name is to be restored either as Hordedef, the owner of G 7220 or Hor-baf, the owner of G 7420. In this case the piece should come from the chapel of the chief queen, G I a. Found north of G I a. See Fig.....
- 26-2-24: Fragment of arm of man leading a bull in very fine low relief resembling the reliefs from G I b, and those above. From debris of G I c. See Pl. 35 a. See Fig...
- c) Fragments from unidentified private mastabas:

"26-12-667" is a typographical error most likely for "25-12-667."

- 24-11-335: Fragment of an offering list, found east of Pyramid G I b. Coarser relief than that used in the Queen's fragments. See Pl. 350, Fig.....
- 26-12-669 667: Fragment of an offering list in compartments. Found in debris of G I c. See Pl. 35 c.
- 24-11-634: Fragment of two vertical lines of titles. Found in the Queen's boat grave. See Pl. 35 a, Fig.....
- 26-2-25: Two fragments of a base line with procession of at least three figures (estates?), feet of at least two men and a woman. The cutting is better than the fragments from G 7050, but different in style from the Queen's reliefs. Found in debris of G I c. See Pl. 35 a, Fig.....
- 25-12-673 b: Large fragment resembling somewhat in style the last.

 Man with hand on back of animal, and holding horns of an ibex. Fragment of hieroglyphic labels over register below. Photo A 4373.

- 29-7-10: Fragment resembling the reliefs assigned to the chapel of Khufuw-khaf's wife (G 7130). Small seated male figure, probably from a door-jamb. Man holds a staff and clasps a handkerchief in his hand on right thigh. Since figure is facing right it cannot come from the north door jamb of G 7130, to which another fragment found in that chapel has to be assigned. Its provenance must remain uncertain. Found in the debris of the isis temple. See Pl. 35 g.
- 26-1-131: Fragment with small figure of a workman, naked but for a loin cloth. Found in debris of Isis Temple. Photo A 4374

5) Pyramid G I-c: Queen Henutsen(?): 46.85 m. square: with E face set back 3.55 m. westward of face of G I-b: stepped core and white casing as G I-a and G I-b: casing courses laid horizontally: NE corner founded on dressed rock emplacement and SE corner resting on two courses of a foundation platform.

1 measurement mussing

Pl. 34

Chapel: original chapel partly destroyed and obscured by the construction of the temple of Isis of the Pyramids of Dyn.XXII with later additions and alterations of the Saite-Ptolemaic Period: the old offering room the partly preserved: rested on a masonry platform which raised the floor of the room about 1.18 m. above the base line of the pyramids: on this was built the walls of the room: as preserved the offering room, with one niche at S end of W walls appeared to measure 7.7 (?) x 2.25 m.: area, 17.32 sq.m.: prop.1/3.42: N-S room with entrance apparently just north of middle of E wall: with palace facade panelling on outside of E wall, on each side of door: I reconstruct the original chapel as a cruciform chapel of type (6a) on the basis of the chapel of G I-b and exterior panelling: two-niched offering room, 9.25 x 2.15 m.: area, 19.89 sq.m.: prop.1/4.3: with entrance in middle of E wall: the panelling requires a court of an outer room (N-S) or a hall. See Part 34

Burial Apartment: sloping passage descending from N: antercom, and E-W burial chamber: antercom converted into a horizontal passage after the introduction of the coffin, by white masonry: burial chamber lined with white masonry: see Chapter VI, p.130, and Fig.65.

Aly white timestime Meaning

Appendix B. p.6.

ملله

Terracing of street E of pyramid and area S of Pyramid: east of the pyramid south of the chapel the rock falls in a steep slope to the south to the front of G 5050: S of the pyramid the rock falled also to the east: at about 10 m. south of the pyramid a long rubble wall, mud plastered on the S side and about 3 m. wide ran E-W and was traced to a spoint south of G 7140: the street E of the pyramid and the area south of the pyramid had been filled out to and the area south of the pyramid had been filled out to the top of this wall with rubbish to form a continuation of Queen's Storlevel with the base of the pyramid and this level was continued over the area south of the Pyramid.

APPENDIX B. p.7.

6) The twelve nucleus cores afterwards included in the eight twin mastabas of Cem. G 7000: each of massive corework, type IV-i, without chapel recess and each with one shaft south of middle:
G 7110 in northern xxx E-W row: G 7120-7420 in middle E-W row: and G 7130-7430 in southern E-W row:

```
Length: Width: Area: Prop.: Height: G 7110 . 36.5 m . 17.25 m . 629.62 sq.m.1/2.11 . 5.32 . m. G 7120 . 36.5 m . 17.5 m . 638.75 sq.m.1/2.08 . 5.18 . m. G 7130 . 37.5 m . 17.5 m . 656.25 sq.m.1/2.14 . 5.61 . m. 67.220 . 36.0 m . 17.0 m . 616.0 sq.m.1/2.11 . 5.40 . m. 67.230 . 36.5 m . 15.25 m . 456.62 sq.m.1/2.11 . 5.40 . m. G 7230 . 36.5 m . 16.5 m . 577.5 sq.m.1/2.12 . 5.33 . m. 67.330 . 35.0 m . 16.5 m . 577.4 sq.m.1/2.12 . 5.33 . m. 67.330 . 36.5 m . 15.5 m . 565.75 sq.m.1/2.12 . 5.35 . m. 67.330 . 36.5 m . 15.5 m . 565.75 sq.m.1/2.12 . 5.35 . m. 67.420 . 35.7 m . 16.5 m . 588.95 sq.m.1/2.16 (?) . 5.00 . m. 67.430 . 36.0 m . 16.5 m . 588.95 sq.m.1/2.16 (?) . 6.00 . m. 67.430 . 36.0 m . 15.5 mm . 558.0 sq.m.1/2.32 . H:70 . m.
```

The two cores, G 7410 and G 7420 were incomplete. The E wall of both were traced from the SE to the NE corner. When the facing of the twin maximal mastaba, G 741047420, was constructed, either the two cores were still incomplete or the W walls with the greater part of the N and S walls were destroyed and replaced by the facing of small stepped courses.

The whole cemeter y of twelve cores appears to have been laid out on a uniform plan. Judging by the width, they were not constructed on the same nfrw level but were aligned approximately both in the N-S and the E-W directions. The fall of the ground to the southeast was not compensated by widening the mastabas. The cores were probably built in N-S lines from west to east. The three cores of each line were probably constructed simultaneously, of the two cores was being constructed when the plan of converting the cores of the two northern rows intow twin mastabas was formed.

The dimensions of the cores show limited variations.

8) The four northern twin mastabas as finished.

G 711047120: twin mastaba of Prince Ka-wa'ab and his wife, Princess(afterwards queen) Hetep-heres II: westernmost of four northern twin mastabas.

See Figs..... Printed in Valume !

See Pls.....

Owner:

h interior

Note

mastala G. 7110 + 20 has two heights for.

Mastaba: core of massive masonry composed of old cores @ 7110 and 7120 connected by massive masonry rempmanixaxxaxixxeres and altered for/chapels: core, 81.5 x 13.25 m.: area, 1405.87 sq.m.: prop.1/4.72: near the south end of old core 7120 a hole was broken and lined with masonry to form a recess for an interior chapel: at the SE corner of old core 7110g a hole was broken to receive another interior chapel. The core was cased in fine white limestone (x-masonry) and

7110 and 7120. \$ hoov of reference and

either to put down have each with subsidiary N niche in casing.

Two heights or Taverage Chapel & 7120: Prince Kawa ab: see reliefs in & 7530: interior offering room (a) of white limestone built in recess reconstructed in core of & 7120: type (3a), with special deep niche at S end of W wall: badly destroyed, reconstructed from two stones in place and construction lines on pavement:

4,0 x 1.6 m.: area, 6.4/sq.m.: prop.1/2.5:/entered from by doorway in N end of E wall, opening in embrasure in sloping face of casing: against the sloping construction of exterior stones. 4,0 x 1.6 m.: area, 6.4/sq.m.: prop.1/2.5: entered from by doorway in N end of E wall, opening in embrasure in sloping face of casing: against the sloping casing is constructed an exterior stone chapel of two rooms (b, c) and a pillared portico(d): which on the east is built over the sloping casing of G 7220: room b, 8.1 x 2.05 m.: area, 16.6/sq.m.: the west wall is builty gainst the slope of the casing N and S of the doorway leaving the embrasure of room a partly exposed: in the W wall north of the doorway are two niches (0.35 m. above the floor) each containing emplacements for two statuettes (probably squatting scribes): S niche, 1.7 x 0.7 m.: with two emplacements preserved side by side: N niche, 1.6 x 0.7 m., with emplacements not preserved: enlarged by doorway from c, at E end of N wall:
room c, 1.5 x 2.85 m. area, 4.27/sq.m.: in W side, sloping
casing exposed: on E, wall built against G 7220: doorway to b, in E end of S wall: entered from d, by doorway at W end of wall: floor of doorway slopes down from level of d to floor level of c: portice d, open to N, with roof supported by two pillars: 2.5 x 4.25 m. (including pillars) area, 10.6 sq.m.: x total area, a-c, 27.3 sq.m.: decorated rooms. total area, b-d, 31.5 sq.m.: exterior chapel. Sum total a-d, 37.9 sq.m.

Decorations of Chapel G X22 7120(rooms a-c): by W.S.Smith:

1) Room a: reconstructed as Hordedef (G 7220): W wall, ka-door as G 7220: W wall N of ka-door, chief figures facing to left and registers of small figures in front, facing to right(as G7140) feet of large figure preserved on slab still in place: S wall Kawa'ab seated at table of bread, facing to right (as G 7140): N wall, Ka-wa'ab standing facing to right, in either a family facing to left (presentation of htmt as @ 7130): N door-jamb standing figure of Kawa'ab (based on frag.(c)): S jamb, without clue: facade panels in embrasures on each side of doorway on each side, Kawa'ab standing facing in with children(?). behind him (based on frag.(c)) and(d).
N Facade panel: owner standing with attendants behind him (see frag c below): S Facade panel: mother of owner /facing to right and two daughters behind him (see frags. d and 1 belw

/and owner

Ph 38a

G 711047120: twin mastaba of Prince Ka-wa to and his wife, Princess(afterwards queen) Hetep-heres II: westernmost of four northern twin mastabas.

See Figs..... Printed in Vol I

Also given other titles in tomb of daughter See Pls..... Meresankh III: hry hb, hry tp, hrp ntrt 1;wt,

Owner: S; nswt n ht-f smsw. rptt h;ty-', wr md sm;w, hm ntr srkt, priest of Anubis core of massive masonry composed of old cores G 7110 and 7120

Core of massive

Note: The red outline represents the edges of a typewritten piece of paper pasted on top of this page.

The head of a large time of the prince (24-12-988 %)

may come from here, but along could be assigned to saving

Alm wales (See Fig.).

connected by massive masonry sampassive conditions and altered for chapels: core, 81.5 x 13.25 m.: area, 1405.87 sq.m.: prop.1/4.72: near the south end of old core 7120 a hole was broken and lined with masonry to form a recess for an interior chapel: at the SE corner of old core 7110# a hole was broken to receive another interior chapel. The core was cased in fine white limestone (x-masonry) and bonded with it two interior chapels of type (3a): the cased mastaba measured, 83.0 x 19.37 m.; area, 1607.71 sq.m.: prop.1/4.28: height 6.1.34.32m. hight of 67120, 5.18 m.

ing,

offering icted in

S end

nes in

by loping

icted an ıred

he west of the

ed: in

with

ing casing

m. above lettes

Decorations of Chapel G 7120(rooms a-c): by W.S. Smith.

1) Room a: The well preserved chapel of Khufuw-khaf, G 7140 can be used as a pattern for the inner offering rooms of the twin-mastabas, which, with some exceptions, probably followed the simple scheme of its decoration. The false-door at the south end of the west wall should have resembled that of Hordedef (G 7220), which is

more complete than that of Khufuw-khaf.

West wall: At the north end of the west wall one slab remains in place showing the legs of Ka-wab, with his wife behind him, and in front a small naked boy holding a lotus flower (see Pl. 37 c and Fig.....) These figures face to the left and the wall must have been completed with several registers of offering bearers proceeding towrd them. Frag. No. 24-12-994 with a cartouche (Fig....) containing the name Hwfw might be from an estate figure on this wall. Possibly the following fragments of inscription with titles and name, facing to the left came from over the large

1 outered

 6×0.7 figures on this wall: m., with emplacements not preserved: what go do do orway from c, at E end of N wall: room c, 1.5 x 2.85 m. area, 4.27 sq.m.: in W side, sloping casing exposed: on E, wall built against G 7220: doorway to b, in E end of S wall: entered from d, by doorway at W end of N wall: floor of doorway slopes down from level of d to floor level of c: portico d, open to N, with roof supported by two pillars: 2.5 x 4.25 m. (including pillars) area, 10.6 sq.m.: total area, a-c, 27.3 sq.m.: decorated rooms. total area, b-d, 31.5 sq.m.: exterior chapel. Sum total a-d, 37.9 sq.m.

Decorations of Chapel G *** 7120(rooms a-c): by W.S.Smith:

1) Room a: reconstructed as Hordedef(G 7220): W wall, ka-door as
G 7220: W wall N of ka-door, chief figures facing to left and registers of small figures in front, facing to right(as G7140) feet of large figure preserved on slab still in place: S wall Kawa b seated at table of bread, facing to right (as G 7140): N wall, Ka-wa b standing facing to right, in either a family group or an abbreviated presentation scene: E wall, # Ka-wa be beated facing to right with registers of small figures facing to left (presentation of htmt as G 7150): N door-jamb standing figure of Kawa b (based on frag.(c)): S jamb, without clue: facade panels in embrasures on each side of doorway on each side, Kawa b standing facing in with children(?) behind him/(based on frag.(c)) and(d).

on south facing away from doowing Towns mother (?)

APPENDIX B. p.9.

- 2) Room b: with two niches which contained four statuettes (squatting scribes) in niches in W wall: S wall, with one or two windows (frag.(e)): presumably decorated in relief (see frag.(e)): E wall, probably also decorated inxreliaf with large figure at S end of wall (see frags.(f)): doorway from b to c, probably decorated with standing figure of Ka-wa'ab facing out (frag. (g)) with name of Ka-wa'ab.
- 3) Room c: probably decorated or intended to be decorated: S wall, W of doorway to b, (frag(g), with part of female figure facing to left, probably behind figure of Rec-wa'ab): jambs of doorway from d to c, on each side above, crouching jakal (Anubis) (based on frag. **** (h), inscribed horizontally war spas hr ntr c;):
- 4) Portico, d: walls not decorated: but pillars apparently decorated on two sides with standing figure (based on frag. (i)).

Fragments in place or found in debris in the chapel:-

(a) in place on slab on W wall of room a, N end: legs of man and wife standing facing in to left with small naked boy in front of man, also facing left and Molding lotus flower in right hand.

(b) 24-12-988: frag. from inner edge of N doorjamb: part of shoulder and upper arm of large figure of man standing facing out to right:

24-12-945: frag. with sloping border from outer edge of jamb: sloping border and one hieroglyphic sign part of border on foods face of fragment.

- (c) large block from embrasure N of doorway to (a): with sloping surface: showing back of leg of large standing figureziza clad in long skirt (tunic?), facing to left behind him two small figures, standing facing in to left, apparently bearing objects and therefore personal attendants: by analogy one or more registers of small figures above this
 - (d) 24-12-1002: frag. apparently with sloping surface, with border on left: thigh of small female figure standing facing to right with two horizontal lines (1) ntr(?) ssm-t (2) Mryt-its: right hand hanging open and left hand probably on breast: in front of this, the hanging open hand of another female figure: probably from facade panel south of doorway to a and behind large standing figure or figures facing in to right.
 - (e) Frag. showing the lower edge of a window: on the left in relief, the right vertical line, signs facing to right h-(t?) hk; df...: assigned to SE corner of room b. on S wall, high up.
- (f) thick block with small end in relief: assigned to S end of E wall of room b, high up: (m); {...., obviously in front of a large figure facing to left: on left of Str vertical line, small figure of herdsmanbowing to right holding stick in right hand, behind him, five head of of cattle standing en wechelon.
 - (g) two fragments from doorway from b to c: 24-12-1128: from western doorjand northern edge: showing on jamb, border and hand and staff of figure standing facing out to right:, in front part of horizontal line reading K!wcb: on the other face (S wall of room c) border and open hand of standing female figure facing out to right, probably with Ka-wab in front of her.
 - 24-12-855: from same jamb, southern edge: on doorjamb, hanging hand with handkerchief from large figure standing facing out to right: on N wall of room b, block border which must have framed the doorway.

msda

wis other

? left?

APPENDIX B. p.9.

```
or

✓ 24-12-1124: upper part of three vertical lines of titles:

                                      1) wr (md smcwl).....
                                                                                                         ay
                                     2) <u>nśw</u>t.....
                                     3) m.....
                                        (hry)-hb.... pe
                                                           perhaps the b on 24-12-1108b fits
                       √24-12-1109b: border line of the same size as above, and one hieroglyph
                                      s. See Fig...
                                                                                                         ):
                       √24-12-937: Possibly part of a title , see Fig....
                                                                                                         ng
ally
                       1/24-12-859: Fragment probably from over head of wife: ... (hm)-t-f
                                     (<u>mryt-f</u>) (<u>s:t</u>) <u>nswt....</u> S<sub>e</sub>e Fig.....
                                (These titles could also come from over the large figure on
                                   the east wall of room b).
                    False-door: The false-door has been entirely destroyed, but it was of
                          the deep , special-niche type, and the following fragments are
                                                                                                         g.
                          probably to be assigned to it:
                       / 36-3-64: corner stone probably from the back of the outer niche on
                                  the south side and the adjoinging surface of the inner niche.
                                                                                                         - man
                                  On the sace of the outer niche, the knees of a small offer-
                                                                                                        bs
                                  ing figure facing to right. On the south face of the inner
                                  niche a strip of linen held up by a figure facing in to right. his would be one of a procession of figures proceeding
                                                                                                         Lotus
                                                                                                          of
                                  in toward the back of the niche as in Hordedef (Figg.....)
                                                                                                        ling
                                  This figure probably held up a strip of linen in each out-
                                  stretched hand, in front and behind him. See. Fig.....
                                                                                                         ge
                       24-12-1117 f, 1111, 1110, 948, 1109 a, 1108 a and perhaps 990 and 939;
Although the last two are more problematical, 939 forming
                                                                                                        зign
Land 1113, 1116 ( soci
                                  the name Ka-wab and 990 of the title (imy)-is, the other fragments
 (Dustrated)
                                  are certainly from the same architrave inscription forming
                                                                                                        ding
                                  an offering formula. Of this is preserved: (dy) nswt Inpw
                                  (htp).....first of the month......s: nswt..
                                                                                                         left
            feb mb (not
                                          (This inscription could also have come from the
                                                                                                        sonal
                                             architrave over the entrance to a).
                                                                                                         a11
                                   See Fig.....
           North Wall: There are no fragments which can be confidently assigned to the north
       Loghin chepel (67140) wall. Khufuw-khaf is shown on the north wall, leaning on his staff
                                                                                                         with
                                                                                                        ing
                         with his wife facing him (6-7145). In G 7650, Akhet-hetep is shown
                         inspecting a presentation of animals. Such a block is the funerary Lucus
                                                                                                        %)
                     √ priests on 24-12-946(Fig...), but this is perhaps from the east wall, see below. The fragments of titles assigned below to the east
                                                                                                         ft
           might
           come
                                                                                                         ging
                         wall may come from this wall also.
           from
           here
            South wall: This probably contained a scene with the prince seated, facing to the
                        right at a table with priests performing the funerary ceremonies as
                        in Khufuw-khaf (G 7140) and many other chapels at Giza. A fragment from
                                                                                                         ft in
                      the list of offerings under the table is 24-12-987(2) with a large
                                                                                                         right
                        1000 sign. See Fig.....
           East wall: Several fragments are probably to be assigned to this wall:
                     24-12-988 a and 24 12-1114: Two pieces on Fig.... The first has part
                                                                                                          end
                                 of the border line down the north edge of the wall and the
                                 hanging arm and back of a large figure of the prince facing
                                                                                                          of
                                 to the right at the north end of the wall. 1114 is probably
                                                                                                         ight
                                 the hand of this figure holding a staff. Asartigax
                                                                                                          of
                         24-12-1115: Upper part of three vertical lines of titles probably
                                 from over the large figure on this wall (could come also from Nors when
                                                                        of y or some de)
                                 1).....
                                 2) nswt.
                                               See Fig....
                                 3)....
                          Fragments from at least two registers of large offering bearers
                                                                                                         t
                                                                                                          othe
```

standing female figure facing out to right, probably with Ka-wab in front of her.

24-12-855 from same jamb, southern edge: on doorjamb, hanging hand with handkerchief from large figure standing facing out to right: on N wall of room room b, block border which must have framed the doorway.

APPENDIX B. p.10.

KRIKESKKd

- (h) 24-12-1125: assigned to top of W jamb of doorway from d to c: the tail of a crouching jackall facing out to right, with remains of horizontal line of large hieroglyphs, war spss hr ntr c;.
- (1) 24-12-861: frag. from top corner of a pillar: shows two lateral surfaces at right angles: on each face a raised border at top and down the edge: on the left-hand surface is the end of a horizontal line (s; nswt n) ht-i with signs facing to left: could be assigned to SW corner of E pillar, or to NW corner of W pillar thus the pillars were decorated on N side with standing I figure facing matxxitxixximprehasticxthatxthexminar in and on the two facing surfaces (W on E pillar and E on W pillar), with a standing figure facing out: it is improbable that the other sides of the pillars were decorated and it is possible that only one side of each pillar was decorated.
- (j) 24-12-108, 109a, 110, 1113, 1116, 1117, 1111, 948:
 Ten small fragments from an architrave: horizontal inscription in relief with large signs: the scattered words show an offering formula, nswt, Inpw, parts of names of festivals, s; nswt ... and K;-wcb: probably from architrave of ka-door in room a but possibly from over doorway from b to a.
 - (k) 24-12-994: small frag. bearing middle part of chartouche reading Hwfw, probably from name of a Cheops-estate: possible from top of W wall of room a.
 - (1) 24-12-1000: small rectangular block with broken edges on right and left: on left edge, front edge of leg of standing female figure in long tunic, fairly large figure: in front of figure remains of two horizontal lines of inscription (relief), large signs reading (1) ... ms-s n (2) Hwfw in cartouche: reconstruct ed as figure of mother of Kawa'ab with figure of her son behind her, with inscription beginning at top of wall, (lwt-f ms-t sq m;; Hr-St and other titles of queen mwt msw nswt) msw-s n(nswt bity) Hwfw: probably from facade panel south of doorway to a, with the two girls of frag. (d) to the left of this block.
 - (m) 24-12-1001: block of stone, 56 cm. high and 35 cm. wide, broken away on right side: on face a register 48.5 cm. high with traces of a register above and another below: main register shows middle of papyrus boat on water, with man standing in middle leaning on staff, facing to rightbehind him a two storied crate containing ducks, and on the crate a heron stands facing right, above heron the word nw and behind this a broken sign with t under it: register above unintelligible: register below, a broken horizontal line of haeroglyphs ... s; ... m: A assigned to exterior chapel probably E wall of room b.
 - (n) 24-12-1125: frag. showing man squatting facing to right holding in each hand reed or twine, obviously making mat: subregister above mat, obscure.
 - (o) 24-12-...: frag. showing man seated facing to right, wik with right knee up and left leg half extended: arms obliterated but apparently extended: behind him a basket on a rectangular stand(?): surface in dront of man uninteligible: probably from swamp-scene from E wall of room b.
 - (p) 24-12-858: small frag. showing mat-skirt and part of legs of herdsman, facing right: assigned to E wall of room b.
 - (q) 24-12-938: small frag.: man in boat pulling oar: head missing.

"24-12-108, 24-12-109a, and 24-12-110," mentioned here are typographical errors for "24-12-1108, 24-12-1109a, and 24-12-1110." 111

facing to left/and probably from this wall:

124-12-852 and 860: two fitting fragments showing the feet
124-12-852 and showing

below a man carrying a jar raised in each hand and followed by a man with a games cooked goose and a cut of meat. The hand of a third figure carrying some object appears on the right. Fig.....

\(\sqrt{24-12-853}:\) fragment with the feet of a figure on the same scale \(\) Fig.

24-12-946: The back of a man on same scale as above, and a second figure reaching back as though to pull an animal (compare similar figures dragging an oryx in processions of offering bears). The second man is labelled: <a href="https://www.hm.ki.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.ndm.no.ndm.ndm.no.ndm.ndm.no.ndm.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.ndm.no.nd

North jamb of entrance door:

24-12-949: A small fragment with sloping border line and the hieroglyph r (title rp't?) from a large inscription. The other face of this fragment shows the border line of the scene on the facade on the north side of the entrance. No other fragments can be identified with the entrance door jambs.

Room b: A long north-south room constructed in the street against the casing of Ka-wab's mastaba, with its east wall built against the casing of G 7220. Entrance from room c on the north. The west wall includes the embrasure of the entrance to koom a, but the construction partially covers the scene on the north side of this embrasure. In this wall, north of the embrasure were two niches with emplacements in which probably stood the statues of Ka-wab as a scribe, fragments of which were found in the debris. The upper part of this wall is destroyed making it impossible to determine the height of these niches, or whether the wall above them was decorated. See Pl. 36 b and d.

Entrance embrasure to room a: north side of facade:

A large block with a sloping face evidently comes from here. It shows the back leg of a large striding figure of Ka-wab in a long skirt, facing left. He is followed by two small figures of men, attendants, or sons of the prince. The figures have been partially chiselled out and it looks as though this was the portion of the wall covered by west wall of room b. The front part of Ka-wab's figure with his names and titles (now completely destroyed) would have shown on the facade, after this alteration in the construction It evidently has to be assumed that the facade of the embrasure was already decorated when the decision was made to build the west wall of room b with its statue niches. The other walls of room b, c and the portico could have been commenced earlier, but the sloping casing of the mastaba front has been cut away to form a vertical wall, both in the west wall of room c, and in the backs of the statue niches. Also the west wall of room b would have been needed to support the roofing blocks. Therefore it looks as though the whole exterior chapel was planned as an afterthought when the inner offering room a had been completed and decorated. It is curious that the architect should have chosen to cover partially the facade relimits. See Pls. 36 b, d and 37 e, Fig.....

Southern facade of entrance embrasure.

24-12-1002: Block with sloping surface and border line on left.

Evidently from Surface and border line on left.

Evidently from Surface and border line on left.

west face of embrasure. Thigh of large female figure standing facing to right. In front of her: simt ntr Mrt-tf-s.

On the right is the hand of another large figure, drawn in such a fashion that the figure must be facing to the left.

This is unusual, but compare facade of G 7130, Fig....

I suggest that the title simt ntr is related to the Queen's

Horobean but he is probably bluebeing a find. man uninteligible: probably from swamp-scene: from E wall of room b.

(p) 24-12-858: small frag. showing mat-skirt and part of legs of herdsman, facing right: assigned to E wall of room b.

+24-12-991-6 Fig. (q) 84-12-938: small frag. man in boat pulling oar: head

APPENDIX B. p.11.

- (u).24-12-852, 860: two adjoining frags. showing upper part of one register and lower part of the register above: above, feet of amall standing figures: below, head and shoulders of two standing men: one man holds in in front of him a spouted jar and behind him a wine-jar the second man carries a haunch of meat on his shoulder and holds up appitted bird in right hand: all figures face to left: possibly from S wall of room b(see frags. (v, w, x).
- (v) 24-12-946: from one register: shoulder and back of man facing left, perhaps deriving an animal before him: behind him is written hm-k; in front of a second/facing left with arms thrust back as man pulling in oryx. assigned with (u) to S wall of room b.
- (w) 25-5-52: frag. of two registers: above feet of horned animal facing to left: below upper part of man facing to right sharpening knife, part of slaughter scene: assigned with (u) and (v) to S wall of room b.
- (x) 24-12-857: frag. of one register: part of slaughter scent with bull lying with head to right (tail and part of body): foot of man facing right and feet of another man facing left: unintelligible rectangular object on left: assigned with (u, v, w) to S wall of room b.
- (y) 25-2-313: two small fitting frags. part of scene showing men bringing down bull for slaughter: hind leg of standing bull with man close behind in peculiar attitude: on right another foot of man poised on toes: bull and both men face to right: unassigned.
- (z) Frags. with parts of large figures:24-12-988: portion of face and wig, facing left:
 24-12-855: frag. of wide necklace.
 24-12-1114: hand with staff, facing right.
 24-12-940: hand of figure facing left, perhaps leaning on staff.
- (aa) Frags. showing parts of small figures 24-12-943, 990, 853, 991b, 997, 993, 24-12-1109c, 989a, 1112, 989b, 984
- (bb) Unintelligible fragments: 24-12-945, 987, 998, 990B, D, E, F, 992: 24-12-941, 1099, 995, 1108.
- (cc) 24-12-999, 1124: two fitting frags.showing types of fow vertical lines of large signs facing to left:
 (1) wr
 - (2) nswt.....
 - (3) m.....
 - (4) hry-hb.....

probably from west wall of room a of E wall of room b.

- (dd) 24-12-1115: frag. of upper part of three vertical lines of large signs facing to right:
 - (1)
 - (2) nswt.....
 - (3)

assingnable to N, S, or E wall of room a, or S wall of room c.

(ee) 24-12-859: frag. part of one vertical line of large signs facing to left: reconstructed as (hmt-f mry)-t-f (s;t) nswt: from above wife's figure in chief scene: see (cc) above.

h man

title hrp simt and that we have here Ka-wab facing his mother the queen of Pyramid G I a. The parallel nearest parallel to such a scene would be that of Khufuw-khaf and his mother on the facade of G 7140 (See P₁....). See Pl. 37d, Fig.....

24-12-1000: This block is to be assigned with less assurance to the same facade space. Rigexexexexements an Kexther sangaextion that xthe xfacks af ye xempas xone that to the xone the xchecke kengx hexthexquenexenc24xt2ck008x The inscription on the right presents difficulties. Dr. Reisner restored it as follows based upon the inscription of Khufuw-khaf's mother: (mwt-f mst sw m; Hr Sth and other titles of the queen, mwt msw nswt) msw-s n (nswt bity) Hwfw. He would have placed it to the right of block 1002, believing that both figures on that block faced to the right. Fig...... is an adaptation of Dr. Reisner's reconstruction of the inscription to include that on block 1002. I believe that both blocks belong to the same figure of Queen Merytyetes. There does not seem to be room for newt bity in front of the cartouche of Hwfw. The sketched reconstruction lacks some twenty centimeters of filling the whole facade, and there may have been an inscription behind Ka-wab, or some small attendant figures. I consider this unlikely, however. Figs...., Pl. 37 a.

South Wall: A block which appears to be the thickness of the south wall (although it could possibly come from the upper part of the east wall)has the lower corner of a window opening into room b. It could be assigned to the east end of the south wall, high up in the wall. Continue last wife to the left of the window frame is part of the an inscription in relief which could form the label of anxattendanx an overseer standing in the corner of the wall beside the

East Wall: This long wall was decorated with scenes from life. The unusual thickness of most of the blocks makes it zertainchatxc probable that they came from this wall, built against the sloping casing of G 7220.

A thick block with the small end decorated with relief can be assigned to the south end of the wall. It shows the upper part of a long vertical inscription such as is usually placed in front of a large figure of the owner surveying the activities of his estate: m_1^* To the left of this is a bowing herdsman followed by the overlapping figures of three head of cattle. Thus it is probable that at the south end of the wall stood a large figure of Ka-wab viewing scenes on his estate, much as in the better known Dynasty V scenes which are found completely preserved for the first time in the rock-cut tombs of the Chephren family/but had been anticipated in the tombs of Raxhatapxand Neferma'at and Ra-hotep at Medum. The herdsman and cattle were in the top register of the wall, since the hieroglyphs on the right form the beginning of the vertical inscription. See Pl. 36 b, Fig..... If the principle signer have 24 the annex of

/late in Dyn. IV

frequent 24-12-940, see Fig.... 24-12-858: small fragment of figure wearing a herdsman's mat skirt. Probably from a similar register of the presentation of cattle.

assingnable to N, S, or E wall of room a, or S wall of

(ee) 24-12-859: frag. part of one vertical line of signs facing to left: reconstructed as (hmt-f mry)-t-f (s/t) nswt from above wife's figure in chief scene: see (cc) above.

80

020

Atlas III,

1/24-12-1001: Thick block with part of swamp scene on end. The main register preserved shows man overseer leaning on his staff in a boat returning from the swamps. Behind him a tame heron stands on a crate filled with captured ducks. Over the heron is a partially preserved inscription. Whether the nw is a label for the heron meaning 'hunter', or whether it making continued by the two signs on the left in some phrase like acceptate those over the bird trapping scenes in the tomb of Ti, I am unable to determine (cf. Wreszinski fiffxx Pl. 75). The interestion hieroglyphs in the register below are part of me horizontal inscription which was probably over a fishing scene, although the phrase also seems to signify bird catching. It is to be restored:h;m m (mh.t ?)... (°f. Montet, Scenes de la Vie Privée, p. 47. Wikhathisekensstars The traces in the register above the boat are not easy to interpret, but seem to be part of the horn or tail of an animal being slaughtered. Since some other fragments mentioned below with details of a slaughter scene have a base line of the same width, I would group them together and place them in aexappers this upper register. See Pl. 37 g, Fig....

24-12-1184 and a large fragment which probably fits with it. These show a seated figure probably cleaning a bird (cf. Wreszinski, Atlas III, Pl. 81 for a similar figure). Certainly this figure is part of the swamp scene, either in the same register with the boat, which probably also contained a bird trapping scene, or adjoining the fishing (or bird trapping) scene in the registe below. See Fig..... Pl. 37 &.

24-12-1126 plus 1109c and 989 a. These fragments which perhaps fit together are similarly to be placed in relation to the swamp scene. The man is probably making a mat.(cf Wreszinski, 1.c., Pl. 89). See Pl. 37 d, Fig.....

25-23131: Two fitting fragments showing feet of men and leg of a bull which they are evidently pulling down for slaughter. The earliest known example of this scene hitherto was in the rock-cut chapel of Nebemakhet (LG 86). Compare also Wreszinski, 1.c., Pls. 59, 86. See Fig.....

24-12-987, 997, 993: three fragments with a similar base line and unintelligible shapes in the register above which may be parts of slaughtered oxen. The head of man in the register below appears on one piece. See Fig....

24-12-857: The feet of several man and the tail of a slaughtered bull appear on this block, but the base line may be wider. It is badly obliterated. See Fig....

24-12-1112: The heads of two small male figures on the same scale as the figures in the slaughter scene. See Fig.....

1/25-5-52: Block with part of two registers divided by a base-line narrower than on the preceding fragments, and therefore perhaps from another wall. Below, a man sharpening a knife and above the legs of a walking animal. Possibly from north wall of room a or south wall of room b. See Fig.....

both from max a scene with men rowing a boat. Possibly from this same east wall, but perhaps from the space over the down with seast wall of the continuous of the continuous

Note: The red outline represents the edges of a typewritten piece of paper pasted on top of this page. Underneath the paper this page is blank.

Note: The red outline represents the edges of a typewritten piece of paper pasted on top of this page. Underneath the paper this page is blank.

Room b: north wall: there are no fragments that can be assigned definitely to this wall. See 24-12-855ā below

Doorway from b-c: west jamb: Large standing figure of Ka-wab facing out to right:

24-12-1128: From northern edge of jamb with border down right side. Arm and hand of prince holding staff, and above his name: K:-w!b. See Pl. 37 d. Fig.....

On the other face, (south wall of room c) border down left side of wall, and hanging open hand of a woman's figure facing to right. This was evidently a figure of Ka-wab's wife or mother. See Fig.....

J24-12-855 a: From left edge of jamb with painted block border down har left side and hanging hand of prince holding handkerchief. The other face (north wall of room b) has simply a fragment of the painted block border which would have framed the door. Fig.....

Room c: For south wall, see above. The figure of the woman manths adjoining the door could represent Ka-wab's wife, Hetep-neres, maxisteevaldokekhiexauther or it could be his mother, Merytyetes. The woman could be standing behind Ka-wab, or facing him.

North wall: no fragments can be assigned definitely to this wall.

East well: There may have been a single standing figure of Ka-wab on this wall. This might explain the following fragment if the pr_ince's name were in the upper left-hand corner of the wall in front of him:

24-12-854, perhaps fitting 24-12-947: The space at the left half-bear shows plaster where it had been covered by the thickness of a wall. The inscription reads s: K:-w;b. There appears to be no room for s; nswt. Fig.....

Doorway between portico and room c (descending ramp): Two fragments which evidently form part of a large figure of Anubis with accompanying inscriptions as on the entrance jambs of Khufuwkhaf (Pl. 43 and Meresankh III(Pl. 63).

24-12-1125: Tail of large crouching jackal (Anubis)
and beneath it a horizontal inscription: wer sost
hr ntr for ... From regelectores west jamb of door.
Fig....Pl. 37 d.

✓ 24-12-990 c: Paw of crouching jackal from east door jamb. See Fig....

Portico: Fragment 24-12-861: From top corner of a pillar: shows two lateral surfaces at right angles. On each face is a raised borderat top and down the edge. On the left-hand surface is the end of a horizontal line of inscription: (s! nswt n) ht-f with signs facing to left. This could be assigned to the SW corner of the east pillar, assuming that the columns were only decorated on their inner and southern faces, or to the NE corner of the west pillar if they were only decorated on the inner and north faces. It is improbable that the sides facing the sloping casing of the two mastabas were decorated.

There remain a number of fragments, some of them bits of inscriptions to which no location can be assigned, part of them wholly unintelligible pieces. These are listed as follows:

24-12-1117 e which perhaps is part of 24-12-1122: The name of Ka-wab written vertically with signs facing left. Underneath this a sign facing right and thus belonging to another inscription: s;. This arrangement is hard to explain. Fig.....

√24-12-942: part of two vertical lines of inscription. That on the right perhaps contains the name <u>Htp-hr</u>s, the wife of Ka-wab represented in the tomb of their daughter Meresankh III. Fig...

 \cap

APPENDIX B. p.12.

- (ff) 24-12-854: frag. the left side of which has been covered by masonry: large hieroglyphic signs facing to left: the wame K; -wcb written horizontally with traces of titles above: probably from front of face of large figure on E wall of room c.
- (gg) Small fragments from inscriptions:-

24-12-997: cw-(t): vertical. 24-12-937: frag. from the front end of a register of of figures facing to right: a vertical line of signs endingr with plural signs.

24-12-939: part of the name of Ka-wa'b written vertically.

24-12-947: and another farg: each with the word s; "son".

24-12-1122: sliver of stone with vertical signs: above (K)?)-wcb (man squatting and letter b) and facing to left and below the b a goose (s;) facing to right.

24-12-942: frag. with vertical line in relief with illegible signs on right:

24-12-991: ... n rvertically. 24-12-987: with h;(1000).

24-12-990: is (papyrus roll):

"36-3-364" mentioned on this page is a typographical error for "36-3-64."

 \rightarrow (hh) 36-3-364: frag. from a corner with border on each side of corner: probably from S side of ka-door in room a: on W wall south of niche, knees of standing figure facing to right: probably with second figure behind him: border in front and signs(?) behind chiseled away: on other face, the side of the outer niche traces of another standing man facing in to right extended out, holding strip of linen in right hand extended out behind: probably another strip in extended left hand held out in front.

Statues in Chapel G 7120:

A mass of fragments of statues and statuettes of granite and diorite were found in the debris of the nearly destroyed exterior in avenue 2, south of the chapel: of these six were inscribed with the name of Kawa'ab:

- 1) 25-1-393: squatting scribe, lower part, diorite: width, 52xxxxx: 28.5 mm.: h., 19.5 cm.: inscribed on lap, iry pcty s; nswt x;-wcb: from shaft G 7111 B: a smaller frag. under 25-1-392. Smith 1.c., P1.10.
- 2) 34-4-1: squatting scribe, lower part, diorite: width, 52 cm.: height 32 cm.: inscription on belt, wr md smcw K;-wcb: inscription on lap, dy nswt htp 1000 bread, beer, cakes, ointment, linen, cattle, and birds rc nb n wr md smcw KJ-wcb: inscription on top of basis,(r)pcty(?) s;-1 smsw wr md smcw/K;-wcb: found beneath roofing slab of portico d of chapel just outside portigo. Smith L.C., Pc-/o

/wr md

- 3) 24-12-467: standing or seated figure, diorite: right side of basis with part of left foot, bottom of basis polished: height of basis, 8.5 cm.: inscription on top, hity c Ki-wcb: Avenue 2, south of G 7120 exterior chapel.
- 4) 25-1-1313: standing or seated figure, diorite: xightxsidexm1 hasis left hand corner of basis bottom of basis polished: height of basis, 8.6-8.8 cm.: perhaps from the same statue as No.3: found in G 7111 D: The cribed on top of bacis:wcb.
- 5) 24-12-978: frag. from left side of basis, diorite: inscription on top, K;-wcb: found in exterior chapel room b. prove that at least five statues of Prince K;-wcb stood in his exterior chapel: two niches in W wall of room b, north of doorway to a, show emplacements for four statues, probably squatting scribes: in addition the following fragments were

Lonson bed [k3]-web:

```
Note: The red outline
represents the edges of a
typewritten piece of paper
pasted on top of this page.
```

Page 12. $\sqrt{24-12-\ldots}$ the single sign s; , facing left. Fig.... $\sqrt{24-12-991}$: two large signs reading : <u>nr.</u> F.g.... √24-12-1117 c and d: two fragments with titles of Ka-wah. One with nswt and the other with . Dw:w. Fig..... ng to deam 24-12-997: part of an unintelligible inscription. See Fig.... WITH Tage 1 1 Trge /24-12-996: Fragment of another unintelligible group of signs. Fig.... of Chan 24-12-1109 d: Fragment which appears to sent represent the shoulders and neck of an animal wearing a collar. Fig.... Fig.contains thirteen fragments which are almost wholly unintelligible of Nos.: 24-12-945(perhaps part of a large human figure), 1109 e, 990 d, 855 b, 990 b, 990 e, 984(two) 990 f, 992, 941(perhaps part of the wig of a figure), 1117 e and 998. In addition there are a few other fragments which have not been 24-12-1122: sliver of stone with vertical eleman illustrated: above (Kir) web (man squatting and Instar b) and mod demon 24-12-943: feet of a small figure, facing right. 24-12-989 b: back of woman's figure and hanging hand, facing right. 24-12-944: unintelligible 24-12-862: unintelligible. 24-12-995: perhaps part of an inscription, but unintelligible. The above pieces are all part of the reliefs of Ka-wab, but there were some other fragments which probably had been scatterd from tombs of the later Old Kingdom. They cannot have come from Ka-wab's chapel, althoung in side n a: they were found in the debris of the street in front of it or on top of the mastaba. These are: nd away: 24-12-564: Small piece with the title to hr newt. Signs face left, a breder down the right side and a straight line across the top of the signs. From debris between 7120 and 7130. es of but, 86 number. Two pairs of overlapping male figures, evidently the bearers and from a carrying chair scene, and probably a Sixth Dynasty piece. From west of G 7120 24-12-1183: men pulling flax, found in pit A of the mastaba. 24-12-1185: men pulling the cord of a bird trap. Also from pit A. Statues in Chapel G 7120: A mass of fragments of statues and statuettes of granite and

diorite were found on the debris of the nearly destroyed exterior chapel and in the debris of the street north of the chapel and in avenue 2, south of the chapel: of these six were inscribed with the name of Kawa ab.

1) 25-1-393: squatting scribe, lower part, diorite: width, \$2xmxx: 28.5 mm: h., 19.5 cm.: inscribed on lap, iry pety s; nswt k;-wcb: from shaft G 7111 B: a smaller frag. under 25-1-392. Smith 1.c., P1.10. (13 atm)

(Black granite?)

(2) 34-4-1: squatting scribe, lower part, diorite: width, 52 cm.: height 32 cm.: inscription on belt, wr md smcw K;-wcb: inscription on lap, dx nswt htp 1000 bread, beer, cakes, ointment, linen, cattle, and birds rc nb n wr md smcw K;-wcb: Bolon inscription on top of basis,(r)pctg(?) s;-f smsw wr md smcw/K;-wcb: found beneath roofing slab of portico d of chapel just outside portigo. Smith L.C., 16.10.

√3) 24-12-467: standing or seated figure, diorite: basis with part of left foot, bottom of basis polished: height of basis, 8.5 cm.: inscription on top, h;ty-c K;-wcb): Avenue 2, south of G 7120 exterior chapel. PLIL (4/4)

Balm 4) 25-1-1313: standing or seated figure, diorite: rights land of pasis bottom of basis polished: height of basis, 8.6-8.9 cm.: perhaps from the same statue

his exterior chapel: two niches in W wall of room b, north of doorway to a, show emplacements for four statues, probably squatting scribes: in addition the following fragments were

Mound

APPENDIX B. p.13.

found in this chapel:-

Note: there is nothing written on

the back of this page.

6) 24-12-931+978: six frags. from shoulders, left arm and torso of statue of large statuette about 1/4 life-size, diorite: exterior chapel. Pl. 16 (4/6)

7) 24-12-978: 342 fragments, many of them mere splinters of statues and statuettes: mostly of diorite (light translucent and dark translucent) but a few of granite: found on or just above floor of room c and portico: chief frags., as follows:

(本) front corner of right side of full wig, diorite. 化小线

b) frag. from leg below knee, diorite.
c) frag. from leg above ankle, diorite. (2016 %)
d) first and second toes of left foot, diorite, perhaps part of 24-12-621a; fits 24-11-978q, to form part of left foot. Pl 1b(3/5)

e) frag. from fragments to frage to the frag problem 10x 3.2 x 4.5 diorite. Pl.16 (3/3)

f) frag. from back of shoulder, 10.8 x 8.2 x 7.8 cm. diorite. [2.16(Vi)

g) frag. from leg above ankle, 7 x 5 x 7 cm.: diorite.

(h) fragment of left leg placed forward with part of its support, 10.4 km. long: diorite. Pl. 16(/6)

√ #) frag. of right foot with roots of toes: life size;
diorite. P0 1 b (3/4).

(k) frag. of left hand open on knee of seated statue; width of hand, ca. 5.6 cm.(ca. half life size) diorite. Pt. $1 \times (3/1)$

1) frag. from wrist of statuette similar to (k):diorite. m) frag. from lower part of face showing mouth, left cheek, and bit of nose, about same size as (k) and (1): diorite. Pl. 1 b(3/8)

n) frag. from ankle, nearly life size: diorite. [2] o) frag. from outside of right ankle: ca. life size:

diorite.

frag. of left leg above ankle, and nearly life size: diorite.

√q) see fragment d,

'r) frag. of knee: diorite. Pl. 1b(2/1)

s) frag. inside of leg and edge of skirt: diorite.

t) four small frags. of full wig, life size or nearly life size: diorite. fl 1 b (2/7-10)

frag. from wig of a different statue, about same size as (t): diorite. Pt. 16(2/6) **(u)**

 \sqrt{v}) see No.6 above.

These fragments indicate several statues and statuettes, life size and about half wire life size which were smashed in the exterior chapel and probably separate represent figures of Kajwa'ab standing, seated and squatting.

- \ 8) 24-12-621: nine frags. of which only three were of recognizable form: diorite: (a) frag. left foot without toes see No.24-12-978 above: life size or nearly life size; (b-c) two fragments of one side of an arm; found in debris over destroyed S wall of exterior chapel.
- $\sqrt{9}$ 24-12-827: frag. from right foot of standing statue perhaps same as 24-12-621a: diorite: found in debris of plundered shaft G 7120 X intruded S of chapel in Ptolemaic-Roman Period. Pl- 16(1/2)
- tot $\sqrt{10}$) 24-12-980; ten frags. of statues of black granite; found in rooms c and portico d: (a) frag. from inside right elbow of seated statue, about life size: (b-c) tow joining frags from inside left elbow of same statue. d-h) six frags., wig, breast, etc. probably from same statue. Same Photo C 11048.

typographical error for "24-12-978."

"24-11-978" mentioned here is a

1 PQ. 16 (1/2)

APPENDIX B. p.14.

- / 11) 24-12-1105: small squatting scribe, breast to legs: total height of figure ca.15 cm.: translucent diorite: skin painted red: found in debris immediately north of portico. P(14(34)
 - $\sqrt{12}$) 24-12-1181: five frags. of diorite statue or statuette: found in thieves hole broken in floor of passage from d to c.
- not deann 14) 24-12-979: eleven frags. of red granite statue: found in debris of rooms c and d.
 - Vertically in front smr wety n mrwt: found in debris of Avenue 2 south of G 7220: black granite. Pe Ib 4/2
 - Conclusion: the exterior chapel of Prince (Rawa ab had contained 10-20 statues and statuettes exposed to view, 4 in recesses in the W wallof room b and the rest standing on the floor in rooms b and c and in the protico d: figures standing, seated or squatting were of different sizes from 1/4 to full life size: one large figure had a small figure beside it (see No.12, above).
 - Chapel: G 7110: built in recess broken in SE corner of old core G G 7110: bonded with white casing: belonged to the wife of Prince Ka-wa'ab who according to G 7530 was Hetep-heres II, daughter of Cheops. schapel almost completely destroyed, but remains of deep special niche at south end of W wall shows an interior chapel of type (3a) similar to chapel G 7120 but slightly smaller measurements not to be fixed: in the street east of destroyed stone chapel, a stone pavement extending to about 5.5 m. N of chapel with remains of c.b. walls built on it.

Decoration of Chapel G 7110: six fragments of relief found in debris of chapel:

1) 24-12-1107: chief figure, woman seated on chair, lappet wig and long tunic facing to right: right arm bent at elbow: back of head, body, and upper part of chair.

- Seafig...., PQ.376.
 2) 24-12-1097 small frag. of inscription, sm;-t nb(ty) mryt-f (?): with vertical line on left: probably from figure of mother. signs facing to left. Sue Fig. ...
 - 3) 24-12-1101: frag. of inscription, parts of three vertical lines: (1) (r)dyt sy
 - (2) $(r) m!! \dots :$
 - (3) hm (ntr) pr

cg. inscription of Khemten on S jamb of G 7530: signs facing to left.

- 4) 24-12-1095: small frag. from outer edge of sloping N doorjamb: border down right side; to left of border,t and head of small figure facing to left, below the t:
- $\sqrt{5}$ 24-12-1100: frag. showing lower and legs of two female figures bearing offerings (estates?). facing to left.

24-12-+852C

6-8) three small fragments: See Fig....
24-12-1098: bears portion of a necklace fully let will 24-12-

24-12-1096: With single sign s: facing to right. 855
24-12-1099: bit from back of Wig of a figure.

I reconstruct this chapel as having been prepared (perhaps not finished) for Hetep-heres II, at that time bearing only the titles of a king's daughter. The Fragment No. 2) indicates that a gueen appeared in this chappen, consumer The mother of Ka-wal as shown in his own chapee, whose manus

Shafts: four shafts, two in G 7110 and two in G 7120: In G 7110, shaft A on N and shaft B on S: in G 7120 shaft A on N and shaft B on S: the two shafts G 7110 B and G 7120 B were the original shafts in the nucleus corest shafts G 7110 A and G 7120 A were made after the twin core was constructed: G 7110 A and G 7120 B were never excavated in rock: G 7110 B was intended for the wife but never finished or used: G 7120 A was completed and used for the man.

Shaft G 7110 A: two meter shaft lined with large nummulitic blocks ending at rock surface: ca. 4.5 m. deep: type 7 X: unused.

Shaft G 7110 B: 1.9 x 1.8 m., -9.8 m. in rock: lined through mastaba with heavy nummulitic masonry, 4.45 m. (5 courses): Chamber: type 3 a(f): on S: 4.5 x 5.0 m.: h., 3.5 m.: area, 22.25 sq.m.(unfinished): capacity, 77.87 cu.m.

Passage: 2.1 x 1.1 m. with height of 1.42 m.? maxkragexef burial

No trace of burial: debris, dirty rubbish and sand: In debris of chamber, frag. of alabaster statue and small alabaster model saucer, both intrusive.

Shaft G 7120 A: burial shaft of Prince Ka-wa'ab: 2.05 x 2.0 m., -10.4 m. in rock: lined with massive masonry, 5.5 m. (5 courses): turning recess in N wall of shaft at bottom, 1.05 x 1.85 m. and 1.35 m. high with horizontal roof: and 1.35 m. high with horizontal roof:
Chamber: type 3 cf: on S: 5.0 x 5.0 m.; h., 3.5 m.; area,
25/sq.m.; capacity, 87.5 cu.m.;
Passage: 2.0 x 1.35 m., and 1.57 m. high: in E side of passage

the passage, opens the lower end of a sloping passx passage (constructed later) which descends from an opening in the floor of the street east of the mastaba, and slants to the WSW: length of sloping passage, 20.4. m.: passage, 2.2. m. wide and 2.3.7 m high: blocked with plug stones (still in place)

Coffin pit: along W side of chamber, 2.4 x 1.2 m. and 0.75 m.

desprecess for coffin lid in W wall at top of

coffin: red granite coffin, 2.25 x 1.0 m., and 0.9 m. high: cavity of coffin, 1.85 x 0.65 m. and 0.66 m. deep: with lid; coffin type d: west side of coffin and lid broken but practically complete: sunk in burial pit to bottom of horizontal inscription: inscription horizontal line on each of four faces of bom:

(1) E face, beginning at N end, dy nswt Inpw htp hnt sh ntr krs m hryt ntr m smyt imntyt ijw nfr s; nswt n ht-f kj-web: (2)

(2) W side, badly broken, dy nawt Inpw htp jint sh Cairo

m nb im;h hr ntr c; K;-wcb, beginning at N.

(3) S end, with signs facing to right, s; nswt n
 ht-f smsw (priest of Anubis), K;-wcb.

(4) on N end, signs facing to left, broken and only

a few signs recovered,hm ntr srkt...... signs painted green in shallow cutting: signs outlined in black.

Canopic recess: in S wall near SE corner: 0.7 x 0.7 m. and 0.6 m. high with rebate around mouth.

Shaft and chamber filled with drift sand which contained Ptolemaic potsherds and frags. of faience amulets: the chamber was probably blocked with masonry and a portcullis slab: in the sloping passage thieves had cut away one side of the plug stones to gain entrance to the burial chamber and in this thives passage were found four fragments of a diorite statue: the opening in the street had been covered by a stone pawement (broken by thieves) and south of it were found fragments of limestone reliefs and a flint flake.

wise there this mate of AF/GAR Height is shown perpendiculor.

to the persuage

Occarding to tom. cord south west port coeffin is Broken away.

Seven alabate venes as follow.

1 model of tyh.


24-12-203, type IX a

24-12-260 "

1170 2m glado g Tupe Xa Judoy

1171 Xb Shaft 7110 B

7 listed under street on p. 269



Jon debris of chamber 6 alabaste saucers of pag. of alabate statue (intresive). these bessels has IX a, h. 1.6 cm., diarm., 5.6 cm.

24-12-26a Malab model saucers has IX a, h. 1.6 cm.; diarm., 5.2 cm.

24-12-16g)

(c) h.1.2 cm.; diam., 6.6 cm.

24-12-116g)

(c) h.1.2 cm.; diam., 6.6 cm.

24-12-116g)

(c) h.1.2 cm.; diam., 6.6 cm.

24-12-116g)

(d) h.1.2 cm.; diam. base, 4.6 cm. has a later, 2 model occasels of type X a.

(e) h.1.2 cm.; diam. has a later, 2 model occasels of type X a.

(f) h.1.2 cm.; diam. has a later, 2 model occasels of type X a.

(e) h.1.2 cm.; diam. has a later, 2 model occasels of type X a.

(f) h.1.2 cm.; diam. has a later, beautiful occasels of type X a.

(e) h.1.2 cm.; diam. has a later, a later has a later, beautiful occasels of type X a.

(f) h.1.2 cm.; diam. has a later has a later has a later, a later has a

APPENDIX B. p.16.

Shaft G 7120 B: 2.1 x 2.08 m., -3.65 m. in rock: lined with massive nummulitic masonry, 5.0 m., (6 courses): type 7 X: three unfinished cutting in rock part of shaft (probably of the Ptolemaic-Roman Period: found filled with dirty sand: had been cleared out recently and refilled.

Later Constructions:

against the N end of the twin mastabas were built G 7101, and G 7102 the mastabas of Qa'ar and Yeduw of Dyn.VI; against the E face north of wife's chapel, was constructed the mastaba, G 7111 and north of that G 7112; south of the man's chapel was excavated the intrusive shaft, G 7120 X but not finished.

Pl. 38b, c, d. 39, 40b, c, d.

G 721047220: twin mastaba of Prince Hordedef and his wife (name not recovered):
second of the four northern twin mastabas counted from the
west.

See Figs..... Plan & Section done A. F.

See Pls.....

Owner: Hordedef, ...

Mastaba: core of massive masonry composed of the old cores G 7210 and G 7220, connected by massive masonry, and altered for interior chapels (cf. G 7110 + 7120): massive core, 81 x 17 m.: area, 1377.0 sq.m.: propp 1/4.73: near the S end of the E face of G 7220 a hole was broken and lined with masonry (as G 7120), a recess to take an interior chapel: at the SE corner of the old core % 7210 a hole was broken to receive another interior chapel: the core was cased with fine white limestone(x-masonry and bonded with it, two interior chapels of type (3a): the cased mastaba mesured 83.2 x 19.35 m.: area, 1592.5 sq.m.: prop.1/4.25: geight,m.: G 7210, 4.27m: height G 7220, 5.4m.

Mason's Marks and Quarry Marks on Core and Casing of G 721047220:

On the massive core, on the W side two horizontal levelling lines were partly perserved: the lower line was mark "ell 2" and the second line was two ells (1.05 m.) above it: these lines were crossed at irregular intervals by three broad vertical bands (ca.5-7 cm. wide), the purpose of which was not descernible.

On the inside of the white casing blocks (next to the core) a number of blocks were found to bear quarry marks in black or red: ll on E, 4 on S and 6 on W, total 21 blocks: most of the marks were unintelligible but three blocks on the E casing bore the name hr-nbty Hr thw cprw ("the working gang Cheops-is-drunk").

Chapels: two interior chapels of white limestone bonded with casing, each with subsidiary N niche in casing.

Chapel G 7220: Prince Hordedef: interior offering room (a) of type (3a) built in recess constructed in old core 7220: special deep niche at S end of W wall: badly destroyed but ka-door preserved to top of tablet, end of W wall, and N doorjamb in place: (a) 4.15 x 1.65 m.; area, 6.84 sq.m.: prop.1/2.51: the outer recess of the special niche measures 1.2 x 0.25 m. and the inner recess measures 0.7 x 1.05 m.; height of inner

APPENDIX B. p.17.

recess, 2.35. m.: entered by doorway in N end of E wall opening in embrasure in sloping face of casing: no exterior chapel preserved.

- Decoration of chapel G 7220: room a, by W.S.Smith:
 a) Ka-door and adjoining W wall on south: on back of deep innerxmit niche, the prince seated facing to right at table of bread(?) on each side wall of the inner niche are four figures of men facing in: on N side, one feet of figure preserved: on the S side, the outer figure holds out his hands in front of him and the other three appear to be carrying illegible objects: Drum: horizontal inscriptions only partly legible,
 - Cross-bar: words written vertically, dy nswt htp dy Inpw htp krs nb im; h hr ntr c; s; nswt n ht-f hcty-c imy is iry Nhn Hr-dd-f.

Tablet: traces on left of seated figure facing right: right side appears not to have been finished.

Back of outer recess: on each side one tall bowl stand with bowl, takes full height of the narrow panel.

Outer recess, sides: on N, destroyed: on S two registers with one figure each with one or two registers above now destroyed: figures face in to right: upper figure with mrh-t written in front and below this hm-k; the lower figure carries indeterminable object in left hand and a case (?) over his right shoulder; in front of the word smsw.

L his face

- W wall south of offering niche; remains of one register probably with 2-3 registers above: man facing in to right carrying birds in each hand; in front of him vertically, it -t ; pdw.
- b) Displaced fragment, 24-12-1129: long block found in street probably from upper part of N wall of room a: on left border and to right of it upper ends of five vertical lines with large signs in relief facing to right:
 - (1) hcty-c iry (Nhn).....
 - (2) hr hry.....
 - (3) imy-r; k;t....
 - (4) cd whc....
 - (5) s! nswt.....

probably stood over standing figure of Hordedef facing to right: the inscription would have taken 71 cm of the width of the N wall measured from the corner: the space in front of thi the figure whether blank or in relief would have been covered by the wooden door when open to a distance of about 110 cm. from the eastern side ...

The reliefs on the ka-ddor had been chiseled away but could be followed in outline: the signs on the loose block had not been chaseled away.

Chapel G 7210: Wife's chapel: offering room(a) and exterior c.b. chapel with of six rooms: (b-g):

a) Interior chapel of type (3a) of white limestone built in hole broken in old core G 7210; bonded with white casing chapel badly destroyed but ka-door of special form at S end of W wall preserved to a height of drum(h.ca.2 m.) line of S wall marked on slab south of niche: stone in place marks N end of room: 4.3 x 1.6(?) m.: area, 6.88 sq.m.: prop.1/2.67: the outer recess of the special niche niche measures, 1.2 x 0.3 m.: the inner niche measures. 0.6 x 1.1 m.: height of inner recess, .2.39 m.: entered by doorway at N end of E wall, opening in embrasure in sloping face of casing. hole for door socket inside doorway on N.

APPENDIX B. p.18.

Exterior c.b. chapel with six rooms, b-g:consisting of one large room or open court surrounding doorway
to room a, with stone platform set in c.b. walls in SE corner,

and five smaller rooms on N:-

made in the E wall of room c.

b) measures including stone platform metxinxexbxxwallxxxeexxinxexbx malisximxSExcormerxxandxfivexxmaxidexxroomsxonx, 7.65 x 2.9 m. area 221 22.18 sq.m.: in the SE corner was a small c.b. room which measured outside, 2.7 x 1.8 m. (area, 4.86 sq.m.) and was apparently originally intended as a magazine(?) with doorway in its N wall: inside this room was inserted a limestone platform, 2.3 x 1.5 m. (area, 3.45 sq.m.): with low parapet on the E, N and W sides: platform inside the parapet > measures, 1.9 x 1.75 m. (area, 2.13 sq.m.): drianage groove descending gently from N to S atround which the floor sloped gently down to the Lchapel: at the S end, the Lchapel lead to a stone culvert under the c.b. wall which in turn emptied into a large stone tank in the street south of the chapel: tank, 0.85 x 1.15 m. and with walls about 5 cm. thick: h., m. and depth, m. room b was originally entered by doorway from E which was afterwards blocked with c.b.: afterwards the room was entered by a doorway in E end of N wall which had existed previously giving access to room c: at this time the later entrance was

[On version 1, the measurements in this line are crossed out and replaced with]
1.9 x 1.15 m. (area 2.18 sq. m)

- c) north of room b had been a room with doorway to e in E end of its N wall: this room was separated into two small rooms by a N-S wall with a doorway: the eastern small room is lettered c and the western d: room c thus became a vestibule when the entrance was made from the outside in its E wall: 2.07 x l.lm area, 2.28 sq.m.: four doorway, to b in S wall, to d in W wail wall (S end), to e in N wall, and entered from outside by doorway in N end of E wall.
- d) see c, above: 2.1 x 1.5 m.: area, 3.55 sq.m.: entered from c by doorway in S end of E wall: perhaps a magazine.
- e) north of rooms c-d, a space 4.4 x 3.05 m. (area, 13.42 sq.m.):
 which contained remains of c.b. walls apparently dividing the
 space into threex rooms, e,f, g: in the N wall was a doorway
 giving access to the whole chapel from the N (see room f,
 below): room e appeared to measure 2.25 x 3.05 m.: area, 6.86
 sq.m.: in E end of S wall doorway to room c: in N wall
 apparently two doorways, one to f and the other to g.
- f) see e, above, eastern part of space north of e: 1.75 x 1.75 m. area, 3.06 sq.m.: separated from g by thin intrusive wall: doorway to e, in E end of S wall: entrance from the outside in W end of N wall: this doorway was afterwards blocked with masonry when the mastaba G 7211 was built.
- g) see e, above: west of f and separated from it by thin intrusive wall: 1.75 x 1.1 m.: area, 1.92 sq.m.: apparently entered from e by doorway in E end of S wall.

Size of whole exterior chapel, 18xx5xxxxxxx 16.45 x 3.5 m.: area, 57.57 sq.m.

Total floor area, b-g, 40.45 sq.m.

Total floor area, a(6.88 sq.m.) and b-g, 47.33 sq.m.

The first entrance was in E wall of room b: the second entrance was from the N in the N wall of room f: the final entrance after the construction of G 7211 was from the E in room c.

Decoration of Chapel G 7210: by W.S.Smith.

The slabs still standing in inner niche of the ka-door and the part of the W wall south of it were not decorated: four fragments of relief were found:-

1) 25-1-42: frag. white limestone, 28 x 18 cm., with signs in low fine relief, all facing to right: from an offering list in horizontal lines separated by lines in relief: upper register showsat bottom a row of **parasmall basins determinative of list above; in the second register from right to left, the word msdmt determined by pellet and the word dpt determined by three conical cakes, and both words are written vertically; below this under the raised line are two vertical lines

APPENDIX B. p.19.

- separated by a raised line and reading from right to left, (1) nswt s; (or s;t) n.....(2) wrts.....
- √2) 25-1-43, 44, 45: three frags. of the same character with unintelligible signs facing to right on one frag. and to left on the other two.
- √ 3) Fragments showing legs of large female figure with small child standing beside her. Found in debris of mastaba north of chapel. see figs.....
 - The conclusion is reached that the decoration of the room a was unfinished: at is possible that the tablet of the ka-door was the only part decorated (see G 4240): the four fragments xound found close together in the debris of the chapel indicate that on one of the walls an offering scene had been finished: the fact that the lower part of the ka-door and the rest of walls were left undecorated would not require any special explanation.
- Shafts in G 7210 and G 7220: the shafts were letter as in G 711047120, A, B in each core: but shaft G 7110 A was found never to have been made and G 7220 B never to have been made used: A on north and B on south.
- A on north and B on south.

 Shaft G 7210 A: a deep trench in the axis of the mastaba showed that the northern shaft had never been made.

area, 25.18 sq.m.: capacity, 85.61 cu.m.:

Passage: 2.15 x 1.12 m. and 1.35 m. high: remains of masonry blocking in passage and a portcullis slab outside, leaning out as displaced by thieves:

In the chamber fragments of white limestone coffin of type d: Canopic pit in SE corner, 0.45 x 0.45 m. with rebate sunk in the days edge on all four sides; and 0.55 m. deep.

In the disturbed debris in the shaft were Ptolemaic objects and grey granite hammer, at about 13 m down: at about 15 m. down were the fragments of a large flat bottomed basin of type D-XXXIV (red ware, red wash), with traces of plaster, used in sealing blocking:

no objects in chamber: chamber not reused in Ptolemaic times: late objects in disturbed filling obviously intruded recently.

aft G 7220 A: 1.85 x 1.95 m., -9.3 m. in rock: lined with masive masonry, 5.0 m., 7 courses: type 3 amx(stair) with additional room on S:

Main chamber on south of shaft, 4.86 x 4.86 m.: and 3.82 m. high: area, 23.62 sq.m.: capacity, 90.23 cu.m.:

Passage: 2.12 x 1.6 m. and 1.55 m. high, with four steps in chamber leading from floor of passage to floor of chamber: in passage remains of masonry blocking but portcullis slab had been broken up:

Unfinished red granite coffin along W side of chamber, 2.45 x 1.26 m. and 0.86 m. high (1.09 m. with the lid at the S end: cavity, 2.1 x 0.9 m. and 0.7 m. deep: dressed smooth inside and on four sides: the bottom of the block was being sawn off apparently to form a lid but broke in two and the southern half was left attached to the bottom of the coffin:on the dressed surface red guiding lines had been marked off to show the side of the box and of the cavity: on the eastern face a horizontal line below marking the line of the saw-cut at the bottom of the dressed surface and another parallel horizontal line above it to mark the bottom of the cavity: at each end was a vertical line marking the ends of the cavity inside: on this side two measurements in red paint were written as if the coffin has been standing upright on its south end and read to the left the coffin the coffin the cavity: a south end and read to the left the coffin the cavity: a south end and read to the left the coffin the cavity: a south end and read to the left the coffin the cavity: a south end and read to the left the cavity in the cavi

insert. Clabrate (520, A,B,CD. 25-1-518-521,522,A,B,CD. aft

Diene desert ich

APPENDIX B. p.20.

(actually 2.1 m.): on the eastern side only the horizontal lines are visible, one for the bottom of the cavity and a double line (about one cm. apart) to marke the line of the saw-cut: On each end were visible two vertical lines and one horizontal line: the saw cut shows that the lid was being sawn off by straight blades working diagonally on each side at the same time: the piece broken away was not found: the piece attached to the bottom on the south was not dressed and showed a rough ridge across the end (not a dressed rectangular end bar, but the usual rough ridge left on undressed blocks of granite brought from Assuan, made to facilitate handling (see Mycerinus, parks): I conclude that the lid was intended to be a plain flat cover as coffin type d: no trace of lid was found in the chamber.

Second unfinished chamber (intended for coffin room): doorway in E end of S wall, with floor sunk below floor of main chamber: 3.75 x 4.75 m. and 1.82 m. high: area, 17.81 sq.m.: capacity, 32.41 cu.m.: the vertical grooves in the S wall show that four workmen were engaged in cutting back this wall when the work stopped and leaving a heap of limestone rubbish on floor:

Passage: 4.8 x 1.05 m. and 1.2 m. high.

Total area of both rooms, 41.43 sq.m.: capacity, 122.64 cu.m. Filling of shaft: disturbed rubbish which contained Ptolemaic potsherds and 8 frags. of hard stone statue (24-12-292 to 295, 297, 298): the chamber had a heap of rubbish and sand sloping down on all sides: in the passage to the second chamber found fragment of seated diorite statue of Chephren (24-12-822). With this were frags.

not drawn XXXXXXXXX

24-12-823: base of RW jar of type A-II b.

24-12-824: frag. of RW model basin of type LXXIXa-m, diam., 10.4 cm.: h., 2.0 cm.

not diam. 24-12-825: frag. of small jar with roll rim.

24-12-826: frag. of jar of type A-II b.

In main chamber, frags. of stones and potsherds:-24-12-846: 4 frags. of alabaster of which only one had a dressed surface.

24-12-847: frag. of undressed translucent diorite.

24-12-848; 850: 9 flint flakes not worked. 24-12-865: frags. of RP pottery from bowls with recurved rim: types C-XXXII or D-XXXVI.

Shaft G 7220 B: 1.85 x 1.8 m.:-1.7 m. in rock: lined with masive masonry 5.0 m., 9 courses: unfinished cutting in SE corner at bottom, 0.5 x 0.5 m. and h., l.l m.: area, 0.25 sq.m.: capacity, 0.27 cu.m.: probably of much later date: shaft recorded as of type 7 X: filled with dirty sand and dust, dumped in recently.

Later Constructions:

Against the N face of the cased mastaba, was found the mastaba of Yeduw (G 7102) and a composite mastaba nearly destroyed east of it: against the E face north of the wife's chapel was G 7211: four intrusive shafts in street E of mastaba: G 7220 X: just south of chapel in street: G 7220 Y: adjoining X on South: G 7220 Z: near north subsidiary niche: G 7220 W: hatme between X and Z.

APPENDIX B. p.21.

G.A.R. Feb. 1941 says:

G 731047320: twin mastaba of Prince, perhaps Ra9Bauw-f and his wife: third from the west of the four northern twin mastabas. the West of the four norther see Figs..... Plan and section done. A. F.

Owner: Ra-bauw-f,

Mastaba: core of massive masonry composed of ald cores 7310 and 7320: connected with massive masonry and altered for chapels: core, 79.2 x 16.5 m.: area, 1306.8 sq.m.: prop.1/4.8: near SE, corner a chapel recess was reconstructed in the old core as G 7110+7120: hole broken in SE corner of old core 7310 to receive an interior chapel, as the two twin mastabas on the west: core cased in fine white limestone (x-masonry) and bonded with it two interior chapels of type (3a): the cased mastaba measured, 82.82x 19.0 m.: area, 1573.2 sq.m.: N.E prop.1/4.36: h., m.: inscribed lines on platform at NW corner: height G 7310, 5.32m: height G 7320, 5.45m.

Quarry Marks:

on backs of casing stones found 18 red quarry marks, all unintelligible, 11 on W, 3 on E and 4 on N.

Chapels: two interior chapels of white limestone of type (3a), bonded with casing) and east of each an exterior c.b. chapel.

> Chapel G_7320: man's chapel: interior offering room a of type (3a); built in recess reconstructed in core: with special deep niche at S end of W wall: badly destroyed but lower part of niche, one slab in W wall north of niche and N doorjamb found in place:

- a) 4.15 x 1.65 m.: area, 6.84 sq.m.: prop.1/2.52: outer niche 1.25 x 0.3 m.: inner niche, 0.6 x 1.25 m. entered by doorway in N end of E wall, opening in embrasure in casing: limestone door socket at W end of N door-jamb.
- Exterior c.b. chapel beginning in front of room a and continued southwards to avenue 2 in which the chapel continued eastwards south of G 7420 and westwards south of G 7320: consisting of 7 rooms, b-h but c-f were badly destroyed by sebakh digging:-
- b) one-room exterior c.b. chapel apparently open to the sky: 3.9 x ca.2.4 m.: area, 9.36 sq.m.: the remains consist of two c.b. long doorways, one at each end of the room or court but not exactly on the same axis line: the doorway to room a opens nearly in the middle of the western side of the room; in the SE corner of the room stands, partly sunk in the floor, a large rectangular offering basin of the ordinary form, 1.1 x 0.9 m., with hole in the S end opening in a stone roofed culvert which which passes under the S doorway and out into avenue 2 where it turns east to a point, 6.75 m. from SW corner of G 7410 120, where it emptied into a stone tank: in real room b in front of the doorway to a, a large Ptolemaic-Roman shaft, G 7320 X, has been intruded with its mouth near the top of the mastaba.
- c) corridor room south of b leading to a long doorway of c.b. between SE corner of G 7320 and the SW corner of 7420: 8.6 x ca. 21 2.4 at floor level: area, 20.64 sq.m.: doorway to b on north and doorway to d oh S.
- d) a N-S room south of c: nearly destroyed but indicated by frag. of thin W wall and by heavy S wall: 4.2 x 2.4 m. at floor level: area, 10.08 sq.m.: doorway to c in N wall: doorway to f in N end of W wall: opens into m e without doorway: at S end of d.

APPENDIX B. p.22.

- e) E-W vestibule corridor at right angles to d: foundations of thick c.b. wall preserved along the S side, 1.6 m. thick: 1.25 x 1.35 m.: area, 1.68 sq.m.: the c.b. wall on the N of room e and on the E of room d which rested on the masonry of the casing of G 7420 (SE corner) had been destroyed.
- The thick southerm boundary wall of the chapel was dug away by sebakh-digging south of room f: its foundation rose slightly from E to W and showed a thickness of 1.7 m. in rooms d, 1.65 m. in room g and 1.6 m. in room h: on the E this wall touched the casing of G 7420440 and on the W was separated 1.1 m. from the N end of the core of G 733047340.
- f) a great sebakh hole descended in the middle of the room and the size could only be reconstructed doubtfully: 3.475 x 2.95 m.: area, 10.25 sq.m.: entered from d by doorway takks at N end of E wall: appossize x khazen kranes x doorway to g in N end of W wall.
- g) well preserved to height of 0.8 m.:/plastered with whitewashed surface: 3.5 x 2.57 m.: area, 8.99 sq.m.: entered from f by doorway in N end of E wall: doorway to h in N end of W wall opposite the entrance.
- h) well preserved to height of 0.8 m.: plastered as g: 3.5 x 2.5 m.: area, 8.75 mq.m.
- The W boundary wall is 1.35 m. thick: the wall between g and h is 1.2 m. thick: the northern boundary wall was built over the dressed sloping casing of G 7320 being 0.9 m. as preserved, must have thickened upwards, perhaps to 1.6 m.
- I suggest that most of the rooms were roofed with c.b. waxx leaning vaults.
- East of room e, were found the remains of a c.b. wall built against the face of the E wall of that room: this indicates another corridor (i) added on the east and probably reaching to the face of G 7430: the drainage tank of the culvert leading from the basin in room b, was under the floor of this room: length of culvert, N-S arm, 17 m. ¡E-W arm, ca.6.75 m., total length of about 23.5 m., width of channel, 0.1 m.: depth ca.,0.12 size of tank, 1.1 x 1.15 m., with walls, ... m. thick, depth, ... m. with tunnel on W edge to admit the arainage from the culvert: tank sunk in c.b. kerb and probably roofed and covered by flooring of room i.

Floor area of chapel:
Room a(limestone), 6.84 sq.m.
C.b. room b-h, 69.75 sq.m.

Total area, a-h, 76.59 sq.m.: to which is to be added the unmeasurable room i.

Decoration of Chapel G 7320, room a:-

Lower part of ka-ddor of special form preserved, and lower part of of W wall S and N of niche: also lower part of N doorjamb: none of the stones in place are preserved to a sufficient height to show decoration: the wall north of niche appears not to have been decorated(?).

Fragments of White limestone with reliefs, found in debris in

interior and exterior chapel: /

1) 25-1-957 to 961, 967, 863, 755, 824: frags. assigned to architrave over doorway: parts of 22-24 vertical lines separated by vertical lines in relief: signs on 11 lines (from left half) face to right and 10 lines (from the right end) face to left: inscription thus divided in two beginning with an offering formula running to the left and another running to right: two inscriptions practicaly identical:

APPENDIX B. p.23.

- (1) (dy nswt) htp (inpw htp hnt sh ntr nb \$; dsr).
- (2) kr(s-t-f) m smyt(imntyt).
- (3) (nb) im;h hr ntr c; prt-r-hrw n-f (bread, beer, be birds and cattle?).

needs correcting

- (4) m wp rnpt Dhwtyt tp rnpt hb wr.
- (5) rkh prt-Mnnw s;d.
- (6) tp month and half month, (m) hb nb rc nb.
- (7) n iry-pcty sbhty (s;b t;ty) wsht shm ch;.
- (8) c; wnrw nswt....
- (9) hm ntr hnm n stp (s;).....
- (10) hcty-c iry Nhn m is
- (11) imy-r;(?).....
- (12) (s; nswt n ht-f and name). Knys sono) his body
- 2) 25-1-825, 862: two adjoining frags., from edge of N doorjamb, showing on left vertical face, on right surface a sloping face: on doorjamb showing sloping border and parts of four vertical lines of inscription (above a chief figure facing out to right):
 - (1) s; (nswt) n (ht-f)
 - (2)wr (pr) dw;
 - (3)r wh
 - (4)B;st(t).....

on the other surface from the sloping face of the embrasure panel shows on the left a border and remains of two vertical lines of signs,

- (1)tjty.....
- (2)hm ntr

these signs face to left and indicate a standing figure of the prince facing in to left.

- √3) 25-1-749 to 852: six fragments of a horizontal inscription with signs facing to right and assigned but not joining a seventh fragment with the sign f: s;-f Hnm-b;-(f) followed by hmw-k;: this inscription was obviously over a row of small figures facing to right of which the first was the son; The scene may have been the S doorjamb with son and other small figures facing in towards a large figure of the prince:
 - The decoration was probably unfinished: apparently the frags. show the decoration of the doorway (architrave, door jambs and embrasure panels: possibly the niche was also decorated.
- Chapel G 7310: wife(s chapel built in hole broken in old core:

 interior chapel of white limestone bonded with casing: with
 subsidiary N niche . 1.11 x 0.35 m. in outer recess:
 chapel. inner recess, 0.37 x 0.35m.
 - a) interior chapel of type (3a) with special deep niche at S end of W wall: 4.15 x 1.55 m., area, 6.43 sq.m.: prop.1/2.67: ka-door, outer niche, 1.2 x 0.3 m.: inner niche, 0.6 x 1.25 m.: built of three upright slabs roofed with a horizontal slab behind the drum(which was missing); all the rest of the bhapel was destroyed to

APPENDIX B. p.24.

the stone pavement and the plan as reconstructed from lines incised on pavement: doorway in N end of E wall opening in embrasure in sloping casing.

Exterior c.b. chapel of 5 N-S rooms: formed by dividing the place

- between G 7310 and G 7410, by 6 very thick c.b. doorways b) beginning just south of embrasure of doorway to room a and extending northwards: 7.9 x 2.6 m.: area, 20.54 sq.m.: northern part of floor paved with stone sill in doorway: bases of two columns in N-S line dividing the room into three parts: both had a circular basis, with diam. of 0.95 m.: on the S basis stood a column drum with a diam. of 0.53 m. and a height of 0.46 m.: this segment of the column was dressed so that it had eight slightly channeled surfaces, similar to Zoser channelled columns but of less pronounced form: the print on the N basis indicated a column of the same size: no evidence was found to indicate the form of the capital, but I would reconstruct with an architrave, either E-W or N-S: the roofing would probably have been stone slabs, although the use of mud-brick would suggest a wooden roofing: the doorway to room a opens in the S end of the west side; at the N and S ends of the room, a thick c.b. doorway, not on the same axis: the doorway on the S opens into room c.
 - c) 2.25 x 2.8 m.: area, 6.3 sq.m.: formed by two thick c.b. doorway, not on the same axis, of which one forms the S end of room b and the other the N end of room d: the eastern side of the S doorway has been damaged and repaired with rubble.
 - d) south of c and enclosing the subsidiary N niche of G 7320: 4.3 x 2.8 m.: area, 12.04 sq.m.: subsidiary N niche, outer recess, 1.1 x 0.35 m.: inner niche, 0.35 0.4 x 0.25 m.: c.b. doorway on N is the S doorway of room c: the doorway on S opens into the space between G 7310420 and G 7410420, and thus leads to the chapel G 7320: at some subsequent time the two chapels, G 7310 and G 7320 were separated by a c.b. wall 1.25 m. thick built across the S side of the N doorway opening from c to d: thus the room d around the subsidiary N niche was blocked off from chapel G 7310 and attached to G 7320.
 - e) north of room b and entered from it: south end formed by c.b. doorway (opening from N) and on the N by a similar doorway opening from S: 20.75 x 2.8 m.: area, 58.1 sq.m.: enclosing the subsidiary N niche of G 7310 which stands near the N end of the room: outer recess, 1.1 x 0.35 m.: inner recess, 0.35 x 0.35 m.: monolithic ka-door set back in casing.
 - f) a short room or vestibule north of e: north end formed by c.b. doorway opening from the N: 2.65 x 2.8 m.: area, 7.42 sq.m.: both the N and the S doorway have been damaged by intrusive shafts of the Ptolemaic Roman Period: the outside of the N doorway is in line with the N face of G 7310420.

Floor areas of chapel G 7310: Room a, 6.43 sq.m., limestone. Rooms b-f, 104.4 sq.m.: e-b. rooms, of which b was certainly/and probably c and f. Total floor area a-f, 110.83 sq,m,

probably the whole of the exterior chapels of G 7310 and G 7320 was constructed about the same time on one plan: the blocking of the chapel of g G 7310 probably occurred some time after the burials as a result of differences of interests between the two sets of ka-priests.

APPENDIX B. p.25.

Decoration of Chapel: no evidence of decoration: a horizontal line on the ka-door and vertical border on the backs of the puter niche indicate an intention to decorate.

Shafts in G 7310+7320: the shafts were lettered as in G 7110+20 A, B in each core: but shaft G 7310 A was found never to have been made and shaft G 7320 B never to have been used: A on N and B B on S.

Shaft G 7310 A: never excavated.

Shaft G 7310 B: wife shaft: 1.9 x 1.85 m.:-10.1 m. in rock: lined with massive masonry 4.45 m., 6 courses: Chamber: type 4 a(1): on S: 5.08 x 5.36 m.: and 2.14m. high:

area, 27.23 sq.m.: capacity, 58.27 cu.m.:

turning recess in N wall of shaft: 1.7 m. wide, 1.0 m. deep and 2.05 m. high:

small blocks inxparrage of limestone found in debris indicate masonry blocking in passage but no remains in passage: broken red granite coffin of type d along W side of chamber:

2.5? x 1.2 m. and 1.06 m. high: and cavity, 2.0? x 0.6 m.: and 0.75 m. deep: flat lid, 0.24 m. thick, with two haddles at each end: upper edges of the lid slightly rounded:

canopic recess in E end of S wall, 0.75 x 0.7 m.: and 0.75 m. high: without rebate:

Shaft filled with disturbed rubbish and 1st. debrisk dumped in recently: intrusive objects of the Ptol Period (faience amulets and potsherds): in the chamber was found also fragments of O'K' potsherds x and a rough diorite saucer of uncertain date (25-1-35).

Shaft G 7320 A: Man's shaft: 2.05 x 2.12 m.: -12.05 m. in rock: lined massive masonry, 4.1 m., 6 courses: Chamber: type 3 af, on S: 4.9 x 5.35 m.; and 3.4 m. high: area, 26.22 sq.m.: capacity, 89.14 sq.m.: with second chamber (unfinished) on S:

Passage from shaft to main chamber, 2.65 x 1.2 m. and 1.32 m. high:

remains of masonry blocking.

no trace of stone coffin.

E end of S wall, a passage led southwards to an unfinished and unused coffin chamber: roughly 1.0 x 1.9 m. and 0.7 m. high: the passage measured 2.25 x 1.15 and 1.35 m. high: in the N end of the passage was constructed a stone canopic chest, 0.85 x 0.83 m. and 0.6 m. high: inside, 0.55 x 0.55 m.: with rebate sunk edge of mouth: flat square lid displaced and lying south of chest: passage blocked on chamber side by a vertical masonry wall, type III b(1): above the doorway from shaft to chamber, a "window" has been cut through the rock from shaft to chamber about at level of roof of chamber, 2.35 x 1.0 m. and 0.75 m. high (probably used in cutting chamber).

Filling of shaft, dirty sand and debris containing Ptolemaic Roman amulets and potsherds recently dumped into shaft by leaving several meters unfilled at top; about at top of doorway, disturbed limestone debris: sand and debris in chamber:

24-12-446 to 452: faience beads and amulets in shaft.

24-12-453, 454: potsherds of Ptolemaic Period. 24-12-868, 871 to 875: in lower part of shaft: faience amulets, etc.

24-12-869, 870: alabster boring core.

Vol. I

net diano

APPENDIX B. p.26.

25-1-70 drawn

In Chamber:
25-1-23: flint flake, 1., 9.2 cm. x 1.3 cm.

25-1-24: flint: pssk; f wand, 1., 7.3 cm. x 2.1 cm.

25-1-25: limestone: small basin, Ptolemaic-Roman Period,

d., 10.3 cm. and 6.35 cm. high, with handles.

25-1-26, 27: faience amulets.

25-1-68 to 75: potsherds, mostly Ptomaic Roman.

Shaft G 7320 B: 2.1 x 2.1 m., ends at rock surface; lined with massive masonry, 4.5 m., 5 courses: type 7 x: on N side, masonry lined destroyed to rock by modern thieves: filling of debris dumped in recently.

Later Constructions:

- 1) against the W end of the exterior c.b. chapel of G 7320, rooms d-4, was built the late stone mastaba, G 73323
- 2) against the E end of the same chapel between G 7420 and G 7430, is the small stone mastaba, G 7431. 04.67432
- 3) at 8.5 m. north of N face of G 7310420, is an E-W quarry schap with face to N: in this is a small rock cut chamber opening to N: the quarryy had been excavated by Tewfik Eff. Boulos but appear to have been filled with limestone rubbish containing a few shafts or even superstructures.
- The street 7300 between G 7320 and G 7420 was filled with drift sand over a layer of limestone debris and a number of ptolemaic mummified burials and some Ptolemaic jars; descending through the sand and the debris were a number of shafts intruded in Ptolemaic Roman times:-
- G 7310 X: opposite N subsidiary niche of G 7310, against the back of G 7410: type 8 b(2) of c.b.: chamber on S: descends through mud floor of chapel to rogk: partly destroyed.
- G 7310 Y: in W side of room 7310 f: long N-S shaft with chamber of type 6 a(2): on W: date uncertain.
- G 7310 Z: sunk in W c.b. doorjamb of northern doorway of room f: type 6 a(3): chamber on S: date uncertain.
- G 7320 X: in room b of chapel G 7320 in front of doorway to room a: masonry shaft descends from top the debras: 1.3 x 1.3 m. at mouth, -7.65 m. in rock: lined with masonry, 1.95 m. 5 courses: at bottom large chamber on S, 3.8 x 2.5 m.: and 2.1 m. high: area, 9.5 mq.m.: capacity, 19.95 cu.m.: width of doorjambs, 0.5 m.: in S wall wide recess (loculus, containing limestone anthropoid coffin): on the floor lying E-W (heads E) four anthropid coffins of which the southern rests on debris: on N side of shaft, large chamber opening directly into shaft: with three loculi, 4.5 x 2.37 m.: and 2.0 m. high: area, 10.66 sq.m.: capacity, 21.32 cu.m.: in the walls high up, three burial chambers (loculi): (a) on W side, near entrance: 1.95 x 2.2 m. and 1.22 m. high:
 - (a) on W side, near entrance: 1.95 x 2.2 m. and 1.22 m. high: entered by doorway in S end of E wall: contained one mummy.
 - (b) opposite (a), in E wall: 2.05 x 2.15 m., and 1.1 m. high doorway on S as (a): empty.
 - (c) in W wall north of(a): 2.0 x 0.45 m.: with entrance in S end of E wall.

The note below was written in red pencil and reads, " Consider possibility which has already prompted placing them together in folder that fragments hitherto assigned to Minkhaf belong here."

WSS 1946

(afterwards Queen) Meresankh II: eastern most of four north-

Mastaba: massive core faced on E with stepped masonry (as type III) enclosing the old cores of type IV, G 7410 and G 7420: core, 79.9 x 16.5 m.: area, 1303.5 sq.m.: prop.l/4.78; the eastern side of this double core was faced with mastive masonry to this facing, two reconstants of the courses of small blocks (and thus the core was convertible in the old cores and faced as F contained the chapel G 7420 and faced as F contained the chapel G 7420 and faced core. Properly the contained the chapel G 7420 and faced core. Properly the contained the chapel G 7420 and faced core. Properly the contained the chapel G 7420 and faced core. the eastern side of this double core was faced with stepped courses of small blocks (and thus the core was converted into type III: preliminary to this facing, two recesses were broken in the old cores and faced as E facedL one of these contained the chapel G 7420 and the other at the N end was walled up byk the casing the chapel 7410 was built in a hole faced core, 82.0 x 19.5 m.: area, 1599.0 sq.m.: prop.1/4.25: faced core faced with fine white limestone (x-masonry) and

manned bonded with it two interior chapels of type (3a): the

<u>Note</u> Horizontal level lines apparently obliterated, as there is no traces left on E face of stepped facing.

2-9-41 A. F.

Mason's Marks and Quarry Marks:

on the stepped facing on the E face, were ... horizontal level lines, m. apart: on the third xxxx course a red horizontal line was marked mh 3 hr nfrw.

On the backs of the white casing stones were found uninteligible quarry marks on 15 blocks

Chapels of G 7410+7420: two chapels of type (3a) each with subsidiary N niche: carel faced chapel recess for chapel G 7420 and a second faced recess at N end which was not used.

Chapel G 7420: man's chapel: interior offering room (a) of type (3a): built in faced recess reconstructed in core: with special deep niche at S end of W wall: badly destroyed: ka-door preserved to height of drum, two slabs still in place one on wach side of NW corner, construction lines on floor: (a) 4.25 x 1.55 m. area, 6.58 sq.m.: prop.1/2.73: outer niche of ka-door, 1.2 x 0.3 m.: inner niche, 0.6 x 1.15 m.:

ka-door built of two courses of three stones each: entered by doorway in N end of E wall, opening in embrasure in the sloping casing.

Remains of exterior chapel of white limestone:b) hall of court around entrance to room a 4.75(?) x 2.2 m.: area, 10.45 sq.m.: just north of embrasure a stone wall 1.8 m. thick containing a doorway in which the door was on the S side (inside room b): the southern wall was destroyed to its foundations.

South of b, the rock descends sharply to the front of 7430.

Decoration of chapel G 7420, room a, of white limestone:on Ka-door, on back of outer recess, on S, a tall bowl stand with
bowl: like (7220 chapel: indicates that ka-door was decorated but the decoration elsewhere has been weatheredx away. The slabs left in place in W wall and N wall were so weathered that no reliefs were wisible but they may have been decorated Facade panels in doorway embrasure showed traces of palace facade panelling.

?? 4.75? examine [stones] in situ

F. O. A. 1940

Drain?

(b) from lower part of scene on N jamb, showing sloping border on tight: parts of two small figures of girls, standing facing to left: in front of the one

4) 25-1-1337:, 1321: two frags. of a swamp scene: probably from E wall:

(a) figure of woman in lappet wig and long tunic, seated facing to left on a throne on a boat: in front of her and above remains of two vertical lines,

on right is written vertically, Nbty-tp-it-s.

(1) .. $\pm i(t)$ (nswt) n(t) ht-f. (2)

in front of her appears to be the hand of a small man rowing: behind her a small male figure holds up a sunshade(?) over her head: between this man and the throne a small indeterminable object.

(b) frag. showing tip of bird's wing over papyrus flower

5) small fragments with traces of inscriptions:25-1-1019, 1322, 1325 to 1327, 1334, 1335/c
6) 25-3-19, 21: 25-1-1329, 1333: four frags. showing two or [hugu] 3ht ... 2)... t mr... more registers of scribes:

APPENDIX B. p.29.

(1) three fitting fragments: above from left to right, scribes case, squatting scribe, eliptical scribes case, figure of scribe writing, papyrus case of sack form: upper part of register below, largely black with unintelligible objects.

(2) parts of two registers: above, seated scribe facing to left and behind him feet of standing figure also facing to left: in register below, the head of a man facing to right and in front of him facing to left the sign m, perhaps imy-r; which indicates a standing figure on the right, facing to left;

 $\sqrt{7}$) 25-1-1323, 1331: two frags. from registers of small figures facing to left:

(a) upper part of man standing with right hand on left shoulder.

(b) legs of two men facing to left.

Now have 8) 25-1-1328, 1330: two frags from registers of small figures

facing to right:
(1) torso with half extended arms.
(2) middle part of legs of man.

9) 25-1-1332: frag. showing base line and stand with five jars.

9) 25-1-1000. 1.26-100

Chapel recess in N end of G 7410 and the Subsidiary N niche: About 23 m. north of the chapel 7410, a recess, 5.2 x 3.15 m.: (area, 16.38 sq.m.) was constructed and faced with stepped courses bonded with the facing of the core: when the white casing was constructed this recess was filled with stone blocks and fragments.

In the casing opposite the northern end of this recess was set a monolithic stela, set back in the sloping casing to form the N subsidiary niche of the chapel 7410; the outer niche measured, 1.1 x 0.44 m.: inner recess, cut in monolith. 0.35 x 0.25 m.: from in front of the N side of the niche, a rock cut drain ran slanting to NE to the middle of the street(1.15 m. long) and there turned northwards and ran north down the middle of the street to the N end of the mastabas where the street ended in a rock-scarp (N-S length of drain, 5.5 m.).

Shafts in G 7410 17420: shaft letters A, B assigned to both cores as in the three twin mastabas on the west: but G 7410 A was found 2 made not to have been excavated and G 7420 B not to have been used.

Shaft G 7410 A: thorough search proved this shaft was never made.

Shaft G 7410 B: wife's shaft (Meresankh II): $1.9 \times 1.85 \text{ m., } -10.67 \text{ m.}$ in rock: lined above with massive masonry, 4.45 m., 5 courses: two chambers, large chamber with burial chamber on south: Main chamber, type 3 af, on S of shaft: 4.95 x 5.42 m. and 3.6 m. high: area, 26.73 sq.m.: capacity, 96.22 cu.m. Passage, 2.1 x 1.6 m. and 1.88 m. high; blocked with filled

> turning recess in N wall of shaft, 1.2 m. wide, 1.2 m. deep, and 1.23 m. high, with horizontal roof.

> Coffin chamber, south of main chamber and entered from it by passage opening just E of middle of S wall: 4.15 x 3.65 m., 1.65 m. high: area, 15.15 sq.m.: capacity, 25.0 cu.m..

Passage, 1.15 x 1.3 m. and 1.65 m. high: blocked with masonry (broken through): redxgranizexpaneiledxcoffinxofxtxpxx xxxxxxxxx

Red granite EDITAN panelled coffin of type d(p); found overturned to east (originally along W wall); 2.22 x 0.92 m. and 0.83 m. high: flat lid with crouching Anubis in sunk relief: ... m. thick: on each long side a palace door with three panels on each side: the ends are inscribed: in S end of E wall, a canopic recess, 0.65 x 0.8 m. and 0.4 m. high, with rebate for lid on top and sides:

No plates on This except es Denn in chamber. Showed be Deference to M. F. A Bullatin and to Deference to M. F. A Bullatin and to Anausings in text. The list drawing how not been prepared.

APPENDIX B. p.30.

Total area of two chambers, 41.88 sq.m. Total capacity, 121.22 cu.m.

Inscriptions on coffin:

On lid over Anubis, nb t; dsr hnt sh ntr: in front of it and continued below it, newt dy htp krs-t-s m it n-s wrt hts Mr-s-cnh: on the offering lists: on N end, at top horizontal line with signs facing to left (east), m;;-t Hr-Stk Mr-s-cnh, with sign n repeated five times below it:

(1) n prt-rhrw (bread, beer, perfume 1000.

- (2) n mnht 1000. (3) n shtr 1000: and squeezed vertically under the fifth n int nbt bnrt:
- on S end: at top horizontal line with signs facing to right(east), (imy) Ht Hr wrt hts Mr-s-cnh: under this seven granaries with the named a grain or a fruit written on each granary nulsed below by (1) it (three granaries):(2)bdti (head of grain-stalk): 100 og: (3) s-t (swt): (4) by (5) bnry: (6) ddw preserved (7) wch.

- East side: one vertical line at each end of palace facade panel: On N, signs face to right and on S signs face to E left: (N) ht- Hr Mr-s-cnh: (S) wrt hts hmt nswt Mr-s-cnh.
- on w side, one vertical line at each end of palace facade, signs facing to left in both: (N) s; -t nswt nt ht-f Mrs -cnh: (S) wrt hts hmt-nswt Mr-s-cnh.
- The shaft was empty to a depth of several meters and above was filled with dirty sand and dust: lower down was disturbed debris with little intrusive material: the debris had run into the chamber as usual but to a small extent: the shaft had not been completely excavated in recent times.
- In the coffin chamber were found in the coffin, frags. of decayed wood and broken human bones: under the overturned box was

found:27-1-7: three fitting fragments making half a model cup of
alabaster: h. 3.7 cm.: diam. top, 3.7 cm, base, 2.0 cm.

127-1-8: alabaster: frag. of top of circular table:
probably diam. ca. 34 cm.: th., 1.3 cm.

127-1-25: alabaster: chip with curved surface.

127-1-9 to 24, 26-29: potsherds which represent fragments of the usual types of Dyn. IV except the RP bowls with recurved rim: include necklace shoulder jars (type B-LV) wype Barnary M), also model saucers.

27-1-5: copper: model bools badly corroded: chisels, axe-head pins, etc.: 9 implements and other fragments.

27-1-6: carnelian: disc bead: d., about 7.7 mm.: th., 3.2 mm.

27-1-3: about 50 frags. of broken human barnary beautiful to the work of large tub (type D-LXXI), RP jars of type A-V, and RP jars of type Bayling XVIII), also model saucers.

27-1-5: copper: model bools badly corroded: chisels, axe-heads

d: rim, 3.8 cm.: d. base, 2.0 cm: found under overturned

Hlrs3

I Think my chele in diease

Shaft G 7420 A: man's shaft: 2.05 x 2.0 m., -10.65 m. in rock: lined area, 32.49 sq.m.: capacity, 120.21 cu.m.: Passage, 1.65 x 1.5 m. and 1.75 m. high: no trace of blocking

found in place in passage:

turning recess in N wall of shaft, 2.07 m. wide, 1.35 m. deep and 2.55 m. high, with roof sloping up to north and with unfinished cutting in N wall made to enlarge the recess: In the chamber no trace of a coffin was found:

canopic pit: in SE corner, 0.6 x 0.45 m., and 0.32 m. deep: without rebate: either the chamber was unused or a garnite coffin has been removed: It is very probable that the granite coffin of Prince Horbaf in the Cairo

That They have. VI



APPENDIX B. p.31.

Museum come from this chamber. The measurements are possible 1., 2.3 m., w., 1.19 m., h., 1.45 m. and the name accords with with that on a fragment of relief found in the chapel reading Hr-(b;-f).

Filling of shaft G 7420 A: the upper part of the shaft was empty to a depth of 8 meters: then followed very mixed dumped debris for several meters, then a stratum of drift sand (in which was a decayed wooden statuette), and again disturbed dumped debris which had rum into chamber around doorway: apparently the shaft and chamber had been excavated recently.

Shaft G 7420 B: 1.8 x 1.8 m., -5.25 m. in rock: lined with massive masonry, 5.65 m., 9 courses: type 7 x: filled with disturbed dumped debrisin planta formal: 25-1-97X: faience: hindquarters of animal: 1.,2.7 vm.:h.1.8cm 25-1-98: faience: frag. of amuket: h., 1.6 cm.: w., 1.1 cm. 25-1-99: rough nearly rectangular flint flake: 5.0 x 6.0 cm. 25-1-100: red granite: frag from leg of statue (life size): 19.0 x 13.6 cm.

Later Constructions:-

South of G 7420, in avenue 2, the western part is occupied by the exterior c.b. chapel of G 7320, rooms e and i with the dripping culvert and tank under the floor: east of this stand a small mastabam G 7432.

a small mastabam G 7432.

In the street east of the mastaba between the two chapels are the remains of a small c.b. mastaba, G 7422, with four shafts in N-S line.

Against the N end of the mastaba, on a lower level was one larger mastaba, G 7411, excavated by Tewfik Eff. Boulos with a conglomeration of small partly destroyed mastaba west and N of it.

Intrusive shafts:

the street E of G 7410+7420 presented three irregular layers: on the floor, lst.debris mixed with sand: above these a deep layer of drift sand (1.0-1.6 m. deep) and above this surface debris consisting of sebakh siftings, black earth of the Ptolemaic Period, containing pottery, shawabtis, amulets, etc. of the Ptolemaic-Roman Period: close to the mastaba were found a number of Ptolemaic-Roman mummies, some in lined and roofed burial chambers and some in open pits in the sand: shaft Y, stone roofed pit, was just south of chapel 7420: shaft Z, also lined and roofed was about 13 m. north of chapel G 7420: north of it were 11 open graves each containing a decayed mummy:

Sjust south of chapel 7410 was a lined and roofed grave: north of this chapel were Aux graves of the same type:

inside the mastaba between the two old cores was an intrusive shaft, a lined grave, numbered G 7421 X.

<u>Note</u>

Shafts Y & Z were not shewn on Wheeler's plan and therefore could not be traced.

A. F.

APPENDIX B. p.32.

The four southern mastabas intended to be twin mastabas: as finished:-

G 713047140: Prince Khufuw-khaf and his wife: twin mastaba, the westernmostof the four southern mastabas: south of G 7110+7120.

> Plan & Section done. A. F. See Figs.....

See Pls.....

Owner: Khufuw-khaf, s! nswt n ht-f mry-f, rpt, sd; wty bity,
smr wty, [mrr nb-]f m iswt-f nb, hm ntr Hwrw, hry, wdb
ht-nh, wrw hb, d mr Dp, Dw; w, hrp h, hm b; whn
mdw Hpp, mdw hdt k; (?), hm ntr th wtot Hr (House, Edge)

Further Visions Fith below is Cains selection No 46 and relief 24-11-635 belonged to 16 hours belong 37)

Mastaba: core of massive masonry consisting of old core G 7130 of type

IV i and an addition on the south of massive corework type IV-iii with recess for interior chapel: N chapel built in hole in core 7130: core, 66.0 x 17.25 m.: area, 1138.5 sq.m.: prop.1/3.82: near the south end of & 7140 a recess had been built to receive the man's chapel: and at the S end of 7130 a hole was broken to receive the wife's chapel: the core was cased in fine white limestone (x-masonry) and bonded with it two interior chapels of type (3a): the cased mastaba measured 68.5 x 20.05 m.: area, 1373.42 sq.m.: prop.1/3.41: height,... of G 7130, 6.61m. h. of 7140, 5.18m.

Fragments of two diorite (life size) seated statuetes of Khufuw-khaf (see pp.12, 13).

24-12-962: Fragment right side of base of seated(?) statue

with part of right foot inscribed on top: (Hw)fw-h;f; see Pl. 1. found in pit G 7130 X. May fix status No. 46 in Caises of headless visies. appears to be night aige space broken maniful, 4 wise and howfly 124-12-656: Right hand of seated statue, found in chamber G 7132 A. See Pl.1.

 $\sqrt{24-12-657}$: Right hand of seated statue, found with 24-12-656, See Pl.1.

Masons and Quarry Marks:

On backs of casing stones, 13 with unintelligible quarry marks, 4 on N, 4 on E and 5 on S. levelling line on E face of core.

Chapels: # 7130 17140: two interior chapels of white limestonebonded with casing: each with subsidiary N niche in casing. before chapel G 7140, exterior stone chapel and hefore chapel G 7130 and exterior c.b. chapel: in the street between the two exterior chapels are the remains of other c.b. rooms which filled the W side of the street; north of chapel G 7130, are scantly remains of other c.b. walls destroyed by intrusive mastaba: at N end of street, a c.b. doorway with stone sill giving access to street from avenue 2.

Chapel G 7140: Prince Khufuw-khaf I: interior offering room a of white limestone built in recess constructed ab orgine in additional corework: type (3a) with special deep(?) niche at S end of W wall: outer niche 1.3 x 0.35 m.; inner recess, 0.58x0.54 with W end cut away: well preserved but tops of walls destroyed and hole cut through niche in making a harizontalk burial chamber of the Ptolemaic Period: 4.15 x 1.65 m.: area, 6.84 sq.m.: prop.1/2.51: lentered by doorway in N end of Ewall, opening in embrasure in sloping casing: against the sloping casing is constructed an exterior chapel of fine

white limestone with 2 rooms (b, c): b) same length as embrasure with doorway to a in middle of W side 3.65 x 2.3 m.: area, 8.39 sq.m.: entered from E by doorway in N end of E wall: small doorway to c in E

end of N wall.

c) magazine with stone shelf, north of b and entered by door-way in E end of S wall: 2.05 x 1.7 m.: area, 3.48 sq.m. along W side, at height of 1.25 m. above floor a horizon tal stone slab fixed in the wall forms a shelf, 0.95 m. wide: There is a shallow recess in the E wall beside door, 65 cm. wide, 1.2 m. high and 10 cm. deep. Total area a-c, 18.71 sq.m.

a Kadamie der H. Wissenschegen 1953, Nr. 14 pp. 171-175. Corganier That Queen has come & lead her som our of come Pe with probably gon W.SS. History

I high which is a little larger than our piece. accurate measurements should be taleen of cairo piece. Cairo statue inscribed on right side of theme: 53 news m ht-g session hity ... to be continue by The (H&) gw +3 38 our frequent. Last side of caire disting inscribed: report +34ty as 6 +36y we 5

insert Lonthe back you casing stone

[pr dhuty]

displaced from E face in ruleding I sis temper cans markinet on personal of that temper: 1.31 Sp 12 2 Smw. Interpreted

* Footmote: This miche is restored wrongly as an ordinary simple comprise miche in Ver I, Fig. 114, 194.

There is a small niche cut in the east wall of the mastaba just N. of exterior chapel of G 7140. (See Floroff's tracing)

A. F. 18-8-41 bisel on p. 32 and auny monks

: on the back of a casing block displaced from E face when the Isis Temple was built: overhilt by pavement of Isis Temple, inscription on stone blocks.

I hit sp 12 ibd 2, with other illegible orgins: interpreted as "Year 23 of Chelps."

Decoration of chapel G 7410: 140 E. De Rouge gives some of Room a was fully decorated: including doorjambs and facade panels The inscriptions in Inscriptions hierogly phiques Copies en Egypte, Plaix, LXI. ern side of room b: the door jambs of the outer entrance He adds what appears to be an architrave insemption otherwise unkunn: hatt mót hry sst3 m no-g Hwgur-lecg. This many be

a mistake, but it also may be an architair or drum which has discoppens. Thin 1 text is 7150 Khu futchuf IP WKS [Juny [we]

[53 now nht-g mry-g Hupu [63]

Las-f Las-f Hn nint

L must-g mot sw miss He sth we [t his]

LIne grant of him is written: 53-5 mrs. 5 az nint

A xacondragor (b) standing scribe, partly obliterated. Hunder Rampit

h standing man

MWT-KS

Hhrp

(3)(a) Miner many labelled hm-k; Intyrgm(?)....

(b) Miner worked is labelled hk; het.

(ii) Miner worked is labelled hk; het.

(iii) Miner worked is labelled h wig, beard, short skirt, long staff in left hand, and his right half extended open: behind the chair stands a daughter: is;(t) i nswt (Nfrit -k;(w): in front and facing him stand the two sons holding scribe's palettes (dt ss in s; nswt fw-k) and dyt si in s! nswt Iwn-k!): above three vertical lines with

titles and name,

(1) s; nswt n ht-f thry.

(2) smr wcty shm ch; hm B;w-Nhn "keeper of the door of the

Letepolis nome" (53.D \(\times_{23.D} \) oryx, gazelle, addax, <u>śr-goose</u>, <u>trp-goose</u>, <u>st-goose</u>, mnwt): on the right behind the figure of Yuwenka, written vertically, hryt-hrw wcty(?) n sh (?hb?): right of this separated by vertical line, two signs for 100,000, one for 10,000 and 3 for 1000.

to room b were also decorated: the N, E, and S walls of room b, were probably intended to be decorated. Daressy Annales XVI p.257: M.F.A. Bulletin, Vol.XXXII, No.189 & room l b) entrance doorway? only decoration is on the doorjambs:
on each side at the top is a crouching # jackal (Anubis)
facing outs: over Anubis, hnt t;-dsr, with signs facing
out: under the Anubis htp dy nfr
Hwfw-hc-f.5 Pl. 43

in embrasure: these panels were exposed to view in the west-

side over Anubis, h(nt) (t; dsr: underneath htp dy wsr spss hr ntr c; s; nswt Hwfw-hc-f. PQ.43

b) west side, facade panels of doorway to (a):-N-panel: (W.S.Smith op.cit, Pl.43b) large standing figure of Khufuw-khaf, as a fat middle aged man, facing in to left long pleated skirt with panther skin over it, bare head staff in left hand (attached to right arm) and bandhark; handkerchief in hanging right hand (attached to left arm) in front a vertical line with titles and name: between man and staff a naked boy also facing to left: behind him three registers of two small figures in each:
(1) sons, [wt-k] and [wn-k]: (2) hm-k] SSm-k;w, carrying staff, sandals and bag over shoulder: SS wnw, carries

a case and bag: (3) the heads of two stribes. In fully

Some way seemed of two stribes. In fully

S Panel: (M.F.A. Bulletin Fig.9, W.S. Smith op.cit. Pl.44B

detail of two large figures): two large figures facing

in to right, mother of the prince, Queen (Henutsent) who holds by the hand the prince who stands behind her as a young man: above and in front of queen titles with name accidentally cut away in Prolemaic Roman times Queen has left hand open on her breast and holds with her right hand the left hand of her son: she wears peculiar cap, a long tunic with peak on left shoulder: the prince has a short skirt; his left hand holds his mothers right hand and his right hangs holding a handkerchief (or a band? /: behind him are three registers of two men each

all face to right: (1) (a) standing scribe with papyrus roll and scribes case:/ (2%) standing scribe with left hand bn right breast carrying in his right hand a rectangular palette and pen- case (b) was conducted as has his arms crossed on breast with the sign (k); written in front of his face.

titles and name,

a) S doorjamb: figure of prince seated as on N but facing out to left: girl standing behind his chair: in front, the two sons seated on the ground with one knee raised: \$5; nswt Wt-k; \$ {and s; nswt Iwn-k;}: in same attitude, with left hand on breast holding papyrus roll and right hand half extended on breast open; above, three vertical lines with titles and name is; nswt n ht-f mry-f (2) htm bity mdw Hop (3) Hr hm ntr Hr. Line, signs facing out to left, m; htm-t in-t m [pr] nswt; Is! nswt n ht-f mry-f (2) htm bity mdw Hop (3) Hr hm ntr hr.

line, signs facing out to left, m; htm-t in-t m [pr] nswt:

horizontal line of offerings, signs facing in, (1000, idmy,

mrht,h;tyt, and several other ointments). Pc. 43.

a) E wall (detail to show workmanship: Smith Op.cit. Pl.42 c):

next to door, prince seated on chair facing in to right, with

short pleated skirt, short wig and short chin-beard holding

staff in left hand and other hand (left hand on right arm)

extended open above his thigh: behind his chair stands a girl

extended open above his thigh: behind his chair stands a girl long tunic broad necklace, with left hand raised resting on father(s hip and blue lotus in right hand: above Mans head titles and name but the titles are broken away: in front of him is a wantical line of language resting the him is a wantical line of language. him is a vertical line of large signs facing to right of which the upper part is broken away ([m;;] in-t m

nluwt-f nt dt.
in front of the chief scene are four registers of which the upper and second registers are partly broken away:

Meet

(1), destroyed except for sealed jars at S end:

(2) man standing facing to right holding up a papyrus roll(?) in both hands with box of linen(?) on ground on the other side of him: over the box idmy, tp ssridmy, tp c tyw; second man standing with arms extended in front and belin behind, holding a piece of linen in each hand, beside him again a box: over the box, tp ssr hfr, nhrw: tp ssr nfr, tp-ht: two rectangular tables with four cylindrical jars each, with inscriptions above, ... tp het sft, tp het

M ssst

(3) man holding out a box or tray containing a stand with three holes each containing a cylindrical jar, inscribed under the box, dyt htmt hryt sti nb: man holding out a double bell censer, hm k; Sennuw-ka: in front of his feet is a chest with hryt sntr over it: man holding up a box containing two hs-vases and a bowl stand with bowl det in holds in the false bottom: at his feet a rectangular table with various vessels (ewer, basin, censer, two jars with string handle and a spouted bowl with recurved rim): then come five big jars (type A-II b) each in a ring stand: above them is written, tp het ib, tp het smcwy: then a box: over the box hnw hry sntr: en the box

how hry satr: on the box, db-t 233,000.

(4) three pairs of men carrying apron-like garments: over each garment is its name, ic; b; smcwy, ic; , ic; m; s-t.

See Pl. 44.

a) S Wall: (detail of five prints, M.F.A. fig. 4): prince seated facing in to right at table of bread: full wig, short chinbeard and short skirt: both hands extended, the right hand (left hand) to the bread and the left hand to the offerings under the table: bread, of tall conventional form: above his head arem three vertical lines of titles and name,

Under the table on the left: ideographic list of offerings (bread, beer, clothing, perfume, cattle and fowl): Under the table on the right: two registers of two men each

- 1) on left: man kneeling on one knee facing to left, holding a small jar (nw-pot) in each hand: above him is written, prt-r-hrw (bread and beer): the second figure stands holding a haunch of meat:
- 2) man kneeling on one knee, holds out left hand closed at height of his head and the right extended towards prince: above is written snm jht: the second figure,

H man hat ks ?)

standing, with right hand extended open and the left hand hanging, wrdn (for wdn) iht (bread, beer).

a) N Wall (M.F.A. Bulletin, 1.c., Fig.1): family group: the prince on the left facing out to right, leaning on his staff: bare head or close fitting cap, long skirt (sarong?): before him facing him, stands his wife, long tunic and large lappet wig: her right hand open on her breast and her left hanging holding the processed coiled stem of a lotus flower(blue lotus); above are were vertical lines with the titles and names of both, only partly preserved; horizontally in front of his face with signs facing to right, Hwfw-hc-f: horizontally above her head, with signs facing to left, Nfr-t-k; (w).

() (of wor Db '5)

a) W Wall south of ka-door: four registers each bearing one standing figure facing in, estates bearing offerings:
(1) male, Hwfw-hc-f

(2) female, M; t-b; w-Hwfw; (3) Mnkb-Hwfw.

(4) Woman, Grgt-Hwfw.

all face to right, carrying a basket on the head and leading a small animal.

a) Ka-door: deep compound niche but not the special niche: Architrave missing:

Tablet: prince seated in traditional attitude facing to right at table of bread: bread conventionalized: top line with titles and name is missing: above the bread are 2 horizontal lines with signs facing to left, extending

withree lime be youd the table and continued by the horizontalito the right of the table and extending to fill the space under the table on the right: separated by raised lines: short list of offerings: under table on left, ideographic list

(1000 bread, 1000 beer, 1000 ss, 1000 mnht, 1000 mrht): Cross-bar: bears horizontal line with signs facing to right, nswt dy Inpw htp hnt t; dsr prt-r-hrw m hb nb s; nswt Hwfw-hc-f.

Inner niche: broken away by Ptolemaic cutting but S side is preserved and uninscribed: probably the back and N side were also uninscribed.

Outer niche, the two/panels: on each side a tall bowl-stand with basin.

Outer niche, the two sides faces: on each side, five registers each containing a man standing facing in: on S, (1) partly broken at top, [dyt] sntr;

(2) holding out kbh-jar in left and small far with cordhandle, pdyt kbh;

(3) pours water from ewer in right hand, into a basin held in left hand, dyt mw.

(4) holds out offering table with offerings in both hands

dyt iht:
(5) holds a live goose by neck and wings, stp. ;pd. N side, only four registers preserved, \$\(\begin{align*}(2)\) holds pleated linen (bag?).

(3) carries haunch.

(4) holds out tray with 4 jars, irp.
(5) man carrying wicker case, ist bort.
(View of false door looking SW, M.F.A., fig.2). / Bussein

so Pl. 46

a) W Wall, north of ka-door: a great presentation on the right end, the prince stands facing to left with his wife behind him: prince with short wig, short chin-bushbeard, short skirt with panther skin over it, long staff in right and shm wand in left: behind him his wife, with bare-head (cap?), dog-collar, long tunic, bracelets and anklets: her arm passes around his left with the hand open on her arm passes around his left with her left hand: above 4 vertical lines give his titles and names and two more give

her titles and names:
(1) (s! nswt n ht-f) mry-f (2)hm ntr Hwfw (3)m.iswt-f nb.

/back

Wego of man: nt

In front of chief figures are 5 registers of figures facing to right: (1) Five estates bearing offerings (baskets and live birds) male and female alternately: No.

(a) Hc-k;-h-t-Hwfw: (b) Hwfw-bwr-hwtt (c) Iw-Hwfw:

(d) Bct-Hwfw: (e) Hc-Hwfw.

(2) five scribes: horizontal line above, imy-r; pr d;d;t

ip prt-r-hrw int in niwt-hat pr dt:

(a) squatting with one knee up with pen behind his ear,

writing: in front of him a scribe's case with two Nfx-bnr-wt-t-Hwfw(?) H.f writing: in front of him a scribe's case with two rolls of papyrus on it: probably the imy-r; pr. (b) scribe in same attitude in front of him a scribe's case, <u>K;-mni</u>.
(c) scribe in same attitude, two pens in his hand, K!-n-nb. (d) scribe with right hand to take roll of papyrus from fifth man, Hym.: (e) standing man holding out roll of papyrus to 4th scribe: in front a papyrus case on which is a low table with three unidentifiable objects on it: 1ry md;t Bbi.
(3) above the register is a horizontal line, it t htmt in htmw: five men facing to right: (a) using bell censer. (b) carries in left hand sandal-case on cord handle or perhaps a seal-case on a cord-handle, and in his right hand a fan. (c) carries bag and a strip of cloth in his left hand and a long bag over his right shoulder. (d) carries in left, a skirt and in right holds one end of the spread skirt which the mert man citation (e) holds with both hands: on the skirt is a e; sign as a a tie hanging from middle of upper hem. (4) six men facing to right: (a) carries rectangular box with both hands at level of his face. (b) ewer and basin held high in both hands. (c) circular table with three loaves of bread, held high in both hands: (d) water jar in each hand.

(e) in left, skewered goose and in his right, platter with naunch.

(f) in right hand, long skewers with meat(?) and in less hand an imals to right:

(a) live birds in best hands.

(b) slarge goose in his arms. (c) carries a gazelle on his back (around the back of his neck. (d) carries calf around the back of his neck. (e) carries hyena in same fashion. (f) carries gazelle in hism arms in front. See Pl. 45 Chapel G 7130: wife's chapel, (Princess(?) Nefert-kauw): built in hole broken in old core 7130: of type (3a) of white limestone: bonded with casing: subsidiary N niche in casing: with one room exterior c.b. chapel. a) 4.3 x 1.5 m.: area, 6.45 sq.m.: prop.1/2.86: foundation lines and remains of walls on E, S, and ka-door: outer recess of ka-door 1.35 x 0.3 m.: inner recess,

end of E wall.

Total floor area, 11.59 sq.m.

0.65 x 1.25 m.: special deep niche at S end of W walle

chow entered by door in N end of E wall, opening in embrasure 2.9 m. wide.

b) exterior c.b. room enclosing doorway embrasure to room a: 3.55 x 1.45 m.; area, 5.14 sq.m.: E wall, 1.6 m.: N and S walls, 1.35 m. thick: entered by doorway in S

Decoration of chapel G 7130, room a, Princess(?) Nefert-kauw:
Walls of room and facade panels apparently decorated with reliefs:
represented by fragments found in and in front of room a:

- 1) fragment from N facade panel, showing back of head of a man, fragment from edge of doorjamb: showing on the outside a sloping face and on the inside a vertical face: on the sloping face on the right, a border and next to it part of the head of a man (like Khufuw-haf on N panel of G 7140) facing to right: on the N doorjamb, a sloping border and part of a vertical line of hieroglyphics,rpct...k;....
- 2) four fragmnets shwoing parts of four large figures of which three appear to be male figures: thus the figure of Khufuw-hafi dominated the decoration of his wife's chapel:

 c.f. chapels of Atet and Nofret at Medum and G 7410.
- 3) another small fragment shows part of the name of Wet-ka one of the two eldest sons.
- Shafts in G 7130+7140: like all the mastabas in the southern row of four, G 7130+7140 had its shafts, 2 in number, on the old core 7130: A on N and B on S:

Shaft #7150: A on N and B on S:

67/30+40A
Shaft #7150: 1.9 x 1.9 m., -9.92 m. in rock: lined above with massive masonry, 4.65 m., 7 courses:

Chamber, type 6 b(2) on S: 3.15 x 1.15 m.: and 1.05 m. high:

area, 3.62/sq.m.: capacity, 3.8/cu.m.

Shaft and chamber filled with dirty disturbed dumped debris containing one frag. of black and white porphery squat jar, frag. of alabaster headrest, and many faience amulets and frags of the Saite-Ptolemaic Period: all objects obviously intrusive:

24-12-283: limestone: part of two handled vessel(Ptol.) 24-12-284: frag. diorite bowl with internal rim: d.,29cm.

h.ca., 9.0 cm.: d.base, ca.10 cm.
24-12-285: alabaster: frag. dressed on both sides with one end rounded off: 7.45 x 3.9 cm. and 1.5 cm. thick.

24-12-286 to 291: faience: frag. of vase, three frags.

of shawwabtis and a small pendant.
24-12-305 to 308: misc. Ptolemaic frags.: a shell,
faience amulet, corroded frag. of bronze or copper,
and a faience long rectangular bead.

stone chapel of G 7140 and the exterior c.b. chapel of G 7130 were a series of c.b. rooms with a narrow N-S passage running in front of them: in these rooms have been intruded five shafts (x-shafts) which mutilated the outlines of the c.b. rooms: just south of the N subsidiary niche of G 7140. is visible the N end of a room, entered by a doorway in the N end of the E wall: whether this space southwards to G 7140(exterior chapel) contained one or more rooms is uncertain: around the subsidiary north niche of G 7140 appears to be a long N3S room reaching to the S face of the exterior c.b. chapel of G 7130, and entered by decrway in N end of E wall. (about 7.35 % 1.95 m.). Subsidiary N niche of G 7140, outer recess, 1.15 x 0.35 m. mm: and inner recess 0.45 x 0.35 m. North of the c.b. chapel of @ 7130 the evidece is not so clear owing to intrusive shafts and the small mastabas & 7132 Lbuilt against the casing of the mastaba: but the line of W side of the passage on the east side of the street was followed by all intrusions: at the N end of the street was partly preserved a c.b. doorway anx&xandingxatxnxxide 1.5 m. thick and 0.9 m. wide: with sill of three slabs: this appears to open into a small room about 1.95 m. long with doorway on S endign at N side of subsidiary N niche of 3 7130: the space in front of this niche was clear and opened into the N end of the passage described above: outer recess of N subsidiary niche of 7130, 1 $1.15 \times 0.35 \text{ m}$. inner recess, $0.4 \times 0.35 \text{ m}$. the outer doorway opens into avenue 2 and the sill slopes dowr from the floor of that avenue to the floor of the N-S passage in front of our mastaba: under the floor in avenue 2, ran a

Chapel in Street: in the western side of the street between the exterior

L and G. 7133

APPENDIX B. p.37.

Decoration of chapel G 7130, room a, Princess(?) Nefert-kauw: See Poste 47. Walls of room and facade panels apparently decorated with reliefs: represented by fragments found in and in front of room a:

M This piece is

1) fragment from N facade panel, showing back of head of a man. fragment from edge of doorjamb: showing on the outside a sloping face and on the inside a vertical face: on the sloping face on the right, a border and next to it part of the head of a man (like Khufuw-haf on N panel of G 7140) facing to right. On the N doorjambis a sloping border and part of a vertical line of hieroglyphics, ...rpct...k;....

Brokely jain with No 3 below to read ret ... Wt-k3 ... Sae Fig....

2) four fragments showing parts of four large figures of which

three appear to be male figures: thus the figure of Khufuw-haf dominated the decoration of his wife's chapel: c.f. chapels of Atet and Nofret at Medum and G 7410. See Plate 47, Fig.... One is grom a sested figure with hand clauded on lop acush

I from its small seale 3) another small fragment shows part of the name of Wet-ka one of probably & be assigned & N. don junes. one piece chous

housing arm of

the two eldest sons. Fig..... Pl.47

[in the two eldest sons. Fig..... Pl.47

Shafts in G 7130 + 7140: like all the mastabas in the southern row of

four, G 7130+7140 had its shafts, 2 in number, an the old woman with braceless. core 7130: A on N and B on S:

Note: The red outline represents the edges of a typewritten piece of paper pasted on top of this page. Shaft G 7130 A: 1.9 x 1.9 m., -9.92 m. in rock: lined above with massive masonry, 4.65 m., 7 courses: Chamber, type 6 b(2) on S: 3.15 x 1.15 m.: and 1.05 m. high: area, 3.62 sq.m.: capacity, 3.8 cu.m.

Shaft and chamber filled with dirty, disturbed, dumped debris containing one frag. of black and white porphery squat jar, frag. of alabaster headrest, and many faience amulets and frags of the Saite-Ptolemaic Period: all

Mean

From the style of their cutting in high bold relief and resemblance to the reliefs in the chapel of G 7140, it is probable that several fragmemts found in the street east of the Queens' pyramids are to be assigned to the chapel of Khufuw-khaf's wife (G 7130)

MFA 34.60

 $\sqrt{1}$ 29-7-11: Block with head and shoulders of large male figure facing to right. Wears short wig and chin beard, broad collar and 'boatman's fillet' with long streamers. M.F.A.
No. (36.40) Could be a head of Khufuw-khaf. See Pl. 35 d. Found in debris of Isis Temple. 40 x 60 cms.

20x29eFe10xefextudxealrefigurus xdreingerightex Ernenmaduratuesize
pexbapacicmenthexparthrjankentxthexentronesxdinaex thexerale eduded signered exercic action with an extra the contract of catheres abio of figurere kei ex way x erwe ef cour tho x moe x lu garde of x ebrern to acre

(2) 24-11-692: Two fragments forming a rimblex headless seated figure, but on a larger scale. Perhaps as in G 7140 a seated figure from the east wall of the chapel (the staff which he is holding is not suitable for the table scene of the south wall). Found in the Queen's boat grave. Pl. 35 a.

3) 24-11-635: Block from an architrave with an inscription in large hieroglyphs:....rp/at tayty s;b t;ty wr == 5 pr Dhwty... Khufuw-khaf does not bear these titles in his chapel, but if the Cairo statue of the vizier No. 46 fits the fragment with the name of Khufuw-khaf these titles would be supplied for the prince. Khufuw-khaf bears the title sd; wty bity in common with the statue. This title, as well as rp t which he also possesses are suitable for a vizier. The missing upper portions of the chapel walls in G 7140 leave space for the restoration of the titles of a vizier. Block found in the Queen's boat grave. See Pl. 35 f and Fig.

4) 25-12-668: Fragment from an architrave (?) with unintelligible inscription in large hieroglyphs resembling the preceding block and the style of the Khufuw-khaf chapel. Found in St. 7000, north of Isis Temple. Pl. 35 a, Fig.....

> 1.15 \times 0.35 m.: inner recess, 0.4 \times 0.35 m. the outer doorway opens into avenue 2 and the sill slopes down from the floor of that avenue to the floor of the N-S passage in front of our mastaba: under the floor in avenue 2, ran a

APPENDIX B. p.38.

long N-S enclosing wall which was probably put out of use before G 7130+7140 was finished. See Pl. 47 cms Map.

Shaft G 7130440 B: man's shaft: altered by Ptolemaic cuttings and reused: 2.05 x 2.05 m.: -8.2 m. in rock: lined above with massive masonry, 4.65 m., 7 courses (with levelling course on sloping rock surface).

Turning recess in N wall of shaft at bottom: 2.05 m. wide (E-W), 1.8 m. deep (N-S) and 2.85 m. high with roof sloping slightly upwards towards the N.

Chamber: two rooms, main chamber and coffin chamber:

Main chamber: type 4 a(1): on S: $5.35 \times 5.85 \text{ m.}$; and 2.5-3.2m, a high, with roof sloping upwards from N to S: area, 31.29 sq.m.: capacity, 89.17 cu.m.: for Ptolemaic alterations see below. See Pe. 47

Passage: 2.05 x 1.12 m. and 2.35 m.-2.47 m. high as roof slopes slightly downwards from shaft to chamber: no trace of blocking remained, probably of type II b(1).

Coffin chamber: south of main chamber, entered by passage opening in SW corner of main room at floor level: with S wall lined with white limestone and cofin alcove cut in W wall: the rock cut chamber measures, 3.05 x 3.15

and 1.9 m. high: area, 9.6 sq.m.: capacity, 18.24 cu.m. Lining: the S wall of the room had been cut back in the upper half to a depth of 0.65 m. deep and 0.95 down from roof: on the W below the rock had been cut away for the same depth and downwards for 0.33 m.: this cutting contains the remains of four courses of white limestone blocks (three courses filling the upper cutting and one course in the lower continuation: the lined chamber measured, 2.4 x 3.15 m. and 1.9 m. ki high, giving an area of 7.76 sq.m. and capacity of 14.74 cu.m.

coffin alcove: in W wall: 2.3 x 1.975 m. and 1.8 m. high: area, 4.54 sq.m.: capacity 8.17 cu.m.: the spening on the chamber side had a rock-cut jamb on each side and a rock cut lintel on the roof: this opening was may have

probably blocked with masonry: in the floor of the alcove were cut four horizontal grooves, perhaps to admit ropes used in handling the coffin. New the case k

Coffin: plain red granite coffin of type d: lid and upper part broken in fragments but bottom found in alcove with its E side propped up on stones as left by the plunderers (probably in Ptolemaic times) who lifted the granite piece to search under it: 2.25 x 0.86 m. and 0.92 m. high (1.055 with lid). cavity, 1.89 x 0.59 m. and 0.66 m. deep: flat lid with rebate under edges (Reg. No. 36-10-37). See Fig....

Canopic Recess: In the W end of S wall of chamber, between two blocks of white lining: 0.5 m. wide (E-W), 0.3 m. high and 1.05 m. deep: with back part cut in rock to a depth of 0.4 m.: no rebate.

Passage: from SW corner of main room at floor level to E end of N wall of coffin room also at floor level: cut into to form a burial loculus in Ptolemaic Period but apparently measured 2.1 x 1.05 m. and 1.15 m. high. no trace of blocking but probably again of type II b(1)

Total area of rock cut rooms and alcove, 45.43 sq.m.

Total capacity of rock cut chamber and alcove, 115.58 cu.m. Total area, main room, lined room and alcove, £43.59 sq.m.

Total capacity, main room, lined room and alcove, 113.08cu.m

Ptolemaic alterations in the two rooms of the original burial chamber: In the W wall of the main chamber were loculi I-III (with I and > II near Those level and III near floor.

In the E wall of the main chamber were two loculi in the upper

part, Nos. VIII and IX.
In the 5 wall of the main chamber, were the openings of two passages, the old passage to reem coffin room in the lower W corner (converted into loculus No.IV) and a Ptolemaic passage high up west of middle of wall: in the upper part of the wall were three loculi: n No.V, two on the east, Nos.VI and VII. See Pl. 47 and Fig


See is this can be cheeled in aless of motor. Drawings on motor.

I in The west alone walls and coiling was a shallow cutting which wise apparently intended to grow a ledge in which to rest the Did of the parcophagus. See Pl. 47

> coreer 43.59

["near floor level" is crossed out] with I and II above III and III near floor.'

A. F.



APPENDIX B. p.39.

In floor of main chamber near the N wall, is a shaft No.X, leading down to another chamber.

In the old connection passage between the main chamber and the coffin room, the walls have been cut away to form a room IV.

In the coffin room the N wall west of the passage has been excavated to form room No.XI: but through into No.III.

In the middle of the floor is a shaft, No.XII leading to chamber below: shaft with rebate for covering slabs.

In the NE corner of the room is a small loculus No.XIII. In the S wall of the main chamber high up W of the middle opens Ptolemaic passage running southwards: 5.2 m. long: E side irregularly so that the width from 0.9 m. in the opening in the main room to 1.35 m. in the middle and 1.25 m. at the S end where it opens into shaft & ... this shaft descends from the surface in the Isis temple, room .G. and contained loculi at three different levels: the passage resulted probably the breaking through from one loculus in the mains chamber. \ fwm

Shaft B: filled with miexed dumped debris which had run into chamber around end of passage: the room was found littered stones and debris on wehich we found pieces of newspaper and burnt matches: the passage opening in the S wall of the main chamber of G 7130 B leads to another shaft which opens in the floor of room g of the Isis Temple: this shaft was found by us (said to have been excavated in recent times by the Service). The old chamber of G 7130 B with its Ptolemaic cuttings had been entered from the shaft in room g of the Isis Temple: the whole complex had been plundered at the time the shaft in the Isis Temple was excavated, On the filling of the shaft were four fragments of faience shawwabtis.

In the chamber, main chamber, in the floor debris were other Ptolemaic objects:

36-11-4, 5: Nov.4, 1936: at least 20 molded shawabtis, three inscribed, sb-n-st and ms-n-c mrrt(?): and many frags. showing at least three different molds:

36-11-7: w.lst.: frag. of statue, in loculus No.V.: from life size statue: closed hand holding handckerchief.

36-11-8: in room No.V: w.lst.: frag. from basis or slab: showing raised lines painted red: unintelligible perhaps from servant statuette.

36-11-9: in room VI: frag. of relief with incised instribute inscriptions.

Later Constructions:

Against the S end of the mastaba, was constructed the mastaba of "prince" Khufuw thaf II, B 7150, probably a grandson of Prince Khuwfuw thaf I:

Against the E face of the mastaba, between the chapel G 7130 and its subsidiary N niche, is built the small offering room]

[67133 and a small must lag 7132 with two shafts to the N (A, B) and one shaft (7130 X) to the south.

All threex shafts are of Dyn. IV or early Dyn. V.

In addition to shafts attached to G 7132, there were six other shafts, sunk in the rock along the face of the mastaba: three shafts, G 7140 X, \$\frac{1}{2}\, from N to S, lie between the exterior chapel and the N subsidiary niche of G 7140: three others, G 7130 Y, Z, VV, from N to S, (Z, V) south and one (Y) north of the exterior c.b. chapel of G 7130. In the Saite-Ptolemaic Period the Isis Temple was extended east-

wards across the top of the mastaba (N end of G 7140) to the street G 7100, where the continuation eastwards was destroyed by recent excavations (sebbakhin): see the temple of Isis with its private chapels and burial shafts.

In the same poriod but probably a little later than the private chapels in the Isis Temple, the chapel of G 7140 received several intrusive burials (partly destroyed when Mariette first cleared the chapel): south of the exterior stone chapel about 2.75-3.25 and irregular wall was constructed across the whole street (to keep the debris back on the south) and in the space between the wall and the S face of the chapel was a constructed a burial vault: the S end of the passage east of the exterior chapel was walled off and a shaft built to give access to the vault south of the shaft: in the exterior chamber b, another burial vault had been constructed but of this only the cuttings in the facade panel was preserved: west of room a, another burial vaults (with bent .oof) was cut in masonry and approached by a doorway cut through the ka-door; on top of this though vault in the debris, we found about 12 open graves burials (poorly mummified bodies).

It is also to be rememberd that shaft G 7130 B had been enlarged and re-used in Saitie-Ptolemaic Times (see above).

G 7230+7240: name unknown: intended as twin mastaba but actually finished as two shaft mastaba: the second from the west of the four southern mastabas.

See Figs..... Plan a Section done a.F. See Pls.....

7230

wastaba: core of massive masonry consisting of old core 7/30 (of type IV-i) with addition on south of massive corework of type IV-iii, with recess for chapel: no interior N chapel: core, 65.5 x 15.5 m.: area, 1015.25/sq.m.: prop.1/4.23: *A a casing of fine white limestone had been begun but only the lowest courses (1-3) had been laid along the E face: after white casing had been abandoned, the core was cased in crude brick which rested on top of the unfinished casing where it was already in place: the c.b. casing had the same dimentions as that designed for the white casing, 38.7 x 18.35 m., area, 1230.64/sq.m.: prop.1/3.74: the street east of the casing was filled with rubbish which followed the slope of the rock deepening from N to S: on this street filling was constructed the exterior c.b. chapel. h. 5.25 m & 7230. h. 47240. h. 5.95 m.

Chapel: 6 723047240: only one chapel all of c.b.: interior c.b.
offering room a, built in the chapel recess of 6 7240: of
type (3a): exterior c.b. chapel of type (3a)
with long open court on N/along the E face of the exterior
c.b. ran a N-S passage along the back of 6 703047340.
a) interior c.b. offering room of t pe (3a) with compound
niche in S end of W wall: 3.15 x 1.25 m.: area, 3.93

- a) interior c.b. offering room of t pe (3a) with compound niche in S end of W wall: 3.15 x 1.25 m.: area, 3.93 / sq.m.: prop.1/2.52: /walls white plastered but without trace of decoration (painting): walls more than half destroyed from top down: entered by doorway in N end of E wall, from exterior room b: opening in embrasure in c.b. casing, 3.0 m. wide and 0.3 m. deep: ka-door, outer recess, 0.45 x 0.15 m. and inner recess, 0.15x0.1m.
- b) large room enclosing the doorway and embrasure of room a: hall, 4.1 x 3.25 m.: area, 13.32/sq.m.. inner half over the white casing: entered from e by doorway in E end of N wall: in the south dwall are two doorway giving access the magazines c and d.

- c) N-S magazine south of b and west of d: 2.5 x 1.15 m.: area, 2.87/mq.m.: built over the white casing: enterer by doorway (0.55 m. wide) in N wall opening into room b: doorway found blocked wih c.b.
- d) magazine east of and parallel to c: N-S room south of b: 2.35 x 1.0 m.: area, 2.35 x g:m.: enetered by doorway (0.7 m. wide) in N wall opening into b: hlocked with c.b.: under the blocking is a basin, 0.5 x 0.5 m.
 - e) N-S corridor, originally entrance corridor, north of b, with room f west of it: 2.2 x 1.13 m.: area, 2.48/sq.m. entered from passage on E by doorway (0.75 m. wide)in N end of E wall: doorway to b in S wall and doorway to g in N wall: doorway to room f in S end of W wall: exterior doorway blocked with c.b./the main entrance from the N from room g came into use.
 - f) room west of corridor e: 2.2 x 1.4 m.: area, 3.08/sq.m. entered from corridor e by doorway (0.55 m. wide) in S end of E wall: doorway blocked by c.b.
 - g) N-S corridor similar to e and opening into it from N: 2.6 x 1.05 m.: area, 2.73 sq.m.: the western side was closed with a harrow wall shutting off the room h (probably intended originally to have a doorway at S end): room g was entered from the N by a doorway (0.7 m wide, and this was the main entrance after that in E wall of room e was blocked: doorway to e in S wall.
 - h) room east of corridor g, walled from it by thin c.b. wall a doorway jamb at S end indicates the original intenttion of making a doorway in S end of E vall:

 2.45 x 1.8 m.: area, 4.41/3q.m.: buidt over the white casing.
 - Thickness of walls: the east wall measures about 1.2 m. thick: the N wall (N side of room g, h, is 1.0 m. thick: the other E-W wall (that south of c.b., that between b and f, and that between f and h are 0.7 m. thick: the wall between b and c, d, 0.5 m., that between e and f, 0.5 m., and that between g and h, 0.4 m. thick
 - i) long N-S open court north exterior rooms b-h:
 42.7 x 4.7 m.: area, 200.39/sq.m.: in the debris at the
 N end of the room against the c.b. casing of the mastable
 but near the bottom were found about 70 mud tablets
 inscribed in black ink.

Total area of rooms.

6 - h, 31.64 sq. m.

Total area of the abole abopel.

a - i, 236.26 sq. m.

Shafts in G 723047240: two shafts, A on N and B on S, in the old core G 7130 as the mastabas E and W mx in the same row.

Shaft G 7230 A: 1.95 x 1.9 m., -10.22 m. in rock: lined above with massive masonry, 5.1 m., 10 courses:

Chamber type 5 al, on S: 4.0 x 5.4 m. and 3.0 m. high:

area, 23.22 sq.m.(irregular): capacity, 66.17 cu.m.

Passage: 2.2 x 1.0 m., 1.1 m. high: step down from floor

of passage to floor of chamber, 0.2 m. high:

found open: no traces of original burial.

Shaft 3 7230 B: altered by Ptolemaic cutting: 1.7 x 1.77 m.:-10.58 m. in rock: lined above with massive masonry, 4.1 m., 7 courses Chamber type 3 clx, on S: 4.35 x 4.35 m.: and 3.25 m. high: area, 18.92/sq.m.: capacity, 61.49/cu.m.:

Passage: 1.87 x 1.55 m. and 1.86 m. high: no trace of blocking or original burial due to re-use in Saite-Ptolemaic Times:

Luchen

APPENDIX B. p.42.

- In old chamber a limestone coffin of Saite-Ptolemaic Period with head to E:
- In NW corner a subshaft VIII: in the walls six loculi, II-VII several of them with sub shaft: the chamber of subshaft VII is broken into the chamber of 3 7240 I.

Later Constructions:

Against the c.b. casing of the mastaba G 723047240, on the S stand the small mastabas G 7241, 7243 and G 7450, beginning a field of small mastabas extending southwards.

Against the casing on the N, stands G 7231 and in front of it G 7232, both nearly destroyed.

- In Saite-Ptolemaic period, the Isis Temples appears to have been continued eastwards over the N end of G 7240: a packing of limestone chips appeared to be the foundation of a pavement which formed some sort of approach to the Isis Temple: on both sides of the packed floor were fragments of massive c.b. walls, which appears to form private chapels attached to the Isis Temple and to belong the the Ptolemaic shafts G 7240 I and shaft I is west of shaft J: associated with these shafts if the re-use of shaft G 7230 B: all these shafts had been plundered and replundered down to recent times.
- The street E of G 723047240 was found badly disturbed in recent times and the debris was very irregular with holes separated by heaps of siftings from sebakh-sives: in this street was found an unfinished shaft and a lined grave both probably of the Ptolemaic Period.
- G 733047340: name unknown: intended as twin mastaba but actually finished as two-shaft mastaba: the third from the west of four southern mastabas.

See Figs..... Printed in Volume I air

See Pls....

Mastaba: core of massive masonry consisting of old core G 7330 of type IV-i with addition on the S of massive corework of type IV-iii, recess for an interior chapel: no interior N chapel. core, 65.8 x 16.1 m.: area, 1059.38/sq.m.: prop.1/4.08:/
the core was used without any casing whatever.

1.47330, 3.85 m.: h. of 7340, 5.7 m.

Chapel: 6 733047340: single interior chapel of type \$3a) built of mixed c.b. and rubble in recess constructed ab origine in S end of 6 7540: exterior mud plastered chapel of two rooms (b and c).

- a) heavily plastered with mud: type (3a) with compound niche at S end of W wall: 3.95 x 1.5 m.; area, 5.92 \sq.m.: prop.1/2.63: \forall entered by doorway in N end of E wall opening without embrasure in room b: ka-door, outer recess, 0.35 x 0.25 m.: and inner recess, 0.15 x 0.25 m.
- b) c.b. and rubble structure bonded with walls of room a and extending into street: 3.95 x 2.5 m.: area, 9.87 sq.m.; entered by door in E end of N wall: doorway to a in N end of W wall.
- c) mud plastered rubble, 2.lx 2.65 m.: area, 5.56 sq.m.: entered by doorway in N end of E wall and thus not directly connected with born but all three rooms are parts of one structure with bonded walls: in NW corner of room c is an intruded shaft, 6 7340 Y.

APPENDIX B. p.43.

Total area, a, b, c, 21.35 sq.m.

Across the S end of the street, a c.b. wall connects the SE corner of G 7340 with the SW corner of G 7440: 0.7 m. thick: doorway near western end: this indicates that the whole street was reserved for service in the chapel about 10.3 m. north of N face of the exterior chapel of 7340, a small square room, (3.45 x 3.6 m.) area, 12.42 sq.m.: built against W wall of 7430+40: doorway in W wall: thickness of wall, 0.45 m.: probably belong4 to mastaba G 7332.

Shafts in G 7330+7340: two shafts A on N and B on S in the old core 7330 as the mastaba in the same row.

Shaft G 7330 A: 2.1 x 2.1 m., -10.98 m. in rock: lined above with massive masonry, 3.8 m., 6 courses. Chamber type 3 bf, on S: 3.0 x 2.4 m. and 1.9 m. high:

area, 7.2 sq.m.: capacity, 15.68 cu.m.:
Passage: 2.7 x 1.05 m. and 1.1 m. high: west wall of

chamber in process of enlargement: blocking removed. Shaft filled with dumped debris containing frags. of Ptolemaic-faience and pottery but low down some older

fragments: in the chamber many potsherds of types of Dyn. IV: -

34-6-1: alabaster two frags. of each from a different bowl. \34-6-2: black granite; small conical weight(?).: d., 1.9cm. h., 1.3cm.

nut dan34-6-3 to 7: Ptolemaic frags.: faience, bronze, etc. one had an incised vertical line on back:

..... mst dy-n-bh(?). not dearn 34-6-9 to 10: frags. of faience amulets.

molder 34-6-11: mud: four frags of jar stoppers, without seal impression.

J 34-6-12: flint: round ended razor blade with worked ends:

1., 11.4 cm.: w., 3.25cm.: th., 0.9 cm. 34-6-13: flint: flake, pointed ends: 1., 8.9 cm.: w., 1.35cm

th., 0.4 cm.

√ 34-6-14: alabaster: complete bowl in three pieces: d., 25.6 cm.: h., 7.0 cm.: rounded bottom with plain rim. W. 1643 $\sqrt{34-6-15}$: flint: round ended razor blade: 1., 10.2 cm. 452.

w., 2.3 cm.: th., 0.9 cm., p., 3.9 cm.: d., 1.6 cm., 34-6-17: pottery: potsherds which were set together to form

21 pottery vessels as follows:

7 large wine jars of type A-II b: WSR ware. Vol I Fig. 80 l bag shaped jar of type A-LI a: RBrW. Vol I Fig. 79 x 1 two handled oil jar of type B-LIV, special ware. Vol I neckless shoulder jar, type B-LV: RBrW. Fig. 79 878

4 bent sided round bottomed bowls of type XXX b. 79 532 3 round bottomed bowls with recurved rim: RP: typeXXXII 2 large basins with roll rim and short tubular spout, 79

XXXV = 79 1 bowl with flat base, high recurved rim and long tubular spout: type D-XXXVI: RP. 77 1 model basin: type LXXIX a: RW. See chapter XI, p.....

Shaft G 7330 B: altered in Ptolemaic Period: 2.05 x 2.1 m., -10.54 m. in rock: lined with massive masonry above, 4.9 m., 8 courses Chamber type 3 bf, on S: 4.3 x 3.6 m. and 3.4 m. high: area, 15.48 sq.m.: capacity, 52.53 cu.m.:

Passage: 3.0 x 1.3 m. and 1.15 m. high:

Canopic pit in SE corner, 0.65 x 0.65 m. and 0.55 m. deep:
no remains of burial or equipment due to reuse in Ptolemaic times:

In the walls of the main chamber, ll loculi had been cut and used:

In the lower part of the shaft, open eight loculi or passages to larger chambers:

The shaft was filled with mixed disturbed debris dumped in recently: this debris ran into the main chamber and the opening in the shaft: in shaft many fragments of xha

34- 6-16 Bead \\ \square \quad \\ \square \quad \\ \quad \\ \quad \quad \\ \quad \quad \quad \\ \quad \quad \quad \quad \\ \quad \qu

See Frank's note on original

shawabtis, dummy limestone canopic jars, etc.: from the main chamber came other frags. of shawabtis and potsherds of the Ptolemaic Period, but all burials had been broken up and plundered.

1 27-1-340

Later Constructions:

In the street E of the mastaba stand three small mastabas. G 7341 south of the exterior hhapel, and G 7331-7332 near the junction of G 7330 and G 7340.

The avenue on S, between G 7340 and G 7350 had no structures. North of G 7330 and west of the exterior c.b. chapel of G 7320. rooms g and h, stands the small mastaba G 7333 (originally \Rightarrow numbered G 7322).

In the street 1.5 m. north of the exterior chapel is a large shaft numbered G 7340 X: excavated in the rokk floor of the street close beside the mastaba face, with its chamber cut in the rock under the mastabas.

Shaft G 7340 X: 2.1 x 2.15 m., -4.75 m. in rock: unlined above: passage cut in rock to W, 2.0 m.: in the western part iis excavated a lower shaft, 1.5 x 1.45 m., which descends the through roof of chamber in NE corner, -8.1 m. below rock surface:

Chamber type 4 a(2) (abnormal) on W: $3.75 \times 3.25 \text{ m.}$ and 1.5

m. high: area, 12.18 sq.m.: capacity, 18.27 cu.m.: blocking at bottom of upper shaft, of type V b(3): Along the W side of chamber a panelled coffin (type e(p) of fine white limestone, with painted palace facade panelling: 2.1 x 0.975 m.: and 0.825 m. high: inside, 1.725 x 0.615 m. and 0.6 m. deep: krst-lid with panther skin in sunk relief on top, with two handles on each end. Cairo.

canopic recess in E end of S wall, 0.5 x 0.65 m. and 0.8 m. high (without rebated edge): plundered:

floor debris deposited by rain water and embedded in it frags. from the original equipment: a few broken bones (some in coffin and the rest in water deposited debris:

nel day 27-3-541: RW frags. of two offering jars (type A-IV). 27-3-542: copper: fafig. of corroded saucer: 9.8 cm. in diameter and 3.0 cm. high.

27-3-543; 573: fragments of gold leaf, probably from mummy. 27-3-544, 545, 574: frags. of human bones, including frag. of skull.

On top of mastaba, found in the mixed surface debris frags. of O.K stone statues and vessels and an abundance of faience frags. of the Ptolemaic Periodim including some pieces of inscribed limestone (perhaps from the Isis Temple).

In the street east of G 7330 near the N end, a large intrusive shaft, G 7330 X: descends by masonry lined shaft from top of the mastabas into rock with a large chamber with six loculi: Ptolemaic period: with frags of shawabtis, amulets and potsherds of that period.

In the street south of G 7330 X, two small built shafts x stand against the W face of G 7430: G 7330 Y and Z:

also of Ptolemaic Period. In room c of the exterior chapel of G 7340, was a built shaft and chamber, G 7340 Y: also of the Ptolemaic Period.

Note: Reisner remarks that G 7333 was originally numbered G 7322.

G 7430+7440: Prince Minkhaf and his wife: intended as twin mastaba but finished as two-shaft mastaba: the fourth from the west of the four southern mastabas.

See Figs.... Printed in Volume I a. F.

See Pls.....

Mankabax

Owner: Min-khaf, s; nswt n ht-f, rpct h;ty-c, t;yty s;b t;ty, hr 5
pr Dhwty, imy-r; k;t nbt nswt, s;w nhn, r; P nb, smr wcty,
hry hb, hry tp.

Mastaba: core of massive masonry consisting of old core G 7430 of type IV-i, with addition on the south of massive corework of type IV-iii, with recess for an interior chapel: the recess was walled off by the white casing and unused: in G 7430 a hole was broken and an interior chapel manaxiconstructed.

core 65.0 x 15.5 m.: area, 1007.5/sq.m.: prop.1/4.19: the core was cased with white limestone (x-masonry, but not the massive masonry of the five twin mastabas): casing, 68.2 x 18.3 m.: area, 1248.06/sq.m.: prop.1/3.79: Enclosing walls: close against the S wall of the mastaba, a thin c.b. wall was preserved for the greater part of the width of the mastaba: at the NE corner of the mastaba, a thick c.b. wall on rock extended from the N wall of the exterior stone chapel, replaced after a few meters by a rubble wall of the same thickness: this rubble wall ran to the NE corner and turned westwards to reach the face of room i of the exterior c.b. chapel of 6 7520: this wall formed the S side of the small mastabas G 7431 and G 7432.

Mason's Marks and Quarry Marks:
Found six casing stones with red quarry marks, two on W, two on

E, one on S and one on N.

three bore the same mark but all unintelligible: on core

three bore the same mark but all unintelligible: on core red levelling lines.

- Chapels G 7430†7440: one interior chapel of type (3a) bonded with casing but constructed in hole broken in S end of G 7430: four exterior rooms of stone and two of c.b.:

 Subsidiary N niche in casing: recess for southern chapel in 7440 closed and filled with stone, with subsidiary S niche in casing: around this an exterior chapel of u-masonry of type (5c).
- Chapel G 7430: north chapel: interior chapel of type (3a) with compound niche in S end of W wall:
 - a) 4.25 x 1.35 m.: area, 5.73 sq.m.: prop.1/3.15: with compound niche in W wall, outer recess, 1.0 x 0.3 m. and inner recess, 0.35 x 0.25 m.: opposite the niche 3.60 m. from the floor is a window 60 cm. width. entered by doorway in N end of east wall: opening in embrasure in casing, 1.3 m. long and 0.35 m. deep.

Exterior stone chapel of four rooms:

b) N-S room around doorway embrasure to room a: roof had been supported by two pillars: walls and pillars of num. lst.: 7.75 x 2.15 m.: aream 16.66/sq.m.: doorway to E in N end of E wall, afterwards blocked up with masonry: doorway probably cut later in E end of N wall giving acess to room c: doorway to room a in */wall near N end.

LW

APPENDIX B. p.46.

- c) small room N of b and leading to d: addition built against the face of room 6 on the east and against casing on W: 1.85 x 2.35 m.: area, 4.34/sq.m.: doorway to b in S wall: doorway to d in N wall.
- d) long N-S statue room north of c: 8.1 x 1.6 m.: area, 12.96 sq.m.: On the W side of the room a wall of white limestone is built against the sloping casing.: In this wall are four recesses for standing(?) statues and the vertical planes on the separating pilasters are inscribed with titles and name of Minkhaf: the final entrance to the whole/chapel was in the S end of the E wall of this room d: doorway to c in S wall: the E wall from the doorway to e to the NE corner of room d has like the adjacent casing of G 7510, been destroyed to rock.
 - e) ca. 3.3 x 1.7 m.: area, 5.61/sq.m.: stone vestibule room around the mains entrance, that to d: the north wall is destroyed and the N-S length of the room is estimated: the doorway to d is in the N end of the W wall and the doorway to the exterior c.b. chapel is in the S end of the W wall: running W under the NE corner is a drainage tunnel.
 - The original main entrance to room b from the east gave access the the whole stone chapel from the street and avenue around the NW corner of the massive core G 7520: probably at that time the chapel consisted of rooms a and b, only: when the northern rooms c and d were constructed this original doorway was blocked with masonry and the second main entrance through the vestibule e to room d was made: this second doorway gave access from the avenue between G 7510 on the north and G 7520 on the south: thus the entrance was shifted northwards and gave more convenient access: on the E of room e an exterior c.b. chapel was constructed filling the avenue to the east room e, and this was built on a layer of 1st. debris (mason's debris).

Exterior c.b. chapel of two rooms:-

- f) long E-W hall or more probably open court, built against the E face of the stone room e: 3.65 x 5.4 m.: area, 19.71/sq.m.: floor, 0:24 m. above or below floor of room e: doorway to room e in S end of E wall: doorway to room g in N end of E wall: doorway with/three-stone stops descending to floor of room g: total.... m. from floor of room f to floor of room g.
 - g) small N-S vesitibule east of f: walls destroyed on S and at SE corner: ca. 3.65 x 1.45 m.: area, 5.29 /sq.m. doorway apparently from E in S end of E wall.
 - Total floor areas:
 room a, 5.73 sq.m.:
 Stone rooms, b-e, exterior rooms, 39.57 sq.m.:
 Total stone rooms, interior and exterior, a-e, 45.3 sqm
 Total of exterior c.b. rooms f and g, 25.0 sq.m.
 Sum total of chapel, rooms a-g, 70.3 sq.m.
 - Subsidiary N niche to interior chapel near N end of mastaba in casing: 0.9 x 0.2 m. in outer recess: inner recess, 0.4 x 0.25 m. cut in casing, broken away above.
 - Subsidiary S niche: the chapel recess was blocked by the casing and in the casing was a subsidiary S niche: around this, was constructed an exterior chapel of m u-masonry: this chapel of type (5c) had a deep recess at the S end in the W end of which the subsidiary N niche was exposed: but the chapel was itself in a mastaba constructed south of the exterior stone room b of the northern chapel.

/stone

Note: Floor g is higher present of The ramp than I floor f. The ramp between them must have bed between tightentimetra mour up to some function of some f.

Exterior Southern Chapel:

The southern end of the street between the northern chapel and southwards appears to have been closed by a c.b. wall (0.9 m. thick), probably with doorway in E end: the space between this wall and the Northern chapel was occupied by various structures of u-masonry and rubble: here was built first chapel of u-masonry the lines of which were continued northwards, and south of it another offering room of rubble:a) The structure containing the offering room in which the subsidiary S niche Was exposed was a filled mastaba (G 7441) with retaining walls of u-masonry and 27.9 x 4.6 m.: with an area of 128.34 sq.m.: in the southern part is a long corridor with deep recess in S end of its W wall in the W end of which the subsidiary S niche was exposed: 9.2 x 1.5 m.; area, 13.8 sq.m.: prop.1/6.13: the niche recess measures 1.45 x 1.55 m. with area of 2.24 mq.m.: total floor area, 16.04 sq.m. entered by doorway in middle of E wall, opening embrasure in E face of mastaba: the room was probably roofed but the walls probably did not reach to the top of the subsidiary S niche, but the deep recess may not have been roofed at its W end (cf. 6020 chapel):

- In the body of the mastaba N of the chapel a trench was constructed for burial shafts, but only two shafts were made G 7440 Y, immediately north of room a and G 7430 W several meters north of G 7440 Y: both these contained burial datable to late Dyn.IV.

 Mastaba type VIII c(1).

 Chapel type (5c).
- b) Against the S face of the mastaba containing chapel room a, was constructed a small mud plastered rubble mastaba, (G 7442) containing an offering room b and a burial x shaft (G 7440 Z): 7.0 x 3.75 m.: area, 26.25 sq.m.: prop.l/1.86: with interior offering room (no niche): 3.15 x 1.55 m.: area, 4.88 sq.m.: prop.l/2.03: entered by doorway in N end of E wall opening without embrasure in E face of mastaba. In NW corner of mastaba is the shaft G 7440 Z with intact chamber containing num. ist. coffin with trst-lid: two canopic jars, 81 alab. models, lst.headrest and bead ornaments on the body: late Dyn. Along the face of the mastaba a wall of u-masonry had been constructed but only one course was left in place. Mastaba type VII dic: chapel type (4b?).

Decoration of Northern Chapel and the Two Subsidiary Niches: Northern chapel, interior rom a:

W wall, ka-door: architrave weathered, apparently not inscribed:

Tablet; badly weatheredL man in usual attitude seated at table

of bread, facing to right: table obliterated: horizontal

line across top, illegible: (iry) p(cty)......

with name Mnnw-hc-f in front of face: remains of short

list under this, partly above the bread and partly on

its right: under the table on the left, ideographic list

n mnht 1000, bull's head and five birds heads.

cross-bar: iry pety hety-e s; nswt n ht-f shm (che)

Drum: https://drum.nc-f. Wall areas not inscribed or decorated.

Exterior room b: architrave over doorway from b to a is inscribed on left probably figure of man seated at table of bread but only edge of table preserved: on the right is written vertically, dy nswt htp Inpw htp to the left of this the inscription is divided into two horizontal lines,

(1) nb t; dsr hnt sh ntr krs m hryt-ntr smyt imntyt nfr 1;w

(1) nb t; dsr hnt sh ntr krs m hryt-ntr smyt imntyt nfr 1;v

hr ntr c; nb im;h hr it-f s; nswt n ht-f iry pcty

hr ntr c; nb im;h hr it-f s; nswt n ht-f iry pcty

20.49

CAR.

(2) pr n-f prt-r-hrw m wp rnpt Dhwty tp rnpt W;g hb wr
the first of the month and the first of half month,
hcty-c lry Nhn r P-nb smr Mnnw-hc-f.

Drum of same doorway, lry pcty hcty-c s; nswt n ht-f smr Mnnw-hc-f
The walls are badly weathered and show no evidence of decoration except on the E face of the northern pillar: a vertical line of inscription, pr Dhwty imy-r; k;t nbt nswt......

Exterior room c: uninscribed and undecorated.

Exterior room d, statue-room:

were inscribed vertically with titles and names.

(1) pilaster on S, broken away: (2) signs facing to right, Mnw-hc-f: (3) signs facing to left, s; nswt n ht-f Mnw-hc-f.

part of the N wall and all the E wall to the entrance

part of the N wall and all the E wall to the entrance from the E are destroyed: built like the W wall of white limestone(?): in the debris nearby was found 17 fragments of reliefs which may have come from the E wall.

1) 25-1-721: w.lst.: frag. showing feet of large female figure, facing to left: probably wife standing behind her husband:

(2) 25-1-730: w.lst.: small frag. with large signs facing to right: m:......, with raised vertical line on left and probable.

to right: mil....., with raised vertical line on left and probably on right: prohably from in front of a large figure facing to right: possibly along the wall had man and wife at S end and man at N end facing cach other.

3) 25-1-724: w.lst.: frag.: rectangular stand with two stone vessels on lower shaft: to the left foot of

stone vessels on lower shaft: to the left foot of man facing to right.

(2) 25-1-727: w.lst.r part of two registersL (1) feet of man in long skirt standing facing to right:
(2) head of a scribe with two pens behind his ear.

 $\sqrt{5}$) 25-1-735: hands of scribe writing on roll or tablet.

 \checkmark 6) 25-1-731: knee and hand of squatting man (scribe?).

 $\sqrt{7}$) 25-1-736: small frag. with word hm-k!.

/8) 25-1-734: frag.: man standing facing to left with small animal (gazelle or calf) carried around the back of his neck.

(9) 25-1-729: frag. showing lower half of a man kneeling on one knee in attitude of huntsman: facing to left: naked except for lion-cloth: left hand hanging behind him grasping the coiled end of a leash(?) (perhaps attached to collar on neck of dog standing behind huntsman).

 $\sqrt{10}$) 25-1-732: small frag. with the name of an estate(?) and the foot of a small figure facing to right.

11) 25-1-725: small frag. with word wcb facing to left.

12-17) 25-1-722, 723, 726, 728, 733, 737: seven small frags. with unintellegible signs or parts of figures

Decoration of Subsidiary N Niche:
Architrave: six fragments of white limestone fitted together to form an architrave about 3.0 m. long: two horizontal lines with mean extending figure on left end:

Appendix B. p.49. The Tablet, crossbar, and drum are missing: the niche panels below are broken away to near the bottom of the decoration: These are part time a dateing circulation were constant of the care a part of the care and the c On each panel of the outer recess is the end of a vertical line with signs facing in (to right on S and to left on N): On S,crk r p: and on N, a number and r p. On the facade beside the niche, vertical lines on each side: signs facing in: on each sideMnw-hc-f. in my notations Decoration of Subsidiary S Niche: Architrave: frag. showing the right ends of two lines of horizontal inscription with signs facing to right: (1) dy nswt Inpw htp Tablet: raised rectangular scene with preceding side flanges: reconstructed from frags. Which form only a minor part of whole: the table scene is represented by the head of a man Suggest proubly in relief facing to right in front an incised illegible sign and on the right was an incised e with two vertical strokes below: above was an incised line of titles and name That 25-1-826 withs; Mnw-hc-f. Nothing remains of the left hand flange but a frag. with incised signs facing to right, plural sign. fre..... fry 2323 [mmw] ped The right hand flange: shows head in relief of figure facing to left, above the head from left to right, s;-f h;ty-c smr and seated gigue with sloff on shm che and in front of face Rc-k;w. On two panels, the back of the outer recess: on each side, a standing figure in relief facing in with incised inscription also sure mount and group. on S, man in full wig, chin beard, collar and hry nb sash: Shafts of G 7430 7440: two shafts in old core 7430: as in other three southern mastaba: A on N and B on S. Shaft G 7430 A: burial place of Prince Minkhaf: 2.1 x 2.1 m.: contracting to 1.7 x 1.88 m. at bottom.:-10.26 m. in rokk: lined above with massive masonry, 4.44 m., courses. two chambers: maknxchamberxofxkypexxxxamxxom Main Chamber: type 3 amx, on S: 4.8 x 5.16 m.: and 3.8 m. high: area, 24.7 sq.m.: capacity, 93.8 cu.m.: floor slopes gently from N to S: Passage: 2.8 x 1.64 m., main height at chamber, 1.84 m.: the floor is level but the roof slopes with the edge on the shaft side cut away to facilitate the entrance of the coffin: blocking not found by us (excavated by the Service des antiquites): turning recess in N wall of

Coffin Chamber: S of main chamber: 4.0 x 4.28 m.: and 2.72 m. area, 17.12 sq.m.: capacity, 46.56 cu.m.: entered by passage which opens in S wall of main room in the eastern half and enters the coffin room with the E wall: at floor level: 1.7 x 1.4 m. and 1.6 m. high (chamber much higher): in this chamber was found the red granite sarcophagus/of Prince Minkhaf, set in a coffin pit along the W side: 2.08 x 1.11 m. and 0.805 m. high (height 0.885 m. including krst lid): for description of decoration of coffin see W.S.Smith, J.E.A, Vol.XIX, Nov.1933, p.150ff: coffin pit, 3.36 x 1.32 m. and 0.72 m /: in N wall, a recess to receive the lid before the burial, 2.4 x 0.36 m.:

shaft. 1.58 m. wide and 1.6 m. deep and 1.74 m. high

with horizontal roof.

[10.26 is crossed out]

12.56m.

Canopic pit in SE corner, 0.7 x 0.7 m. and 0.66 m. deep, without rebate for lid.

L deep

doesn't agree with vol. I p. 115 APPENDIX B. p.50.

Total floor area of two rooms, 71.82 sq.m.: ? Total capacity 140.36 cu.m.

Shaft G 7430 B: wife's shaft: 2.0 x 1.95 m.-13.61 m. in rock: lined above with massive masonry, 2.27 m., ... courses: designed for two chambers but coffin chamber left unfinished: main Main Chamber: type 4 a(1), on S: lined chamber with lining unfinished: rock chamber, 4.15 x 4.6 m. and 3.35 m. high: area, 19.09 sq.m.: capacity, 63.9 cu.m.: Xima lined chamber, 3.35 x 4.05 m. and 3.35 m. high with unpaved floor: area, 13.56 sq.m.: capacity, 45.42 cu.m.

lining two or three courses only:
Passage: 1.75 x 1.45 m. (narrowest) and 3.15 m. with roof
level with roof of chamber and with low step between floor and floor of chamber (0.2 m.):

Blocking: remains of interior filled type II b: In chamber coffin pit, 2.35 x 1.0 m.: and 0.86 m. deep: Canopic recess in E end of S wall east of passage cut in rock at 1.85 m. above the floor of the main room: above the lining: 0.6 m. wide, 0.5 m. deep and 0.7 m. high, with rebate for lid.

Unfinished coffin room: a passage opens in S wall of mainx rea: room, east of middle: 2.1 x 1.15 m. and 2.05 m. high, at floor level of main chamber: the room itself unfinish. ed had part of the E and N walls cut and excavation was proceeding at several levels: the unfinished cutting measured about 1.95 x 2.8 m. and max. height of 2.5 m.: obviously unused.

The shaft was filled with dumped debris with many fragments of the Ptolemaic Period (faience etc.): the same sort of debris had run into the chamber in which was found a few blocks from the lining: near the floor was found: 27-2-219: alabaster: model basin: d., 4.5cm.: h., 1.3 cm d.base, 1.9 cm.: may have been intrusive: Chamber appeared to have been cleared out in modern times but was not reused in Ptolemaic Period. In the E wall of the shaft was an unfinished cutting of

are these drawn Pitc. 27-2-219 g moder dens gerselo. See Chapter on alm verselo.

Later Constructions:

In front of the mastaba between the exterior stone chapel and the southern side of the subsidiarym S niche was constructed a long mastaba with a chapel in which the only offering niche was the subsidiary S niche itself: see above the southern chapel of 7440.

indeterminable date.

South of the mastaba just mentioned was built another small mastaba with an offering room and one shaft: see southern chapel, above.

North of G 7430+40, between it and G 7420, in the eastern end of avenue 2, stand two small mastabas of Dyn.VI, G 7431 on the west and G 7432 on the east.

Adjoining G 7432 on the south in street 7400 E of G 7430, the angle of the old enclosing wall had been converted into a small mastaba with one burial shaft (G 7433 A).

In the Saitik-Ptolemaic Period: two c.b. structures were built on top of mastaba, one at NE corner extending into avenue 2 and the other south of it: these appeared not to be directly connected with shar shafts.

In the NW corner of the unused chapel recess of G 7440, a shaft, G 7440 madaxinxthaxPtolemaic lettered as X shafts, G 7430 W, G 7440 Y and Z were in the mastabas of the southern chapel and were of late Dyn. IV or early Dyn. V: shaft G 7430 X cut in floor of room a of the northern chapel was a Saitie-Ptolemaic shaft with numerous loculi and chambers.

APPENDIX B. p.51.

Construction of the five massive cores and mastaba G 7050.

After the construction of the eight twin mastaba, five massive cores were added east and south of the twin mastabas and a mastaba (G 7050) was added south of the small pyramid G I-c. The finished mastabas enclosing these cores are now given in chronological or approximately chronological order.

G 7510: Prince Ankh-haf and his wife Princess Hetep-heres: the greatest mastaba in the Eastern Field, built on rock east of G 7410+7420 and the northern part of G 7430+7440.

See Figs.....

See Pls.....

Owner: Ankh-haf: s, nswt n ht-f smsw rp't, h, ty-', tayty
s, b t, ty, sd, wty blyy, smsw is.t, imy r, wsht, imy r,
[k,](7)t nbt (and imy r | k, t nt nswt), hry-hb, [hry]
d,d, [hrp] i, wt [nbt], s, w nhn, wr dyw pr Dhwty, hrp
mrwt sm w [mhw], smr w ty, hry d,d, nhb, mdw Hp, hm ntr
b, mpt, Dw, w. Inpw(priest of Anubis)

The back (west) wall of the mastaba covered a descent in the rock at S end of G 7420: at the N end of the mastaba is the southern edge of the old-quarry scrap and the two mastabas G 7810 and G 7820 are built on a lower level: the casing is nearly destroyed to its foundation on the E face.

Masons and Quarry Marks:-

Chapel: interior white limestone chapel with two niches in W wall, type

(4a) with serdab behind southern or chief niche: with
exterior chapel of six rooms (b-g):

exterior chapel of six rooms (b-g):

a) 7.6 x 1.7 m.: area, 12.92 sq.m.: prop.1/4.47: the chief southern niches, measures, outer recess 1.05 x 0.4 m. and inner recess 0.35 x 0.35 m.: the northern niche is shallow, being, cut in the lining of the room, outer recess, 0.65 x 0.1 m. and inner recess, 0.2 x 0.1 m.: with serdab behind southern niche: doorway in N end of E wall, opening in embrasure in casing 4.35 m. long and 0.65 m. deep: in the embrasure on the S side is a limestone ring (footing of a wooden column?) hollow was two stone blocks at the bottom of the state hole (on which the wooden column?) rested: on the other side the pavement has broken up but probably had also born a similar emplacement: the embrasure was paved with a stone extending to the W wall of the c.b. chapel.

For Plan & Section
of James, See:

Sisa Fig. 8

Many Macrophis, I

- b) the embrasure room formed after the construction of rooms c-g: the ends were formed on N and S by two thick c.b. walls of which the southern contained a doorway: the W side was formed by the sloping face of the embrasure and casing: the E face of the room by the outside of the exterior rooms c-g: 6.6 x 2.15 m. (including embrasure): area, 14.19 sq.m.: south of the doorway in the S wall, a long N-S passage led out to the SW corner of the me exterior c.b. chapel, 7.35 m. long and 1.3 m. wide(E-W): this passage appears to have been that chiefly used in the later period of the chapel service: in the floor towards the S began a drainage tunnel which beyond the chapel curved around to discharge eastwards.
- The rest of the exterior chapel was built as one block of five rooms all bonded together: this block was separated by a space about 1.35 m. from the foot of the sloping casing of the mastaba.
- c) large E-W hall infront of doorway to room a but not symmetrically placed with reference to it: measured, 6.25 x 7.9 m.; area, 49.37 sq.m.; with wide plain doorway in W wall giving access to room a, 3.15 m. wide(N-S) not in the middle of the wall (1.3 m. from N wall and 1.85 m. from the S wall: down the middle of room ran the bases of an E-W row of four columns of which the fourth stood in the wide Goorway in the W wall: these columns stood a little N of the E-W axis of the hall (2.85 m. from the N wall and 3.35 m. from the S wall: the basis consisted of a stone footing ring (in two half circles) hollow inside and, apparently, the wooden column was sunk in the hole which descended 40-60 cm. in the floor: the stone pavement of the embrasure and room b continued into the doorway in the W wall of room c but the rest of the room had a mud floor laid on a packing of limestone rubbish: I conclude that room c was originally an open court and that later was roofed with wood supported by wooden columns: the room was enetered from room g (vestibule) by a doorway in the E end of the S wall (wath wooden door inside room g). along the N side of the hall or court, opposite the first three columns from the E and close to them ran a thin c.b. wall, one brick high, with projecting bricks at intervals: the purpose of this c.b. wall remained unexplained.
- d) The westernmost of the four rooms south of hall c:
 N-S room, 5.2 x 1.55 m.: area, 8.06 sq.m.: entered by
 doorway from e, set in the N end of the E wall: with
 wooden door on inside: the western wall is built over
 the stone pavement in front of the interior chapel:
 the room was filled with packed debris of decay and in
 this was found the bust of Prince Ankh-haf:
 against the W wall near the N end, is built a plastered
 c.b. pedestal or offering platform, 0.82 x 0.55 m. and
 0.55 m. high: on the north side of this pedestal the
 structure was extended to the N wall(?) by a low
 platform of the same width: it is suggested that the
 bust of Ankh-haf was standing on the higher pedestal
 facing to east and that the low platform was an offering
 platform: under the bust wase found 94 models of plaster:
 in same room also pottery and models:
 25-3-241: painted white limestone: portrait bust of

Prince Ankh-haf: h., 52 cm.: width of base, 31 cm.: w.shoulder, 46 cm.: thickness of base, 24 cm.: 25-2-408: 2 frags. rim of flat pottery dish. 25-2-409 to 494: small plaster models:

69 model basins, flat bottomed, 1.3-1.6 cm.:
diam., 2.2-3.2 cm.: six were painted black
inside and ten others showed traces of black
paint:

8 rudely made jars with splay foot (several mericus)
obviously neckless shoulder jars:
14 models of food offerings mostly conical loaves
of bread, but including several cakes and

APPENDIX B. p.53.

```
models of fruit.
  25-2-1230: coarse RW: oval tray with flat bottom and roll rim
       type F-XXVI a: h., 8 cm.: width, 39.6 x 37.6 cm.:
       d.base, 32 cm.
/ 25-2-1232: mud ware: "flower pot": type F-XXV
h., 16.4 cm.: d.top, 21.0 cm.: d.base, 11.2 cm.: \sqrt{25-2-1232}: mud ware: bottom of another "flower pot" of type
       XXV ....: d.base, ca.18 cm.
  25-2-1233: base of bowl stand of RW (red wash): diam.roll
       rim on base, 28.0 cm.
  25-2-1234: RBrW: model saucer: two examples: h., 2.0 cm.
       d., 9.2 cm.: d.base, 4.4 cm.
25-2-1235: RBrW: 2 model basins: k., 3.2 cm.: d., 8 cm.:
       d.base, 4.4 cm.
  25-2-1236: RBrW: 3 model basins: h., 4.0 cm.: d., 10 cm.:
       d.base, 4.4 cm.
  25-2-1237: RW: one model jar, degenerate neckless shoulder
        jar with splay foot: type XLIX a: h., 6 cm.: d.top, 4.4
       cm.: d.shoulder, 4.4 cm.: d.min., 2.8 cm.: d.splay
        foot, 4.4 cm.
```

- e) Wider N-S room east of room d: 5.2 x 2.6 m.: area, 13.52 sq.m.: in the Sw corner the room had been penetrated by a Ptolemaic (door in d): (2) doorway to vestibule rom g in N end of E wall with door in room e: (3) doorway to room f in S end of E wall (no door indicated);
- f) Small room partly destroyed, east of S end of room e:
 1.55 x 1.77 m.: area, 2.74 sq.m.: entered from e by doorway in S end of W wall: on the south wall of the badly denuded room appears to be a pilaster and this would indicate some alteration in the plan of the chapel.
- g) vestibule room east of north half of room e, north of f and south of R end of room c: 2.7 x 1.85 m.: area, 4.99 sq.m.: with three doorways: (1) main entrance to chapel from east in south end of E wall (door om inside), opening in embrasure in facade: (2) doorway to hall or court c, in E end of N wall destroyed by the intrusion of late shaft G 7511 A and place of door not determinable (probably under room g): (3) doorway to room e in N end of W wall with door in room e.

Floor area of the rooms of the chapels:
Area room a, 12.92 sq.m.
area room b, 14.19 sq.m. Total area, c-g, 78.68 sq.m. Total area, b-g, 92.87 sq.m. Sum Total rooms a-g, 105.79 sq.m.

The exterior room were filled with decay of the c.b. walls mixed with sand: over the surface of decays was deposited a layer of thieves debris littered with Ptolemaic Objects and fragments (faience, pottery, etc.).

An alabaster offering basin smashed in fragments and incomplete, was found in the lower debris in the passage south of room b; 25-2-382: frags. set together as far as possible; measured, 46 x 36 cm.: inscribed with titles in finely incised hie roglyphics, facing to right, on two sides and probably H [bub 13 wt [mst] two unattached frags give (a)c h; (ty e) to be read (iry p) cty h; ty-e, probably from the beginning of one (a) [Ind], probably part of the title of a priest of Fhnum, perhaps from upper part of right margin.

See Pls.... b. ... www..., gum bet margin.

mare 63 cmpit

APPENDIX B. p.54.

Decoration of room a of Chapel G 7510:-Interior chapel of type (4a) of white limestone, with the upper parts of all walls badly broken. W Wall: built of single large slab north of S niche. [sh mla W Wall: southern ka-door: Architrave: fragments found in chapel: single line of signs in relief facing to right, Nant [du http] Impu hat [t] esa... krś m imntyt m nb im;h hr ntr[c]... hat [t] esa... hat nt-f smśw... Impu... hat signs smith Opp.cit. PI-40a. Tablet: without flanges: frag. shows part of chair facing to right and behind it vertically(s; nswt) n ht-f śmśwh;-f.... Detail Smith op.cit. Pl.40c, e. Crossbar: not preserved: we [dyw] be ahuty ... Input He Two gragmons 3 dwgw Drum: Smith Pl. 40d. (2) p3 mb-hs-8 Niche panels: Desturged sieplace with attached sheet W wall: northern ka-door: Architrave: the S end of the architrave was found attached to a large block fallen from the wall and bore the name Htp-hrs; two other frags. with large horizontal inscriptions (signs facing to right) with border line The rest of The architrans is in above but neither to be placed: (1) part of the name of position but our fo Hetep-heres: (2) signs facing to left written vertically f smswt (determined by woman with staff) ntr Sestroyed don't 80 Tablet: lowere part preserved: chair and feet of woman facing to right at a table of bread(?): to the right of the table is the lower part of a "cupboard list", with two registers of stone vessels on the left and two registers of granaries on the right; surface under the table, weathered away. Crossbar: horizontal line with signs facing to right:
s!-t nswt nt ht-f smswt mr(yt)-f Htp-hr-s. Drum: Htp-hr-s.
The rest of the ka-door pears no inscriptions if it was ever decorated. ... Fit , quienes is drawing , Tig ... W Wall, between the two ka-doors at the N end a large figure of Ankh-haf, leaning on his staff, facing to left, without wig and wearing a long skirt: behind him is a small naked boy labelled s; s;-t-f Cuh-t-f. To the left of the large figures were 3-5(?) registers of small figures facing to right: now preserved in fragments of varying sizes: one fragment protectly from the upper part of the wall shows the ends of three vertical lines of titles/probably from above the head of Ankh-haf. this fragment has on the right the beginning of a register beginning with scribe standing facing to right reading from a tablet; other fragments show scribes and men in

respectful attitudes,, cows, men bringing birds and

haunches of meat: thus the scene is obviously a presentation scene similar to that in Khuwfw-haf between the two niches: at the top was a register of estates of which definite evidence was preserved on a number of fragments: the line of estates at the top of the wall continued over the architrave of the southern ka-door.

W wall: northern Ka-door:

Architrave: the S end of the architrave was found attached to a large block fallen from the wall and bore the name adultation the history.

The rest of the architrave is in position above the false-door, but the surface is destroyed.

Tablet: lower part preserved on wall: chair and feet of woman facing to right at a table of bread. To the right of the table is the lower part of a 'cupboard list', with two registers of stone vessels and two registers of granaries on the right. The rest of the surface of the tablet has weathered away.

Crossbar: horizontal line with signs facing to the right: st nswt nt ht-f smswt mr(yt)-f Htp-hrs

Drum: Htp-hr-5

The rest of the northern ka-door bears no inscription if it was ever decorated. Frequent No. 25-5-61 (48) might be book of another architage black with name: Hyb-hob but carned be assigned to this don. Assis, you was used

H I344

away.

Registers in front of the chief figure:

,1) This is on a level with the base of Ankh-haf's titles and now contains only the legs of two scribes. In front of them is a battered inscription evidently referring to the record-of funerary estates.

2)On the right two scribes hold up their tablets in front of the chief figure. They are followed by two men standing in a respectful attitude. Beyond a long break is probably to be restored a figure carrying the pair end of a pole supporting a chest. This may be part of a row of men present-

ing clothing in chests, on when even we actually claim.

3)A figure on a somewhat larger scale stands facing Ankh-haf. His name is probably (R) -htp. Behind him is a trace of a smaller female figure, which suggested the placing of three fragments of estates bearing offerings. Toward the left end of the register is a man carrying birds toward the right, and beyond him, beneath the architrave of the southerm false-door seem to have been seated figures of scribes, facing left, of which parts of two are preserved.

H [the kow or emtw]-8

man

/part of

from east wall. See

Fig....

S Wall: three fragments assigned to this wall indicate an offering scene or a table scene: the large figure is not preserved but should have been seated facing in to right: the three frags. (c) Wig(?) hb wr pr(t Mnw).....(d)h;bread-beer-cakes, head of bull, oryx, and birds ih-t nb

drinks, het hnt (det arm paddling) dsrt(?) and above these a dividing line that looks like the base of a jar. (2)/particle a list

(3) parts of two registers of a picture list: above basins with round cakes in them: in the lower registerm on the right is a wicker stand with sheaves of grain and a stand of fruit.

N Wall: fragments assigned to this wall indicate an abbreviat ed presentation scene/with standing figure of Ankh-haf on left facing to right, as in N wall of chapel of G 7650: frag. (1) part of the body of large figure facing out to right

wearing a panther skin: frags(1-1) each shows figure of woman er girl facing to right standing in traditional position with left hand on breast and the other hanging open: probably from behind large figure of Ankh-haf! perhaps open show a man dragging in an pryx to the left.

Reth-hr-s ither gives for this graps three graps. with in scription between the containing other name. The brief containing other name. indicate search girls believed mother GOO These prices may come could come.

E Wall: this wall is completely destroyed that none of the fragments could be assigned to it with any certainty: if the following fragments are assigned to this wall it hore a family group at the S end.

(1) several frags. of the wig of a large female figure facing to the left which could hardly be placed on the W, N or S wall. No. 25-5-61 (44,60,75)

(2) frag. showing the lower part of two boys holding each other by the hand and facing to left also, to the right of them behind, is the foot of a third figure: compare the family scene in G 7650(facing to right). Door-Jambs: no frags. assignable to doorjambs. We pluster

Facade Panels: probably decorated but no reconstruction possible.

Shafts in G 7510: the mastaba had actually only one shaft(B) but this was in the position of the chief shaft in the two shaft mastabas: the chapel was also * two-niched chapel: while the chief niche was decorated in the name of Prince Ankh-haf, the minor N niche was decorated in the name of his wife, the eldest King's daughter, Hetep-heres: therefore we cut a great trench in the axis of the mastaba northwards from shaft B, but found no trace of second shaft: this fact suggested the possibility that this Princess Hetep-heres may have been the Queen Hetep-heres II who is known to have been married to Prince Kawa'ab and to his brother King Raded?

Shaft G 7510 B: tomb of Prince Ankh-haf, built in the early part of & the reign of Chephren: 2.6 x 2.6 at top: 2.3 x 2.45 at bottom -17.53 m. in rock: lined above with massive masonry the top part of which had been destroyed by plundering, 2.65 m., 4courses.

(Nucari)

S Wall: Several fragments can be assigned to this wall which indicate an offering scene or a table scene. The size of the hieroglyphs in the inscriptions seems very small, but they appear not to be suitable for the tablet of the west wall southern false-door, which is the other possible alternative. The large figure on the south wall is not preserved but should have been seated facing to the right. 1) From a picture list of foodat the right end of the wall is a frament with parts of two registers of offerings. Above are round cakes in basins, and below two wicker stands with fruit and sheaves of grain. 2) Part of a listhof drinks: hd.t, hnt (det. arm paddling), dsrt....; and above a dividing line something that looks like the base of a jar. 3) Fragments of several vertical lines of titles, joined on the right to an offering formula: Then: 1)(imy-r;) k!t nswt....

2) dy nswt htp, prt hrw n-f m (wpt rnpt !, etc,)....

3) w;g, hb wr pr(t Mnw !)....

4) (htp !)mhw (sm;w!) ht nbt. (shit!)

Other fragments of titles from above:

1)mn lnpw r h;w.t !

2)mdw hp 2)mdw hp 3) hm ntr b; npt 4)...f mr... 5)s;(nśwt).... 4) Fragments of titles of Hetep-heres, written without border lines, but apparently from this same inscription:

Appendix B. p.56.

Chamber: type 2 amx (ramp), lined with white limestone: on S: 3.45 x 3.8 m. and 3.5 m. high: area, 13.11 sq.m.:

capacity, 45.88 cu.m.:

Passage: 2.05 x 1.05 m. and 1.0 m. high, sloping floor and roof: blocked with masonry set in plaster, type II b(1): partly destroyed: probably with portcullis slab mextr destroyed by plunderers:

No pavement: no coffin: no canopic receptacle.

Filling of shaft: filled with disturbed limestone debris mixed with sand: hole in mastaba over shaft: in shaft upper part disturbed debris and sand with frags of Ptolemaic faience (bowls and amulets, 25-1-638 to 640) and a frag. from the arm(?) of an alabaster statue & (25-1-641 and a Ptolemaic RW bowl (25-1-642): below this was again disturbed debris containing casing blocks thrown down from the upper part of the shaft: this disturbed debris extended to the bottom of the shaft and had run into the chamber to a small amount: in the debris in the doorway and in the chamber were found a number of Ptolemaic objects: faience amulets, etc., 25-1-1143 to 1149: and a wooden mummy maskm, 25-1-1150: the shaft had been completely cleared out in modern times and filled with surface debris and excavated filling.

Later Constructions:

On the south of G 7510 was built the original massive cores G 7650 and G 7520 17530, both of the same size and construction in & the first half of the reignm of Chephren and immediately cased: north of the mastaba was constructed later the nummulitic mastabas of type VI a, G 7810 and G 7820.

In Dyn. V-VI: area east of the mastaba and the exterior chapel was occupied by small and medium sized mastaba: these fell into decay and were badly denuded by weathering the area was only lightly sanded up before the Saite Ptolemaic Roman Period: south of the c.b. chapel was the medium mastaba G 7631: at an interval of several meters, north of the chapel was built G 7512 with small later mastabas and shafts (G 7513 and G 7514) intruded between c.b. chapel and G 7512: north of this were 3 badly destroyed mastabas, G 7516 andx, G 7518 and G 7519: then came a larger composite mastaba,. G 7521 north of this was G 7522 and destroyed mastabas to the NE corner of G 7510: east of this line the field ECALIBRE continued eastwards but the superstructures were badly destroyed.

Over the whole area were late intrusive shafts of which all trace of superstructure had been denuded away: most of these were of the Ptolemaic Period.

APPENDIX B% p.57.

South of the finished mastaba G 7510 and about 9 meters away were constructed two massive cores originally of about the same size, core G 7650 on the east directly in front of core G 752047530: both made about the same time in the early part of the reign of Chephren but after core G 7510. The mastabas appeared to have been finished almost immediately (a few years) but both were considerable altered in finishing. The casing blocks of the western mastaba appears to have been constructed in the middle of the reign of Chephren.

G 7650: Princess Merytyetes, her husband Akhet-hetep and parkers her mother the easternmost of the two massive cores south of G 7510 and infront of G 7530+7540.

See Figs..... Printed in Volume I A. F.

See Pls.....

Owner:

Average height of mastabas as preserved 6.30 m.

Mastaba: core of massive masonryof type IV-i: 36.0 x 16.25 m.: area, 585.0 sq.m.: prop.1/2.21: cased with fine white limestone extended to the south by casing backed with num. blocks to become core type IV-iv, containing an interior chapel: cased mastaba measures 51.75 x 19.1 m.: area, 988.42 sq.m.: prop.1/2.7: interior chapel of type (4a) with subsidiary N niche (badly broken) in casing.

average h. as preserved 6.3 m.

Masons Marks and Quarry Marks:

From Street 7500 East of Room 67530 a

Joodated guarry nades new found, (1) on back of the north wall of
the interior chapel (ineised). hist-sp 13 36d 4.

(a) on back of a casing block in the north end of the westoba

(ineised). hist-sp 13 36d 4.

a) 6.0 x 1.7 m.: area, 10.2 sq.m.: prop.1/3.53: white limestone with two niches in W wall, type (4a): chief or
southern niche torn out, outer recess(uninscribed) 1.0
m.wide: minor northern niche, outer recess 0.65 x 0.1
m., and inner recess 0.23 x 0.1 m.: entered from E by
doorway in N end of E wall, opening in embrasure in
casing, 3.95 wide and 0.4 m. deep, it is reasonable to
suppose that the famous Merytyetes stell recorded by
the two De Rouge's came from behind the empty place
of the S niche.

The exterior c.b. chapel consists of xixe six rooms:

a drainage tank north of this chapel emptied into a roofed channel which emptied into the street packing south of the chapel.

May a good

S. J. Massach

S. J. Massach

G7650 between W

G7650 between W

APPENDIX B. p.58.

- b) room around the entrance to room a, with its wooden(?) roof supported by one column (stone basis) nearly in the middle of the floor: 4.0 x 3.5 m.: area, 28.0 sq.m. entered from N by doorway in E end of N wall (door embrasure on inside): doorway to c in E end of south wall: walls plastered and colored black as far as prepreserved: the drainage culvert enters under doorway to f, crosses the E end of the room from N to S and passes out under the doorway to c: a limestone offering basin (uninscribed) sunk in the floor against the S wall near the middle.
- c) small vestibule room leading from b to d, south of doorway from b: 1.1 x 1.05 m.: area, 1.15 mq.m.: doorway from b in N wall: doorway to d, in W wall.
- d) another small room W of c and leading to e: 1.1 x 0.7 m. area, 0.77 sq.m.: doorway from c in E wall: doorway to e in S wall: it is difficult to see how these two little rooms, c and d, could have served any purpose except to complicate the use of room e.
- e) southernmost room in c.b. chapel: 1.8 x 2.77 m.: area, 4.98 sq.m.: apparently a magazine: entered by doorway from small room d, set in W end of N wall.
- f) north of room b, a vestibule room with stairway in W wall: 1.24 x 2.05 m.: area, 2.54 sq.m.: entrance doorway in W end of N wall, opening in embrasure in N face of chapel: doorway to b, in E end of S wall: the drainage culvert enters under the entrance doorway, crossed the room diagonally from NW to SE and passes out under the doorway to b: in S end of the W wall, opens the door of a c.b. stairway, 0.65 m.wide: the stairway descends to the W by three steps and then turns northwards ascending by five steps before it is denuded away: this stairway appears to give access to the roof of the chapel: the embrasure doorway must have had the wooden door (not found) on the inside.
- g) morthxofxroomxbx the part outside the N entrance: at 4.55 m. north of the embrasure entrance to room f, is an irregular rock cut drainage tank, apparently to collect the drainage from the street to the N which sloped to th S: from this tank the drainage culvert already mentioned runs southwards to pass under the entrance, then SE under the floor of room f, passes under the doorway of rooman from f to b, southwards across the E side of room b, under the doorway from b to c, and slanting to the SW under room c, under the wall between c and e, under the S wall of room e and empties in the limestone packing of the street to the south: only the wall from which form the N and S walls of room e appear to have been built after the construction of the culvert: E and W of the culvert north of entrance doorway, two long walls of c.b. were built later against the embrasure itself preserved to a length of 3.5 m.: on the E, partly built against G 7750, was a c.b. compartment with walls apparently bonded with the long N-S wall, measuring inside, 2.5 x 0.87 m.: apparently entered by a blocked doorway at S end of W wall, but so denuded that the conclusion is uncertain: the two long walls seem to form a corridor the same width of as the entrance doorway:
- Outside the E side of rooms f and b, c.b. walls enclosing three rooms were found but these were built on top of a small mastaba of Dyn.V-VI and appear not to be connected with the chapel of G 7650.

APPENDIX B. p.59.

Decoration of room a of chapel G 7650:-The upper parts of the walls were shattered and the southern ka-door had been removed.

W Wall: southern ka-door: the sides of the outerx recess, undecorated, are preserved to a depth of 0.36 m. and the south side 0.56 m. deep: but on the south the side is dressed to about 0.58 m. damax only and the remaining surface is slightly rougher where the monolith containing the rest of the niche was set: on the inside of the N side of the outer niche is evidence that a monolith was set against the inside edge of the outer recess: thus the monolith would have extended from the face of the S side of the outer recess to behind the stone forming the N side of the outer recess: the width of the monolith containing the backs of the outer recess and the whole of the inner recess, would have had a maximum width of 1.29 m.: the stela of Queen Merytyetes as reported by Margiette and the de Rouges had a width of 1 25 and would have fitted the place left by the removal of the monofith: that stella was 2.5 m. high: and appears to have included the crossbar, the back panel of the outer niche and the undecorated inner niche: on the back panels of the outer recess seems to have been a figure of a woman with one peak on the shoulder of her tunic? facing in, on each side: Et de Rougé, <u>Inscriptions hieroglyphique copiés en Egypte</u>, Pl. LXII, gives three inscriptions:

(1) horizontal line from the crossbar, hm-t nswt mryt-f ht-

Hr Mryt-its.

(2) three vertical lines from over one of the figures on the back panel,
(a) wrt hts nt Snfrw.

(a) wrt-hts nt Hwfw.
(c) in;h(t) hr Hc-f-rc Mryt-its.
(3) three vertical lines over the figure on the other side,
(a) hm t nswt/Mryt-it-s.
(b) hm t nswt/Mryt-it-s.

(b) mryt sm;-t Nbty dd iht nb ir n-s.
(c) nt h(-t-f)

the last inscription is apparently badly copied and I suggest the reading from the lines reversed,

(a) sit newt nt h-t-f.....

(b) sm;t Noty dd int not ir-t ns.

(c) hmt nswt mryt-f Mryt-it-s.

No certainty is to be won for this reconstruction and the monolith may have been decorated in the name of Akhet-hetep.

W Wall, Northern ka-door: Architrave: missing.

Tablet: woman seated in usual, attitude at table of bread, facing to right: wearing lappet wig and long tunic with shoulder ties: below table, an ideographic list (on left, ointment, bread, linen, beer and two lood-signs): above table short list in two horizontal lines, with words written vertically and continued beside and below the table on the right

(1) arm with water and ewer and basin, hown with water line and bread and a wine jar, isd, irp.

(2) shtp, sht wid, sht he beside the table, rtthty, t; nbs, two joints of meat on platters and a head of a goose and head of bull): on the right of this is a "cupboard list" of linen consisting of three kinds (1dmy hawks broken away), the sir and c;) at the top of the tablet beginning of the linen list, was a horizontal line of titles and name,

Crossbar: (s;-t) nswt nt ht-f mryt-f Mryt(it-s).

Drum: no inscriptions preserved.

Inner niche: uninscribed.

Outer niche: two back panels: figure of woman standing facing im, on each side: far hand on breast and the near hand hanging open at side: wears a lappet wig and tunic, xan ankles and bracelets: on the S, is written horizontally over her head, (M)r-t-tr-s on the N, inscription destroy Outer niche: the sides were uninscribed.

Footuple: The hierogly plus!

W Wall between the two ka-doors; on the left a woman seated at a table (of bread) facing to right; table rests on a separate base line about level with the bottom of the woman's tunic: below the table to the right, two joints of meat on platters, and a haunch of beaf (one above the other with broken space which probably bore a fourth cut of meat): to the right of the upper cut is a dressed goose on a platter: to the right of thexapperxentxiaxa this is the foot of ma small figure apparently carrying a live bird in right hand, facing to left on a base line of a second register from the bottom: At the N end of the wall is a large standing male figure facing to left, with staff: in front of him stands a small female figure facing to left with right hand on breast and left hanging: behind him there were several registers of children: above are two naked boys facing to left with hands at sides (a) holds a live bird and the second a lotus flower: left hanging: a fragment from the MacGregor collection (
(Newberry's catalogue, No.1567, Sotheby's catalogue of the Macgregor collection) appears to fit on these two figures: the first girl is labelled Htp-hr-s and the second, Hwfw....

Smith opp.cit. Pl.41,: Gulbenkian collection. /
In the lowest register between the large figure of and the table is a slaughetr scene.

W Wall. south of the S ka-door: the wall is broken off at the base line: 0.8 m. wide:

W Wall, north of the N ka-door: 0.4 m. wide: parts of three registers (with one or two more above):

(1) legs of small figure striding to left carrying bird in each hand:

(2) two figures, facing to left of which the first holds up on each side of him a small jar and the second is obliterated .: labelled Nfr-htp.

(3) two figures standing facing to left the first figure is broken and the second carries a staff in his left hand and a ring-stand(?) with jar against his breast with the right hand.

N Wall: on left end, a large figure of aman leaning on his staff, facing out to right: full wig, hry-hb sash: above him five vertical lines, facing right, broken away at top:

(a) ... hm ntr with cartouche (illegible) smr wcty:

(b)hm (B;w) Nhn shm chc.

In front of chief figures parts of three (originally four) registers of small figures facing to left.

Reg.l: two men proceeding to left carrying a pole on their shoulders: from the pole hangs a wide garment with ties hanging down from the top edge.

Reg.2: two men dragging in an oryx to left: the first man is labelled hm-k; Iwhw(?).....

Reg. 3: obliterated by weathering except foot of man and hoof of animal.

APPENDIX B. p.61.

Reg. 4: only lower part preserved: two men bring in an animal (ibex or gazelle): first man labelled hm- k; Prty-t. To the right of the registers was a blank space where the wooden door was opened against the wall: above this space at a height of 2.5 m. is a raised line indicating a border or a horizontal line above the space.

 \sqrt{s} Wall: offering scene with family group which is continued on S end of E wall: in the middle of the wall is a large standing figure (feet only preserved) facing to the right ((probably Akhet-hetep) with staff: behind him are visible the feet of a daughter and to the left of this is a wide space in which probably stood the wife and perhaps another daughter: in front of man on a separate base line stands a son also facing to right; to the right of the staffwas a narrow vertical strip apparently occupied by a picture list of offerings: below is seen two cuts of meat on platters and below them a horizontal row with bull's head, a broken space, and three heads of birds each with label above it.

E Wall: upper part of wall badly shattered but partially reconstructed from fragments found in the chapel: the wall presents two seenes: on the south is the continuation of the family group on the S wall and the rest of wall is taken by a family group markhandakandakhannatx viewing a fishing scene.

E Waal, family group on south continuing family group on the S wall on the N end of the southern group is a large figure of a woman seated on a throne facing to right; in front of her on the right stand a boy facing right and stretching out his right hand to her: with his left hand grasps the right hand of a smaller boy to the right of him: the second boy stretches out his left hand to another figure and there may be a fourth figure to the end of the wall: continued on south wall.

VE Wall: chief scene north of the family group just described:-At the N end of the wall is a family group of five figures all facing to right except the small boy who faces back to right: on the right is a large figure of a man (Akhet-herep) standing with staff: between himm and staff a small boy facing to left (feet preserved): behind the man is a daughter a large figure of Princess Merytyetes and behind her another daughter: the wife and the last daugher stand in the traditional attitude with left hand on breast and right hanging and probably the first daughter was in the same attitude: six fragments with vertical lines of inscritpion are assigned to the wall above the woman and last daughter: (1) s;t nswt nt ht-f (2) hm ntr Hwfw (3) hm ntr Ht-Hr (4) hm ntr Nit (5) Mr(t)-t-(t)-f-s: the daughter behind is labe fled over her head, s;t-s nt ht-s Hwfw..... Smith op.cit. Pl.41.

Lutel a giohing scene

this gragment

. much trans

In front of the family group is a swamp scene consisting of bird netting scene/below it and with a register of figures bringing birds and fish, at the bottom of the wall the fishing scene: -

- (1) the bird netting scene, indicated by men in the third register, bringing live birds, is represented by only a few fragments: a frag. shows the legs of two men crossing in the attitude of men springing the trap: the frags 29-7-20 in coents is shows a base line with signs below belonging to another register (the name Tti): a frag. shows a man facing to right with shoulder pole with case of birds?) hanging from pole.
 - (2) Fish-seining scene: on the wall are parts of scene preserved: on the left the upper part of three men pulling in the seams below on the right, the feet of two more figures and the upper edge of fish net with floats attached.

APPENDIX B. p.62.

(3) line of eight figures of which all but the last on the right, face to left:

(1) on left.

- (2) two figures standing facing to left but nearly obliterated.
- (3) man running but only the back of one leg preserved.
- (4) running, carrying two live birds in right and one in left hand

(5) running, but his burden indeterminable.

- (6) running, carrying two fish in left hand but object in right hand broken away:
- (7) running carrying a large fish(?) across the back of his neck.
- (8) standing facing to right: holds a tablet or sheet of papyrus again his breast with his right hand and grasps with his left his right wrist and thus appears to belong to the family group on the S end of the wall.

Door-jamb on N: on the wall, is preserved the feet of a large xx figure of man with his wife behind him: both standing facing out to right.

Door-Jamb on S: feet of large figure of man near the middle, facing out to left, probably with wife behind him: in front of him the feet of a small figure facing to right.

Facade Panel in Embrasure on N side of Doorway:

On left the feet of a large figure standing facing in to left,

that factorize with staff: in front of him
on left edge, a vertical inscription ending in a t(
(probably Akhet-hetep): between him and staff, lower
part of small figure (a son) facing to right: behind
him at least two registers of two small figures each:

(1) standing facing to left, first figure chlisters, obliterated except for feet and second figure, in short skirt with left hand on right shoulder and right hand hanging.

(2) standing with right hand on right shoulder and right hand hanging, labelled hm-k; Isi: the second has left hand hangingx on right shoulder and right hand hanging, labelled hm-k; Pr-k;.

Facade Panel in Embrasure S of Doorway:

On the right a large standing figure facing in to right with staff: on edge in front two vertical lines the first of which ends in ...;ht-htp and the second endstp (probably also Akhet-hetep): behind him on the base line are two standing figures of girls (destroyed above the waist): the first has her left hand hanging: the second holds a lotus in her hanging right hand, labelled Hwfw; above them is a second register preserved on a loose block showing two standing male figures also facing to right.

facing to right.

A number of fragments could not be definitely assigned to any wall: three small frags. with hieroglyphs.

Shafts in B 7650:

In the original core were two shafts, A on N and B on S:
In the southward extension of the cased mastabam against the S end
of the original core was a third shaft, C, and this was the
chief shaft in the mastaba.

Shaft G 7650 A: 2.07 x 2.07 m.: -11.67 m. in rock: lined above with massive masonry, 2.53 m., .4 courses.

Chamber: type 3 amx on S: 4.65 x 5.3 m., and 3.75 m. high: area, 24.65 sq.m.: capacity, 92.44 cu.m.

Passage: 2.42 x 1.15 m., and 1.26 m. high: no trace of blocking. The shaft was filled with disturbed debris mixed with sand and in this debris were a small number of faience amulets and vessels of the Ptol. Period: this debris ran down into the chamber around the doorway: the chamber and shaft had been cleared out in modern times and refilled with surface debris.

APPENDIX B. p.63.

- Shaft G 7650 B: 2.0 x 2.0 m., -0.0 m. in rock: lined with massive masonry, 4.1 m., 6 courses: type 7 x without chamber. Filled with disturbed debris: had been cleared out like shaft A.
- Shaft G 7650 C: chief shaft: 1.95 x 2.0 m., -11.4 m. in rock: lined above with massive masonry, 4 10 m.: , .. 4 courses. Chamber: type 3 afx, on S: 4.85 x 5.3 m., and 3.9 m. high:
 - area, 25.7 sq.m.: capacity, 100.23 mum. Passage: 1.95 x 1.6 m.: and 2.28 m. high: blocked with masonmy of which part remained, and outside with a portcullis slab of which pieces were found:
 - Blocking: type I b(L): in bottom of the shaft in the original filling was found the frags. of a large basin with trace:
 - of plaster used in sealing the blocking. $\sqrt{\text{Red granite panelled coffin of type e(p) stood N-S}}$ along the W wall near the NW corner: 2.35 x 1.0 m. and 0.9 m. high inside, 1.9 x 0.6 m. and 0.62 m. deep: lid with flat top and two heavy end bars 0.18 m. high, each pierced with two horizontal holes about 4.5cm. in diameter: no end handles on lid and the holes were apparently used for ropes to handle the lid: the under edge of the lid was rebated so that a projecting surface set down inside the box: the box was panelled on all four sides with a continuous series of palace facade doors, 5 on each long side and 2 on each short side: panelling marked in black paint.
 - Canopic pit in SE corner close to rock walls: 0.6 x 0.65 m. and 0.7 m. deep, with rebate for lid in upper edge.
 - Filling of shaft: disturbed debris and blocks fallen from shaft lining: about half way down was found a one-handled jug of DbW(18.5 cm. high)x which was of the Ptol. Period(29-3-194): no other objects of the Ptolemaic Period were found and the shaft had been cleared out probably much earlier than the plundering of modern times:
 - In the bottom of the shaft, badly smashed were found frags. of jars containing plaster used in sealing the blocking: 29-3-233.
 - In the chamber, a small amount of the debris had run in around the doorway but the canopic pit and the coffin were clear of debris: on the floor of the chamber were found the following: -
 - $\sqrt{29-3-252}$: alabaster: model basin: h., 2.2 cm.:
 - diam., 6.8 cm.: round bottom. 29-3-253: alabaster: model bowl, round bottom: h., 1.4 cm.: d., 5.9 cm.
 - 29-3-254: alabaster: frags. of a number of other models like, 29-3-253.
 - $\sqrt{29-3-255}$: alabaster: two frags. of shallow tray with
 - nearly vertical sides: h., 1.2 cm.: d.ca. 13.0 cm. $\sqrt{29-3-256}$: pottery, special ware: two handled oil jar of type B-LIV: upper half only: h. as preserved 24 cm. d.rim, 11.2 cm.: d.neck, 7.6 cm.: d.body, 20.5 cm. with handles, 28.0 cm.
 - 2933-257: frags. of pottery vessels of RW and RBrW. In the coffin were found a few broken human bones.

Later Constructions:

- S of the mastaba between it and G 7660, a small mastaba G 7652 is intruded.
- Against the W face of the mastaba, between it and G 7530 is a small mastaba, G 7524.
- The other structures E of the chapel (between G 7750 and 7760, and those north of the mastaba (between it and G 7510) are of the Ptolemaic Perid.
- In the street east of the mastaba the debris consisted largely of broken crude bricks from destroyed chapels (?) of the Ptolemaic Period and through this debris had been made a number of burial shafts, G 7600 R to Z.

APPENDIX B. p.64.

G 7520+7530+7540: originally a massive core of type IV-i was built behind (west) of G 7650 core and was of the same height and size: original core, 36.7 x 16.25(16-16.5) m.: area, 596.37 sq.m.: prop.1/2.2 this was obviously designed for the mastaba of G 753047540 intended for Queen Hetep-heres II but when that mastaba was finished it was shifted southwards to bring the chapel doorway opposite the space south of G 7650 so that the finished mastaba G 7530 +7540 was en echelon to G 7650: at this time the massive blocks in the northern part of the original core for a length of 17.5 m., were removed leaving only the lower part of this N end of core G 7520: with these blocks and other blocks an addition was built against the south end of the original core and thus a new core was formed called G 7530+7540: which measured 29.5 x 16.865 m.(16.5 at N and 17.25 at S): this new core measured about, $47.5 \times 16.88 \text{ m}$: area, 633.0 sq.m.: prop.lW2.22: this enlarged core was cased with fine white limestone to form the mastaba G 753047540 of Hetep-heres II.

G 7530+7540: Queen Hetep-heres II with rock cut tomb of Queen Meresankh III under its N end: west of G 7650 and en echelon with that mastaba.

See Figs..... Plan and Section done A. F.

See Pls.....

Owner:

Mastaba: reconstructed massive core (see above) of type IV-iii: about 47.5 x 16.88 m.: area, 633.0 sq.m.: prop.1/2.22: with recess for interior chapel: cased with fine white limestone: 50.37 x 20.125 m. (19.25 at N and 20.0 at S): area, 1013.69 sq.m.: prop.1/2.5: with interior chapel of type (6b). exterior stone chapel (unfinished), and subsidiary N niche: north of this niche the rock in the street has been excavated) the rock cut tomb of Queen Meresankh III.

Ito form

Chapelx of G 7530+7540: interior chapel of type (3b) or (6b) of white limestone: $4.75 \times 1.5 \text{ m.}$ area, 7.12 sq.m.: prop.1/3.11: with deep compound niche in middle of W wall flanked by palace facade panelling on each side: with print of circular offering stone in outer recess of ka-door, ka-door, outer recess, 1.3 x 0.55 m., and inner recess, 0.55 x 0.5 m.: nearly completely destroyed particularly the E wall and entrance: drawn from construction lines: entered by doorway in middle of E wall.

Exterior stone chapel: probably unfinished and badly destroyed begins at SE corner of cased mastaba and extends northwards for a minimum length of 14.75 m. and a width of 3.8 m.: the chapel with a width of 3.8 m. fills the street but leaves a very narrow space at the back of G 7660: that is, G 7660 was built after the exterior chapel had been built as far as it was ever built: the S wall is standing to the height of one course of large blocks, including the SE corner and one block in the E face adjoining the SE corner: the rock under the S end of the chapel falls away and the slope is compensated by a heavy foundation platform to bring the floor of the exterior chapel on a level with the rock in the street north of the chapel and on a devel with the floor of the interior chapel: it is probable that this chapel contained three or more rooms but all trace of the interior plan has been destroyed because most of the floor has been torn up.

Subsidiary N niche: at 22.0 m. north of N gamb of doorway to interior room a: outer recess 1.1 x 0.2 m. and inner recess 0.3 x 0.2 m., badly weathered and upper part broken away.

North of subsidiary N niche, the street has been excavated for the rock cut tomb of Queen Meresankh III(see below, G 7530) 是

RALEXQLXERSING

Date of Casing of G 7530+7540: on the back of two casing stones in place in the W side of the mastaba were found quarry inscriptions: on the E was found a displaced block with a similar inscription from which the year had been cut away:

Name: h;t sp: Month: Season: Day: \subseteq (1)..7.....wrt hts Htp-hrs. ~(3).....wrt hts Htp-hrs.

On the subsidiary N niche, on each side of the back of the outer recess is an incised vertical line with signs facing to right; (N)(h;t) sp...2(possibly 12) ibd 4(?) Smw day 22(?)

rnpt. (S)(p) rt day 7(or 6) (r) npt......

The year 7 of the quarry inscriptions was either year 13 or 14 of the king concerned (See Sethe, Untersuchungen; III p.79): the date on the subsidiary N niche is not completely preserved and might be read 2, 5, 12, 15 or 22, with which would designate the year 3-4, 9-10, 23-24, 29-30, or 43-44: the date on the south panel is wh wholly illegible: as there is no burial in the mastaba, the dates probably record on the N the beginning of the work on the mastaba and on S the completion of the mastaba as the work was proceeding on the casing and was half finished in year 13-14 I would recom reconstruct the dates on the subsidiary N niche as year 7-10 and on the S panel as year 13-14 or 15-16; this would give four to six years for the construction of the core and the casing including the chapel.

The evidence for the king in whose 13-14th year the casing was built, is purely circumstantial:

(1) the position of the mastaba.

(2) the construction of the mastaba.

(3) the family relation of queen Hetep-heres II, particularly as mother-in-law of Chephren: this evidence indicates vert strongly that the mastaba was built in the years 9-10 to i 13-14 (or alternately 15-16) of Chephren.

Decoration of the Chapel of G 7530 7540, room a:

The walls of the interior room of type (3b) or (6b) are nearly destroyed: the lowest part of the W wall and one slab in the N wall remain.

W Wall: ends of grooves just visible indicate a palace facade panelling on each side of the deep niche which was completely destroyed but traced on the pavement with a circular offering stone in the niche.

N Wall: the remaining stone shows the left hand part of the lowest register showing a procession of women facing to left: (1) feet and ankles only remain.

(2) carries a strip of linen in her right hand and in the left hand a wand with a hand carved on the end.: wears tunic with only one shoulder stemp: head missing. (3) carries a box on her left shoulder: head missing.

(4) a dwarf, carries the high narrow case usual with dwarfs.

(5) woman, wears tunic with only one strap, and carries a strip of linen held up on either side of her.

Unplaced fragments: show men facing to left: possibly also from N wall:

(1) show parts of two registers: above is scribe's case on ground: dividing line: below figure of man facing to left with righthand on left shoulder: in front and over him is written, (s)mrw m t; wy(?) and verticallyt m,, 壳

> (2) shows part of two upper registers, above is the border which ran along the top of the wall: in the upper register are three men facing to left, standing:

(a) carries start long papyrus roll held at his side.

(b) holds up cylinders jars in a stand.

(c) holds up strip of linen in right hand and in front of him written vertically, ... hm-k; Pth-n-k;w: in the second register, two figures:

APPENDIX B. p.66.

(a) man standing facing left with arms hanging at sides, labelled imy-r; pr hm-k; K;-.... behind him stands, (b) a smaller figure with left hand on right shoulder, labelled shd hm-k; Pth. spss.

Other fragments, four in number:

 $\sqrt{(1)}$ with part of one hieroglyph: perhaps Imntyt or similar. 27-4-1242.

 $\sqrt{(2)}$ 28-5-35: part of a large htp-sign. $\sqrt{(3)}$ 27-5-1, shows part of offering formula with signs written vertically, facing to below the upper edge of three compartments of a compartment list of offerings: (ntr c;) prt-r-hrw n-sx (bread, beer, cakes) m wp rnpt tp rnpt Dhwty the words in the three compartments below appear to be nswt(;), nt...., and again nswt.....

/(4) 28-5-36: fitted together of several small frags.: shows the hind legs of a cow tied together with the front part of a calf behind: evidently a milking scene.

(5) 28-5-11: fragment with subsidiary maile figure: head and shoulder facing right.

(6) 28-5-35: small door, element of panelling in W wall.
(7) 28-5-102: men carrying offering found in St.S of G 7530 probably from the chapel.

Hot drown.

Shaft G 7530+7540: the interior of the mastaba was searched for a shaft long and carefully but no trace of a shaft was found any where and the conclusion was reached that no shaft had ever been made: therefore Queen Hetep-heres II was not buried in the mastaba prepared for her.

G 7530: the rokk cut tomb of Queen Meresankh III made by Hetep-heres II for her daughter Meresankh III: under the northern end of mastaba G 7530+7540, north of the subsidiary N niche of that mastaba.

Paj. GIZA NECROP I Type RC(Id). Elem your play this type trated p. 225-229. p. 225 (8) quent Description of the ful

Rock cut tomb: type RC (id), with three rooms and burial shaft: approached from a open court excavated in the floor of the street between G 7530 17540 and G 7650: 7.75 x 3.2 m. and a about 2.0 ,. deep: area, 24.8 sq.m.: capacity, 49.6 cu.m.: this court was approached by a stairway at each end cut in the rock on the E side of the cutting: the southern stair consisted of five rises and below the floor of the street four sloping steps: the whole measured 2.55 x 0.75 m. with total rise of . 1.83 m.: the northern stair had been partly cut away when the secondary tombs to the north were constructed and only two sloping steps remained, 1.3 x 0.8 m. but originally four steps with a length of 2.65 m. in the southern scarp of this court was a rectabgular cubicle cut in rock, 2.0 m. wide (E-W) and 1.60 m. deep (N-S) and 1.63 m. high: this may have been closed with slabs to form a serdab which contained the statuettes of Meresankh II, faunce found in fragments in room a: the serdab(?) was later broken into on the roof by shaft G 7530 Z which continued downwards through the floor: the floor of the serdab(?) was . 0.21 m. above the floor of the court;

[1.63 crossed out] 1.30

MEA 30,1456 30.1457

The doorway to the chapel: on the western side of the court, two pilasters were set up of monolithic num.lst. with an architrave (now missing) across the top: the roof of the doorway and the one stone on the inside were also inserted but the rest of the chapel was cut in the rokk and decorated with sized reliefs.

Room a: large N-S hall: 7.0 x 3.33 m.: and 2.6 m. high: area, 23.31 sq.m.: capacity, 60.6 cu.m.: prop.1/2.1: entered by doorway towards S end of E wall: in W wall entrance to room b, divided by a pillar into two doorways: in the N wall is the entrance to room c divided by two doorwaysxxinxthexnxwallxisxthexentrence pillars into three doorways of which the eastern and western were blocked after the decoration of the chapel: in the

S end of W wall was a shallow ka-door: in the south wall

APPENDIX B. p.67.

> were three statue-niches below the base of the decoration (1) with a rebate with rock cut statue of squatting

scribe, on the W, probably Khemten the elder: (2) middle niche without rebate, rock cut figure of

squatting scribe, probably Khemten the younger:
(3) the western niche without rebate, with inserted

group of four small squatting scribes, probably the sons of Khemten the younger:

No.1, had been closed with a slab plastered in place and was probably made when Khemten the elder superintended the making of the chapel: the others were made later, probably after the death of Queen Hetep-heres II.

All walls and pillars were decorated with sixed reliefs. In the upper part of the E wall at . 2.15 m. from the entrance was the opening of a horizontal window which opened in the rock face of the rock cut court.

/capacity,29.89 cum.



Room b: N-S offering room: 5.5 x 2.4 m., and 2.28 m. high: area, 13.2 sq.m.:/propp 1/2.29: in the W wall is a kadoor flanked on each side by a statue-niche each containing two standing female figures probably Makexhere Hetep-heres II on right and Meresankh III on left: in the S niche the woman on the right (N) has her right arm around the waist of the other figure and the other figure has her left arm around the shoulder of the N figure with her hand on the left shoulder of that figure: the other hands are both hanging: in the right hand pair (N) the two figures hold hands with the other hands hanging: on each side of the two niches with the ka-door between them the wall is decorated with a shallow palace facadexpanelling: in the floor in front of the ka-door is the burial shaftof Meresankh III (shaft G 7530 A) $\sqrt{\text{with a black granite sarcophagus of type f(p): the N and}$ S walls were decorated as was the back of the pillar in the entrance from a: the decoration of the E wall north of the entrance had been partly outlined in black on plaster but never finished.

Room c: north of room a: 2.55 x 4.65 m. amd 2.05 m. high: area, 11.76 sq.m.: capacity, 24.1 cu.m.: cut in the rock in the northern wall are ten standing female figures separated by a narrow space into two groups, three on the E and seven to the W of them: the three figures on the E are slightly larger, while the next four are nearly the same size and the last three on the W deamsas decrease in size to a girl about half the height of the larger figures: counting from E to W,

(1) with lappet wig, probably Metep-heres II. (2-3) both with full wig.

(4-7) all the same size, each with full wig: probably Meresankh III.

(8) the largest of the three smaller figures: with full wig, probably the eldest daughter, Shepseset-kauw.

(9) smaller than No.8, with her left arm around the waist of No.8 with left hand showing on left side of that figure: the arm would have been much too long: second daughter of Meresankh III.

Smith, op.cit, Pl. 16 d. (10) smallest daughter also with full wig: above on the lintel over the niche is a horizontal line of inscription with signs facing to right: the beginning of the line is obliterated and the end: I restore the beginning, (mwt-s wrt hts Htp-hrs) s;t-s m;;t Hr-St wrt hts tyst Hr, sm;wt Nbty mry(t-f) ht Hr s; nswt (n ht-f) smrt Hr......

ending with the name of Meresankh III. The room was entered by a wide entrance from room a divised by two pillars into three entrances: after the decoration of room a, the two side entrances were blocked by masonry and on each side of the remaining middle doorway a door-post was inserted which undoubtedly bore the leaves of a two-leaf wooden door.

APPENDIX B. p.68.

Objects found in the Meresankh Rock Cut Tomb in Debris:

- 1) Pair statuette of Hetep-heres II and Meresankh III: hard yellow limestone: h.ca. 59.0 cm.: composed of about 12 frags. registered under 27-4-63 and 964: standing figure, Hetep-heres II, a little taller, on the observer's left and Meresankh III on her left: Hetep-heres has her left arm around the neck of her daughter with her left hand on the left shoulder of the smaller figure; her right hand hangs open at her side as do both hands of Meresankh III: on the top of the basis is an inscription partly restored but certainly reading miit Hr-Sthim!wt Nbty Htp-hrs on the left and sit-s hmt nswt mrat-s Mr-s-cnhb see Dunham, Bulletin of Museum of Fine Arts (Boston), Vol.XXXIV, No.201, Feb.1936. See Smith op.cit.Pl.16 c.
- 2) Standing statuette of Meresankh III: hard yellow limestone: three fragments incomplete registered under 27-5-7(head), 27-5-3 (the legs and pilaster) and 27-5-18 (the feet and front part of the basis: found in the shaft): the torso with hands from knees to neck is missing): full wig: hands p probably hanging open at sides: on the top of the basis is inscribed Mr-S-cnhi on the back of the pilaster is an inscription, (1) horizontal line marked off by incised lines (1) m; thr-Stowrt hts Mr-s-cnh; three vertical lines make separated by incised lines: (2) in s;-s smsw (3) s; nswt n ht-f, (4) Nb-m-; ht ir n-s;
- 3) Servant statuette, a brewer: white limestone: h., 25.5 cm.:
 Reg. 27-5-6 (4 frags): head, arms, and part of basis missing:
 man standing bending forward pressing much through basket
 seive into beer basin:
- 4) Servant statuette: woman squatting with basket on her lap: white limestone: h., 24 cm.: 27-5-4: head and part of base, missing: basket and arms, damaged.
- 5) Servant statuette: butcher: white limestone: h , 19.5 cm.: broken and incomplete: 4 frags.; squatting on ground with one knee up and right hand extended holding a knife (slaughtering?): 27-5-8:
- 6) Other frags. as follows:-
 - 27-5-5: w.lst.: frag. showing base and feet of small standing figure, probably serwant statuette: the piece was made separately and attached to rest by means of two pegs: feet painted yellow.
 - 27-5-9: frag. of white 1st. with part of a worked surface: 17 x 13 x 6.5 cm.
 - 27-5-14: w.lst.: two frags. of basket (painted yellow) from a servant statuette: h., 1.5 cm.: diam., ll cm.: h., 0.5-0.8 cm.
 - 27-5-13: w.lst.: part of an arm broken off a statuette (servant?): 5.6 x 2.5 x 2.3 cm.: traces of red paint. Mixed in the same debris were found the following:
 - 27-5-10: alabaster: two large frags. of flat topped circular table with diam. of over 30 cm.: these were part of the alab. table (stem and middle part of top) inset in a block of white lst. and found in the upper debris of Shaft A: this stone-table probably stood in front of one of the ka-doors.
 - 27-5-15: RP: frag. from rim of bowl with recurved rim: 7 x3.3 and 0.6 cm. thic.
 27-5-16: frags. of ox-bones: probably from the chamber of A.

"27-4-963" is officially registered as "27-4-963a,

27-4-963b, and 27-4-963c."

FA receivativation



Decoration of RC Chapel of G 7530: Meresankh III:-Facade Panel: an incised vertical line on each side, close to the

doorjambs:

(2

(N) inscription with signs facing to in to left: s;-t nswt
Mrs-cnh h;t sp l ibd l Smw hrw 21, k;-s htp hp-s r wcb-t
"The Kings daughter Meresankh: year l, month l of the
Shemuw-season day 21: her ka was at rest (and) she went
to the house of purification".

(S) inscription with signs facing to right, hm-t nswt Mrs-cnh: ht h;t sp l ibd 2 prt hrw 18: hp-s is-s nfr: "The king's wife Meresankh: year after the year l (i.e., year 2) month 2 of the Prt-season, day 18: she went to her good tomb".

The elapsed time between her death, recorded on the N and her burial recorded on S, was 274 days. 64.

I would place these dates in year 1 and 2 of Shepseskaf.

Outer doorwayL architrave: incised horizontal inscroptions

m;;t Hr-ST wrt hts nbtyht Hr wrt hswt hm ntr

Shwty smrt Hr mryt-f s;-t nswt n ht-f hm-t nswt Mrs+cnh:

signs face to right.

Outer entrance: drum: inscribed with incised signs facing to right m; t Hr-St wrt hts hm-t nswt Mrs+cnh.

Outer Entrance: N Door-jamb:

Large figure of Meresankh standing facing out to right:

lappet wig, long tunic: left hand on breast and right

hanging open (actually left hand): behind her stand two female attentants each in a separate register: the upper figure bears a box on her head: the lower figure with fly-whisk in left hand and fan over right shoulder: In front of queen are two short registers on men bringing in

n front of queen are two short registers on men bringing in live animals: in the upper register, a man labelled hm-k; Rri, pushed in a hyena to left: in the lower register a man dragging in to right a resisting oryx. Detail Smith op.cit., Pl.47a.

At the top of the jamb, a large crouching Anubis facing out to right: over it, hnty sh ntr and before it dy nawt htp: under the Anubis a horizontal line, below which is incised horizontally, the spast hr ntr c; nb......

Below the Anubis scene and over the queen are three vertical lines of inscription facing out to right, (1) m;;t Hr-St s;-t nswt, (2) wrt hswt hm-t nswt (3) Mrs-cnh.

Outer Entrance: S doorjamb:

Large figure of Meresankh standing facing out to left:
lappet wig, long tunic, collar and necklaceL holds
flower with right hand to her nose and left hand (actuallyt right) hanging open at side: hehind her again two
female attendants one above the other: the upper girl
has a flap-fan in right hand and carries on left shoulder
a round topped coffer.

In front of Meresankh, Khemten, facing to right, holds up sheets of papyrus long vertical line infront of Khemten is continued by three vertical lines ending behind his head, (1) rdy ss n hmw (2) r m; in (3) imy-r; hm-k; (4) wcb nswt im; hw hr nb-f Hmtn. "presentation of the accounts of the graftsmen by the overseer of the funerary priests, the purifying priest of the king, the one honored before his lord, Khemten".

At the top of jamb is again the crouching Anubis facing out to left: over it, imy-wt nb t;-dsr: in front, dy nswt htp and horizontally under it, ;ht spsst hr ntr c; nb t; dsr.

Under this and in front of queen (above Khemten inscription) are four vertical lines with signs facing to left:

(1) mg;t Hr-St wrt hts (2) smrt Hr mryt-f (3) ht hr hmt nswt s;t nswt (4) Mr-s-cnh.



4

Room a, West Wall:

(14

S end of wall, south of the entrance to room b: shallow ka-door in shallow recess with architrave above.

Architrave: inscribed with two horizontal lines, incised signs facing to right, not separated:

(1) dy nswt htp dy Inpw htp hnty sh ntr krs-t m smyt imntyt.....

(2) m wp rnpt tp rnptw;g monthly and half
monthly and Mr-s-cnh vertically across both lines.

Tablet: Meresankh seated at table of bread, facing to right
(conventionalized): the chair or throne has lion xexxxxx
represent on the side, sitting with straight fore-legs
forming the front leg of the chair: Meresankh III wears
lappet-wig, long tunic: left hand on breast and right
hand half extended open palm down: across the top,
horizontally s;t nswt n ht-f mryt-f hmt nswt Mr-s-cnh
under this the inscriptions in vertical lines ont the
right, facing right smrt Hr mryt-f tyst Hr srt hts ht
Hr hm ntr Dhwty hmt nswt Mr-s-cnh: under the table is

an ideographic list (mnht, ss, hnkt, t;).

Cross-bar: inscribed m;; Hr-Sts;t nswt mryt-f
hmt nswt Mr-s-cnh.

Drum: and panels below are not inscribed.

Wall S of ka-door: two registers each bearing one standing figure of which the upper figure is smaller: above, man standing facing to right, with left hand extended palm up and right hand hanging (hry wdb attitude): below, larger figure of man standing facing to right, short wig, short skirt: left hand stretched out with palm down: in right hand a roll of papyrus labelled rh nswt imy-r; pr imy-r; hm-k; ss im; hw Hmtn: in front of him on ground a cylindrical roll-case: On the wall above the architrave: a rwo of offerings, picture tixtxlist, bread, cakes and jars): probably the upper figure on the S is calling this list.

The figure of Meresankh north of the ka-ddor belongs to the decoration of the S doorway to room b (see below).

Room a, W wall: the doorway to room b: on the pillar dividing the door-way to b is a standing figure of Meresankh facing to left and on the S side of the doorway (N of the ka-door) is a similar figure of Meresankh, facing to right:

On S side next to ka-door, Meresankh standing facing to right:
lappet wig, long tunic, dog collar, necklace; bracedets and
anklets: right hand hanging open: left hand open on breast:
behind her three female servants in a vertical row:

(1) carrying long case over her shoulder.

(2) with box on her head and staff in her left hand:

(3) with sistrum in her left hand and a small sack in her right hand: in front of queen a vertical line of signs facing to right, m;; Hr-St wrt hts hm-ntr nbty-b;-p-f

on the E face of the pillar north of the doorway to b:

Meresankh, standing facing to left; bead garment, lappet wig right hand open on breast: left hand hanging: inscription in vertical line in front of her, m;;t Hr-St wrt hts/htx/ Wrxhmxmtxxmbtx* hm ntr Ht-hr nb Iwnt, hmt nswt Mr-s-cnh.

W Wall north of double entrancex to room b:

Family group, Queen Hetep-heres II, Queen Meresankh III Prince Nebemakhet and Siz other children:

(1) Standing figure of Hetep-heres II, facing in to left clad in double peaked tunic, natural hair (colored yellow with red lines), necklace and anklets! hands open crossed on breast and covered with by garment: in front of Hetep-heres is a vertical line, with signs facing to left: mwt-s m; Hr-St wrt hts ssm i;mt shm pr hmt n nswt Htp-hr-s.

(2) The next large figure, to the right, is Meresankh III, standing facing to left: clad in long tunic, overlaid with a panther skin, natural black hair, short: dog collar, necklace, bracelets: right hand closed on breast holding a fly-whisk and left hanging open: above her are five vertical lines with

/nbty

with signs facing to left:

- (a) s!-t-s nt ht-s s!t nswt nswt m; t Hr-St Mr-s-cnh
- (b) wrt hts wrt hswt.
- (c) hm ntr Dhwty smrt Hr.
- (d) sm; wt Nbty mry(t-f).
- (e) hmt nswt mryt9f Mr-s-cnh.

Smith op.cit., Pl.44 a.

(3) The third large figure is Prince Nebemakhet, standing to right of Meresankh and facing to left: full wig necklace, bracelets, hry-hb sash and short skirt: right hand half extended open with palm down and left hand hanging with handkerchief: over his head two vertical lines with signs facing to left,

(1) s;-s s; nswt n ht-f hry hb hry d;d;.

(2) Nb-m-!ht. (4) Small girl sitting on her feet immediately behind figure of "etep-heres: clad in long tunic and bandeau around head: holds up a fan(?) or whisk(?)

in right hand and has her left hand on her right shoulder: no inscription: probably a servant.

(5) In front of Meresankh, stands a naked boy with side lock and necklace; faces to left but with head x turned back towards Meresankh: holds a lotus to his mother in his left hand and holds in right hand a live hoopoe by its wings: labelled Hnt-r-k;.

(6-8) Behind Nebemakhet, stand three naked children in three registers arranged vertically:

(a) above a boy with finger of right hand on his mouth: necklace: with left hand hanging.

(b) girl holding hoopoe by wings in right hand and

left hand hanging open.
(c) boy with finger of right hand in mouth: left hand hanging open.

W Wall: architrave over the double entrance to room b, extending from above the head of Tetep-heres on the N to above the head of Meresankh south of the doorway: two horizontal lines of incised inscription with signs facing to right:

(1) above, dy nswt Inpw htp hnty sh ntr nb krst m smyt imntyt hp-s m htp hr w;wt nfrt hppt im;hwt hr-sn i;w nfr n-s hr ntr c; prt-r-hrw n-s t; hkt psn m hb nb monthly and half monthly feasts with n-s dbht rc nb Mr-s-cnh &xxxixx] vertically across both lines.

(2) mwt-s s;t nswt m;;t Hr-St Htp-hr-s s;t-s m;; Hr-St wrt hts ht Hr smrt Hr mryt-f tist Hr sm; wt Nbtym mry wrt hswt hm ntr Dhwty s;t nswt hmt nswt Mr-s-cnh.

Room a, North Wall: two pillars and architrave: the middle doorway was altered by the insertion of a stone lintel when the two side doors were blocked and a wooden door set in the middle / doorway:

Eastern Pillar: in relief, stands Meresankh facing to left: short hair, long tunic, wide necklace, bracelets and anklets, dog collar: right hand open on breast: left hand hanging open at side; above her head, four vertical lines with painted signs facing to left:

(1) s;t nswt nt ht-f.
(2) m;;t Hr-St.

- (3) smrt Hr.
- (4) Mr-s-cnh.

in front of her is a naked boy painted on later, standing facing to left with wide necklaceL arms hanging at sides labelled s; nswt n ht-f Rc-dw;

Western Pillar: in relief standing figure of Meresankh facing to right: clothing and attitude as on E pillar but reversed: above her four vertical lines, facing to right (a) s!t nswt nt ht-f: (b) tist Hr (c) ht Hr. (d)Mr-s-cnh: again a boy in front of her, painted on later: standing with body facing to right but with head turned back towards his grandmother: with finger of right hand on his lip: labelled s; nswt n ht-f N-wsr-rc (in a cartouche -cnh.



APPENDIX B. p.72.

old lintel over middle doorway: m;; Hr-St Mr-s-cnh. Later lintel over middle doorway: s;t nswt nt ht-f hmt nswt Mr-s-cnh.

Lintel over W doorway: smrt Hr mryt-f Mr-s-cnh. Lintel over E doorway: m;; Hr-St Mr-s-cnh.

Architrave across whole wall: horizontal line of words written vertically with signs facing to right but the first sign on the right, Inpw faces to the left: dy inpw htp nb th dsr krs-t-s nfr hr ntr c;prt-r-hrw n-s m hb(nb) c nb iht nb nfrt m nswt dy htp w;h n-s wdn stp n stpt i;wt nfr spsst hr Inpw hnty sh ntr.

blocked border in red.

Room a, South wall: the wall is divided into two scenes, an offering scene above and a picture list of funerary furniture below Offering scene above: Meresankh seated facing to left; on a block xxxxx throne decorated with papyrus plant: clad in long tunic and-wig: holds in left hand coiled stem of lotus and in right hand another lotus held to her nose: rest obliterated: squatting on ground in front of her, a small girl with hands crossed on breast: in front of chied figure is a picture list of offerings in five horizontal lines separated by horizontal lines in relief; rows of offering,-

(1) cooked geese on tables, lotus, meat, etc.:

(2) vegetables and fruits on tables:

(3) rectangular table with vegetables, etc.

(4) nearly obliterated.

(5) offerings on a rectangular table:

Intruded in the W end of the lowest line is a dog facing to left close to the squatting girl and he belongs to the chief scene not to the picture list.

On the left of the picture list are three registers of figures

facing to right. Jeft

(a) three men on right, standing facing to right, all

with arms crossed on breast and hands on shoulders: then follow ten squatting men (4-13): Nos.4-6 have right hand on left shoulder and left hand grasping the right fore-arm: Nos.7-8 have the same position with the hand reversed (right hand grasping left arm): Nos.9-13 have the left hand closed on breast and the right extended palm dowm.

(b) nine men bearing offerings to right: Nos.1-2 bring a table of food: LNos. 3 with cooked goose on skewer: No.4 in one hand a basin on a stand and rest not clear: labelled hm k; war-tsw: No.5 holds up two beer-jars: No.6-7, obliterated: No.8 varries live goose: No.9 holds three ducks in each hand by their

necks: No.10 holds hyena in his arms.

(c) twelve men: Nos.1-2, standing facing to right, holding out hide with tail or similar: No.3 with haunch of beef: Nos.4-3, cutting up a bull: No.6, sharpening a knife: Nos.7-8, cutting up a bath second bull: No.9 sharpening a knife: Nos.10-11, two men dragging in an oryx: No.12 carrying a young gazelle in his arms.

Furniture scene, below:

on the right a figure of the ss kdwt Rh; y painting a statue of Meresankh: the man and the statue stand on a base line a little higher than the main scene.

To the left of this, on a platform stand a bed-canopy with two servants making up the bed.

To the left of the canopy, the wall is divided into two subregisters:

(a) servant facing to left laying a fly-whisck on an arm-chair (with lion under arm); then a carrying chair resting on ground and a servant is laying a pole on the chair and a fan is leaning against the back of the chair: then a woman carrying in her right hand a flap-fan and in her left a sack: then a man carries a long box (curtain-box?):/ then

two women carrying a chest on their shoulder; under the chest is a monkey on a leash; finally two women one behind the other, each carrying a tray on her head.

I two women comy

No.1 is labelled him - k3 - Raic

APPENDIX B. p.73.



(b) begins with pieces of furniture and continues with about 12 figures bearing other pieces: (1) long rectangular box (table?) on which stand a round topped box, a square box (on which stands a headrest), a large rectangular chest on short legs, a tall colthes bag (with calf's head); a long box on which stands a high table (on table, a flywhisk): then two women carrying between them a shrine: three women carrying unidentified objects: woman bearing a gray on her head: No.6-7 also carry something between them: No.7, a female dwarf bearing something on her head: the rest is illegible body damped (perhaps five women).

This lower scene appears to continue the lower scene

on the S end of E wall.

Below these two scenes are the three statue-niches (mentioned above) with figures of squatting scribes, Khemten Khemten-sherm and the four sons of Khemtensher.

Room a: E Wall, south of entrance doorway: Five registers: two with boating scenes and three with scenes of craftsmen at work.

1) Topmost register: two boats proceeding to left:

(a) First boat: MAXPRO a ship with prow missing having been on a stone now torn out of place: of the usual flat bottomed wooden type as in Reg.2: rowed by at least four oarsmen(6?): in the middle sits Meresankh in carrying chair with a woman standing behind: two steersmen each with long steering oar.

- (b) second boat, papyrus raft paddled by three paddlers: just in front of first paddler, stands the lookout or plot with body facing the stern but with face turned to look forward, holding in right hand a stick stretched to boat in front: in the middle sits Meresankh on a throne smelling a lotus flower: in front and facing her a little maid with fly-whisk: behind the queen a woman holds a sunshade over the queen: one steersman with long steering oar.
- 2) Second register: two ordinary wooden boats with long shelter: the first rowed by 11 men and the second by 8 men: proceeding to left.
 - (a) First boat: on prow man with long pole (pilot): second man squatting on top of long shelter: the back part of the cabin is shrouded in cloth: in front of the sheeted part of the cabin, stands a female figure with lappet wig, perhaps Meresankh: 11 omrsmen: three steersmen with long steering oars: the prow of the boat bears a animal head turned backwards.
 - (b) Second boat: like the first; with 8 oarsmen; animal head on prow: two steersmen at stern: in front of the sheeted part of cabin, woman facing forward and resting one hand on frame of cabin.

- 3) Third register: craftsmen at work:
 (a) on right end, a standing statue facing to right: infront of it stands facing it a painter holding shell palette and painting with brush the statue: over him faintly visible as kdwt Rh;y.
 - (b) a seated statue of woman facing to right: in front of it the sculptor (gnwty(?) In-k;-f) working on statue with rubbing stone held in right hand.
 - (c) three men dragging a shrine with ropes to the right: the first man faces to left and the other two to the right: the shrine contains a standing female statue and rests on a sledge; the shrine is shown as if seen from the front with open doors: statue faces to left: to the left of the shrine, drawn partly over the door-leaf is the standing figure of a man facing to right holding a double bellcenser: behind another standing man steadies the shrine with his hands.



APPENDIX B. p.74.

- (d) three men dragging a seated statue not in a shrine to right: another man in front of statue facing to left holds out double bell-censer.
- 4) Fourth register: various craftsmen at work (stone workers?) (a) two men polishing a granite sar cophagus: the second
 - man stands on a platform or low box. (b) a break enough to take a man at work.
 - (c) man bending over a rectangular object (perhaps a wooden coffin).
 - (d) man squatting facing a ka-door.
 - (e) man striding to right and the rest of the wall is too obliterated to be interpretated.
- 5) Fifth register: metal workers and men covering furniture with gold(?):
 - (a) wooden shelter supported on three (or three pairs) of posts: on left man squatting beating out sheet of gold: then four men in two pairs facing each other, smelting gold(?) with blow pipes.
 - The register then divided into two subregisters:
 - (b) in upper register, two men facing across a low stand(c) in upper register: a round topped chest with a man
 - squatting facing to left.
 - (d) two men facing squatting.
 - (e) in lower register: carrying chair on ground: on left man squatting facing chair: on right a man bending over chair, and facing to right.
 - (f) lower register: man squatting facing to right, with an indeterminable object in front of him.

Lowerphy

Room a: E wall, north of entrance: a composite scene with four registers on the south and consists of (a) La large figure taking the whole height of the four registers, (b) a swamp scene taking the height of the upper two registers, and (c) the four registers on the south of which the third and fourth run under the swamp scene:-

a) Standing figure of Ka-wa'ab, facing to left, with staff in right hand and handkerchief in left hand: drawn with short hair but adorned later by painting a full wig: broad necklace and string of beads and amulets; short skirt, bracelets and hry-hb sash: above six vertical lines of inscription with signs facing to left:

- (1) (1)tf-s iry pcty (2) s; nswt p smsw n ht-f:
 (3) hry-hb hry d;d; (4) shm i; t ntrt (5)'; Dw; w (Letopolis
- (6) K; wcb.

b), Swamp scene: Hetep-heres with Meresankh behind her, standing on a papyrus raft pulling papyrus-flowers: Hetep-heres plucks with both hands: Meresankh plucks with the right hand while her left is around the waist of Hetep-heres: standing in front of Hetep-heres is a small naked boy with his right arm around her leg and holding a lotus-flower in his left hand (faces to right) at the stern of the raft another boy holds a punting pole and had his leg twisted around the pole: netepheres wears a lappet wig, long tunic, broad necklace and anklets: Meresankh has short hair with papyrus bandeau and is clad in beaded tunic, dog-collar, broad necklace, bracelets and anklets: on the right is a papyrus swamp nearly obliterated by rain water entering from window at top of wall: inscription partly horizontal and partly vertical: mwt-s s;t nswt bity Hwfw, and horizontally , wrt hts Htp-hr-s s!t-s mryt-s and continued vertically, m;;t Hr-St wrt hts Mr-s-cnh: the inscription continues n gowing the left in five horizontal lines:
(4) sss-h-s wid n Ht-Hr m phw hnc mwt-s m;;-sn iht nb

nfrt nt-t m Mht-iw(?).

"She plucks the papyrus of Hathor in the swamp "together with her mother and they behold all the "good things which are in the Delta".

c) Five registers of various kinds: (1) top register: procession of 13 estates proceeding to left: (a) female. hbt-Hwfw: (2) male, Mtn-Hwfw (3) female, Hwfw-nfr-htpt: (4) male, Df;-k;-Hwfw:
(5) female, Irt-rc-ddf: (6) male, Idb-Hwfw:
(7) female, (h;-fht-Hwfw): (8) male,Hwfw: (9) female, Mrt-Hwfw: (10) male, Hwfw-mmn-hr-ist-Hr
(11) female, Shty-Hwfw: (12) male, Iw-Hwfw:
(13) male. Pr-h-t-kf. (13) male, Pr-h-t-k;. Detail op.cit, pl.49 a. X (2) bird trapping scene with two subregisters on the right; chief scene, the springing of the bird trap by five men pulling the rope; another man gives the signal with a white cloth and a third man gathers the birds from the trap: the net is spread over a pond and the man gathering birds is wading in the pond outsaide the net: on the left, a man walks to right, holding a bunch of ducks in each

registers: (a) upper register: man facing to right, tieing bunches of papyrus labelled sss w;dt mhy: two men facing weaving a mata and two men facing tiening a mat, labelled wh, kni.
(b) man putting birds in a crate: two men facing

hand: behind this man on the right, are two sub-

and plucking birds.

(3) third register: begins on left under swamp scene:

(a) man leads a crane to left holding its beak:

(b) crane walking alone:

(c) three geese walking also to left,

(d) herdsman leads a bull, labelled.

man leads in a stalled ox to left, labelled,

(f) man leads a calf, labelled in the mother (g) man leads a calf, labelled

(g) man leads a calf, labelled It.

(4) Fourth registerbegins under swamp scene and the cranes: from left to right:

(a) four papyrus rafts proceeding to left, prt m s; hnc nhbt in mhtyws. first raft bears a heapp of bird-crates and a crew of four including an overseer of which the third man is poling the raft and the 4th man threatens with a papyrus bundle the first man of the second raft: the second raft is empty and bears a crew of three of which the first is paddling and the third man on the stern in punting: the thrid raft had no cargo but bears a crew of three: the fourth raft has a crew of four: the crews of the third man and fourth rafts are engaged in a struggle for precedence: the second man of the fourth raft grasps the stern of the 3rd raft while the first man is engaged in a fight with the whole crew of the 3rd raft: the last man of the third raft grasps the ankle of the first man of the 4th raft who is being attacked with paddlesx by the first and second man of the 3rd raft: the third man of the 4th raft squats holding his own paddle and that of the second man: the fourth man of the fourth raft is poling that raft.

(b) a man standing facing to right labelled hk; n niwt, leaning on staff overseeing ramp trampling in deed driven by four men with whips: to the right is a man sowing seed followed by a man with a sack of seed carried on his

Room b West Wall:

In middle of wall a shallow ka-door in a shallow recess:

tablet obliterated, woman seated at table: crossbar
inscribed with titles and name, nearly obliterated
sit nswt nt ht-f? milt Hr-St Mr-s-cnh, rest blank;
across the top of the wall (architrave) runs a horizontal inscriptions with large incised signs facing to x
right; nswt dy htp dy Inpw htp nb t; dsr hnty sh ntr
krs-t nfr m smyt imntyt ihp-s m hryt-ntr m nb im;h hr
ntr c; nb krst prt-r-hrw n(?)-s m i(milt).....hmt nswt:

(2) m.......hmt nswt:

(2) m......prt-r-hrw im n-s m wp rnpt tp rnpt
Dhwtyt wig skr hb nb wr rkh prt-Mnw monthly and half
monthly feasts, n sit nswt nt ht-f milt Hr-St Mr-s-cnh.
On each side of ka-door is a statue-niche containing two

female figures standing (see above).

On each side of this central arrangement of ka-door and statue-niches, the wall at N and S end is covered with a shallow palace facade panelling.

NO! Lotus is certainly not held to nose, but <u>over lap.</u> FOA '39

rother ovaludop

Room b, North Wall: offering scene:-

On the left, a larger figure of Meresankh seated facing to right: lappet wig and long tunic: left hand extended closed holding x(coiled stem of lotus?) and right hand holding lotus to her nose(?): in front of her a vertical inscriptions with signs facing to right, wrt hts s;t nswt Mr-s-cnh;

In front of her are two other registers (3-4):
1) Upper register: (a) man standing out a bird in both hands: (b) standing holding pair of birds in each hand: (c+d) two harpists: (e-f) two flute players

hand: (c)d) two harpists: (e-f) two flute players: (g) male singer, squatting like the musicians: (h) standing man carrying a calf in his arms:

(i) man bearing patter with meats. (2)

Second register: (a) man kneeling on left knee holding out two small nw-pots, one in each hand: (b) standing holding cooked goose in right and conical cake in left: (c) four dancing girls (kicking back with left foot), with left hand on hip, and right hand uplifted) (d) three girls singing standing with right hand outstretched palm up and left hand on hip): (e) three women standing clapping their hands.

Third register, under whole scene: the left side of the register is obliterated and illegible: under the first figure of register 2, stands the first visible figure in register 3: (2) standing with two upraised beer(?)-jars: (b) standing with bird in right hand and supports baskets of cakes on his head with left hand: (c) standing, with duck in right hand and on left shoulder a tray with a conical cake(?): (d) standing also with tray with cake on his left shoulder and holds x with his xight right hand against his breast: (e) basket of cakes with pictures of various cakes, on space above the basket: (f) a man bending over another basket also with pictures of cakes on wall above it: (g) a woman facing to right and a man facing to left pick up a basket of cakes: (h) to the right of this is a picture list of offerings in three horizontal lines, (1) cakes, (2) cakes and basins, and (3) wine jars.

wine jars.

4) nearly obliterated on the left: (a) man standing facing to right (overseerm?): (b) two horizontal rows of wine-jars: a man facing to left is filling last jar of lower row: (c) man bending ever large jar with his hands inside (preparing jar for filling: (wic) standing man (overseer?) facing to right: (e) in front of him, five small scenes: (1) upper part of register, man squatting on ground forming bricks(?) and above this bricks(?) set to dra(?): (2) below No.(1): girl grinding grain(?), labelled ir(i) n-k hsb: (3) larger figure kneeling on one knee with left hand-outstretched to fire, head turned back to left and right hand stretched

APPENDIX B. p.77.

out touching back of figure in scene No.2, labelled, wn this nnt;: to the right of him as an oven(?): and be yound that another oven(?) and scene (5): (4) above the ovens in scene (3) is a man or woman squatting on ground: sifting grain or flour: facing to right: and a woman on knees grinding grain, labelled m rdyt ss: (5) continues scene (3) to right: man or woman squatting on ground before an oven, facing to left.

Room b. South Wall:

above an offering scene and below a judgement scene: Upper Secne: on right Meresankh seated facing to left: at table of bread: wears aappet-wig and long tunic: left hand half extended to table, her right hand is also extended but is obliterated as far as the elbow: above the table and in front of her face are four vertical lines with signs facing to left: (1) m;;t Hr-St...... (2) Tyst Hr hm ntr Ht-Hr (3) smrt Hr mry (4) Ht Hr..... on the left of the table is a large compartment list of offerings.

To the left of the compartment list are two registers of

figures facing to right:-

(1) upper register, (a) man kneeling on right knee, right arm bent at elbow with palm up and left hand extended with palm up towards list of offerings, labelled s;h-t in wt: in front of him a hieroglyphic list of offerings (beer, bread, cakes, and geese):
(b) man kneeling on right knee both arms half

extended, each holding a nw-pot.

(2) three men facing to right bearing offerings:

(a) holding out a goose in both hands: labelled hm-k; hry hb Iry: (b) man holding a goose in his arms: (c) carrying a haunch of beef in his ram arms: Lower Scene: judgement scene:

On the right is a larger figure squatting facing to left in front of him a scribe's case: the other figures face to right: the squatting man is probably Khemten the elder: to the left of the case, are five scribes squatting all in the attitude of writing: (c) a standing figure with a stick in his left hand while with his right he holds the head of a bowing man (d) four men squatting on the found ground (delinquents): (e) man standing has his left hand on the head of the last squatting man: (f) a standing man.

Above the scene runs a horizontal line of inscription with signs facing to right: badly obligerated: at the right end can be seen the name Hmtn: near the middle signs become again legible, det. crossed sticks hk; w followed by another long block: finally, .. pr-s dt m b;h imy r; pr int hk;w d;d;t m s;w.

East Wall: consisting of an unfinished scene north of doorway to room a and a small scene on the back of the pillar which stands in the entrance from a to b:

On the wall north of the doorway: wall plastered flat on the plaster an outline drawing in yellow (faded red) of three registers of a harvest scene:

1) upper register: two men carrying bag(?) of grain on a pole: followed by two others carrying a similar burden: all face to right.

2) Second register: on the right a stack of grain(?) and to the left, three figures winnowing.
3) stack(?) of grain: to the left a man scooping up grain in a container not identified: to the left are two other figures(?) very sketchily drawn.

Back of pillar in entrance: obviously inscribed after the death of Khemten the elder: on the left stands Meresankh facing to right wearing a lappet wig, collar and long tunic: right hand hanging open at side and her left hand holding a blue lotus to her nose: before her facing her stands Khemten-sher: wears short wig, necklace and short skirt and holds out a papyrus with both hands: above the

Involentent of offerings is one herizontal line of inscription uning to left in his re mb his hant new Mrs-enh in his re mb dt.

APPENDIX B. p.78.



head of Meresankh are five short vertical lines of inscription (incised),(1) m;;t Hr-St wrt hts, (2) s;t nswt nt ht-f (3) smrt Hr (4) hmt nswt mryt-f (5) Mr-s-cnh over Khemten is one horizontal and three vertical lines: (1) m;; ss (2) imy-r; pr imy-r; hm-k; (3) nb im;h hr nb-f (4) ss Hmtn-sr.

Herry Kong hard branger

(23,25)

Room c: see the description of the chapel above for the ten statues and the architrave inscription cut in the N wall: the other walls were not carefully dressed or decorated: a fault in the rock near the NW corner which appear also in the SE corner had been smeared with plaster: On the south wall near the SE corner were some figures, perhaps an account, written in black paint on plaster.

Shaft G 7530 A: the burial place of Meresankh III: excavated in the rock floor of room b of the chapel, in front of the ka-door: no other burial shaft was found in the mastaba G 7530 +7540. Shaft, 2.04 x 1.94 m., -5.1 m. in rock: no lining above: but mouth of shaft probably covered with stone pavement after filling: found open and partly excavated. Chamber, type 4 a(1), on W: 4,66 x 3.12 m. and 1.98 m. high:

area, 15.4 sq.m.: capacity, 28.79 cu.m.:

Passage, 2.08 x 1.56 m.: Expacity; and 1.98 m. high: blocked with masonry bound with plaster, blocking type II b(1), but nearly destroyed: the thieves had dammed back the


shaft filling temporarily with rubble. Coffin: (black) granite sarcophagus of type f(p): stood N-S along the W wall of the chamber near the N end : 2.16 x 0.87 m. and 0.795 m. high (0.975 m. including 1id) cavity, 1.835 x 0.55 m. and 0.58 m. deep: the box is decorated with simplified palace facade panelling with six simplified palagexfaradexpanellingx "doors and seven simplified panels on each long side and with three doors and four panels at the ends: each corner is bounded on each side by a panel: around the top of the box on all four sides is a horizontal rounded molding, 5 cm. wide and projecting 1 cm. but this does not xxx continue down the sides at the corners. A narrow (5.5 cm.) projecting (1 cm) base band runs around on all four x sides under the panelling. The lid is flat on top and has a lightly marked hollow cornice maxaxixxfour around the top on all four sides: the underside of the lid is rebated so that the projecting part set in the cavity of the box: there was lid-ledge in rock wall on W but a bank of rubble had been constructed between the box and the wall to support the lid before closing the Em coffin: the lid had two rough projecting handles on me each end.

or is it rud

6.78. bottom

Inscriptions on the coffin: East side, at the top, a horizontal line with signs facing right, mist Hr Sth, wet htm , wet heart, her signt ismt hum not B3-f(?), sm: wt nb.ty mry, a it now t nt ht.f mrt.f Htp-hr-a hum not B3-f(?), sm: wt nb.ty mry, a it now t nt ht.f mrt.f Htp-hr-a

E. side, vertical line at N. end, di n (i) n s3t.(i) hmt nswt Mr-s cnh:vertical line at S.end, identical with N.end. W. side, horizon tal line with signs facing right, m33t Hr Sth wrt hts wrt hswt etc, identical with the horizontal line on E.side. N.sæde, at top horizontal line with signs facing right, tist Hr, smr Hr, hm-ntr t3sh, s3t nswt Htp-hr-s., S.sæde, at top, hm ntr Dhwty, (imy)ht Hr, hmt nswt mrt.f s3t nswt Htp-hr-s.



Appendix B. p.79.

Canapic Pit, partly sunk in rock and partly built of rubble: south of the SE corner of the coffin: 0.7 x 0.68 m. and 0.48 m. deep: this probably contained the four limestone canopic jars found in the chamber: one jar was in the canopic pit, two others were just outside (one on the N and one of the W) and the fourth was in the NE corner of the chamber.

Burial: dismembered by plunderes: most of the bones were found scattered on the floor of the coffin but a few were on the floor outside: almost complete: examined by Dr. Berry and stated by him to be a woman of about 55+3 years (52-58 years old): deposited with the other royal remains in the Cairo Museum together with the coffin.

Objects found in shaft and chamber of G 7530 A:

The shaft was found not completely filled: the debris sloped down from about 50 cm. below the E side of the shaft to nearly two meters on the west: apparently after plundering the thieves had raked into the shaft the debris they had excavated with part of the floor debris of the chamber: I judge that this was done at the end of the O.K. before the cemetery had sanded up but certainly not in the Ptolemaic Period: in the disturbed debris near the top was found:-

had been inserted the stem of a circular alabaster table and table badly broken: inscribed on ton of with the top rested on the top of the block; both block

inscribed on top of table,

h.ca.1.8 cm.

inscribed on top of see p.68: 27-5-10 a. / 27-5-18: yellow limestone: fragment of a statuette of(part of the base and feet) part of the statuette No.27-5-3, with name Meresankh incised on top of base.

XXXXXXX 27-5-19: black granite: frag. of indeterminable object

 $15.8 \times 12.5 \times 6.0 \text{ cm}$. 27-5-20: copper: three frags. of small saucer: d.ca.5 cm.:

Found in the chamber: which was paractically free of debris: 27-6-1: w.lst.: canopic jar with domed lid: h., 24.8 cm.: d.rim, 10-12.7 cm.: d.body, 15 cm.: d.base, 9.5-10 cm.:

depth, 21.5 cm. 27-6-2: w.lst.: canopic jar with domed lid: h., 24 cm.: d.rim 13 cm.: d.body, 16 cm.: d.base, 10.2 cm.: depth 20.5 cm.

27-6-3: w.lst.: canopic jar with domed lid: marke of tube borer in bottom: h., 23.2 cm.: d.rim, 14 cm.: d.body, 20.3 cm.: d.base, 13 cm.: depth 20.1 cm.:

27-6-4: w.lst.: canopic jar with domed lid: h., 24.0 cm.: d.rim, 12.6 cm. d.body, 15.6 cm.: depth, 22 cm.: d. d.base, 9.6 cm.:

These four jars would have required a maximum cavity of $36.5 \times 36.5 \text{ cm}$: and 0.27 cm. deep: the canopic pit measured 0.7 x 0.68 cm. and 0.48 m. deep. the greater size of the pit indicates that the jars were contained in a wooden canopic chest set in the pit which was probably covered a stone slab.

 $\sqrt{27-5-5}$: copper: model saucer, oxidazed: d., 4.3 cm.: h., 1.0 cm.: with round bottom.

1/27-6-6: copper: adze blade frags.: the surface has a thick green patina but the breaks have only red oxide patina: long blade with back end in disc-form: 1., 16 cm.: w., of cutting edge, 3.3 cm.: min. w., 1.5 cm.: w.of round butt, 2.1 cm.: th., 0.5 cm. with patina.

27-6-7: copper of saucers and implements: not fitting together representing probably two or three saucers and two or three implements.

APPENDIX B. p.80.

when 27-6-8: mud: lumps of jar sealings: no trace of impressions:

AVIa? $\sqrt{27-6-10}$: RW, red wash: ovoid jar with roll rim, neck: type A-VIa, h., 16.7 cm.: d.rim, 5.4 cm.: d.neck, 4.6 cm. d.body, 11.9 cm.

XXXXXX

part of rim and side: d.body, ca.20 cm.

DXXXIX? /27-5-12: RP inside and outside: flatt bottomed basin with flating concave sides and rim on edge: type D-XXXIX a: h., 10.7 cm.: d.rim, 33.6 cm.: d.base, 11.5 cm.: broken and incomplete.

27-6-13: flint nodule: elliptical shape, with green copper stain on one side (used for sharpening copper blade): 11.1 x 8.1 x 5.2 cm.

27-6-14: RP inside and out: frag. of bowl , shape not determinable: 4.0 x 3.5 x 4 cm.: obviously from a large basin

27-6-15: RW: frag. probably from large bowl: 8.5 x 7.5 x0.9cm

27-6-16: RW: three small frags.of bowls and a frag. of bone: probably from a jar of type A-IV.

27-6-17: RP. frag. from bowl with contracted mouth with rim painted black: 4.2 x 1.1 x 0.6 cm.

27-6-18: green(?) faience, faded: 45 cylindrical beads: x 1., 1.4 cm.: also bits of copper and tiny scarps of gold foil.

Street E of G 7530 +7540:

Between the exterior chapel of G 7540 and the rock cut tomb of Meresankh III (G 7530), was an unfinished cutting in the rock, 3.75 x 1.25 m., and 0.85 m. deep; with sides xontxexim contracting slightly downwards: from the S end descended two steps (three rises) and at the N end the rock had been cut down but not to the bottom of the cutting: this cutting represented clearly the beginning of a rock cut tomb similar to the cutting for the exterior court of G 7530, but was near the middle of the street not on the E side: I assume that the workmen began cutting the rock cut tomb of Meresankh III here and were shifted to where we now have the finished tomb of Meresankh III.

The street north of the rock cut court of G 7530 has been altered by the cutting and construction of later tombs (see below after G 7520).

Against the N end of G 7530 17540, a stairway ascend from above the street level to the top of the core of G 7520: this stairway probably originally ascended from the street level but fell into disuse when the later mastabas were built.

G 7520: the N end of the original core similar in size and construction to the core of G 7650 and standing west of it: this end was left when the core G 7530 † 7540 was shifted to the south: the casing of the finished mastaba G 7530 † 40 was built in a trench across the old core.

See Figs..... Plan done A. F.

See Pls.....

APPENDIX B. p.81.

Mastaba: core of massive masonry of type IV-i left on N: When & G 7530+40 was cased: 17.5 x 16.2 m.: area, 283.5 sq.m.: prop.1/1.08: not cased but later a num. 1st. wall was built on the W side of the street in line with the front of casing of G 7530+7540, and enclosing a narrow space along the E face of G 7520, core, containing two shafts and apparently part of G 7524.

Chapelx G 7520: no trace of a chapel was found but probably the rock chapel of G 7524 served all the shafts of the OKKYIM this area.

> Shaft G 7520 A: north of middle of core; 2.0 x 1.8 m.:-10.7 m. in rok:

area, 22.32 sq.m. capacity, 80.35 mu.m.

Passage: with wider outer half, 2.2 m. long: N half, 1.7 m. and inner half, 1.0, wide: height, 1.2 m. Blocking: completely removed.

Coffin: roughly built stone coffin: inside, 2.25 x 0.6 m. and 0.7 m. deep: covered with single flat slab: inside was found the bones of a disturbed skeleton.

The objects found in the debris in the chamber were mostly of the Ptolemaic Period, but three limestone jar lids may have been from canopic jars belonging to the originat burial.

Filling of shaft and chamber: the shaft had been cleared out in modern times and was found filled with disturbed dirty debris containing objects and frags. of the Ptolemaic Period: 27-2-275 to 285: faience: frags. of shawwabtis, vessels and amulets: in shaft.

27-2-286: frag. of purple glass from a bottle(?): modern : found in shaft.

27-2-287: red pottery: crudeley modelled head of animal: h., 2.6 cm.: w., 2.8 cm.

27-2-290 to 294: frags. shawwabti, faience vessels, flint flake and RW saucer: lower in shaft.

Found in the chamber:

27-2-341: limestone: three disc lims: diam.15 cm.: thick, 1.6 cm.: probably from canopic jars.

27-2-342; 343: lime stone: two rudely carved mortars or similar: Ptolemaic Period.

27-2-344 to 349: faience: frags. of shawwabtis, amulets and vessels of Ptolemaic Period.

27-2-350: RW potsherd from large vessel.

G 7520 and G 7530 40: Later Constructions:

When Meresankh III was buried in G 7530 A, the group of tombs consisted of the white cased mastaba G 7530 + 40 with its unfinished exterior stone chapel, the rock cut tomb of Meresankh III (G 7530), and the uncased core of G 7520, probably with the burial chamber of its shaft A already finished and perhaps already used: the rock cut court of G 7530 was entered by two flights of steps, one leading down from the south and other from the north: the southern stair was approached from the south probaly by a path south of G 7650: the northern stair was approached from the north and the street in this direction must have been open to the avenue south of G 7510: further from the street north of the court of G 7530, a flight of steps was constructed leading up to the top of G 7520, perhaps for the burial in G 7520 A.

Before the excavation of the rock cut tomb, G 7530, the nummulitic mastabas, G 7550 and G 7660, had been built belonging to two brothers of Meresankh III, "prince" Dawanehor and "Prince" Ka-em-sekhem: the N end of G 7550 was enclosed by a rubble wall and at the east end the space between this enclosing wall and the exterior chapel of G 7540 was filled with limestone debris to bring the level up to that of the floor of the chapel of G 7540: from this platform a ramp (with rubble retaining wall on W and filled with limestone debris)

This is the only mention found to date of a G 7624, presumably a rock-cut tomb just north of the the chapel of Meresankh III, G 7530-sub. This is either an otherwise unrecorded tomb, or (less likely) a mistaken reference for G 7524.

was made against the back of G 7660 and descended to the lower level of the street east of G 7550: the space between the E face of the exterior chapel of G 7540 and the back of G 7560, is very narrow and it seems doubtful whether the ramp was used for access to the rock cut tomb, G 7530: it may have been used for passage from the chapel of @ 7550 to

the chapels in the street G 7400 and G 7300.

In Dyn.V, the rock of the street north of the rock cut court of Meresenkh III was considerably altered and a rock cut tomb > numbered G 7624 was excavated; about the same time the rock surface east of the core G 7520 was enclosed with a wall of u-masonry, G 7524 A-B: a little later and E-W wall was built on top of the rock scarp cut for G 7524 and completed by another wall on the north to form G 7524 C-E: in the N end of the rock cut court was then constructed the small mastaba, G 7525.

In the Ptolemaic Period a number of crude brick chapels were built on the top of G 7520 and over the debris filling the streets: the debris was penetrated by a large number of intrusive xxx shafts of this period: these had all been plundered and the plundering had continued down to recent times: as a result the surface debris on top of the mastabas and in the streets was strewn with fragments of faience, shawwabtis, amulets,

and vessels as a well as pottery.

Note only one shoft G. 7540 U shewn on was strewn with fre and vessels as a we the E foce of G 1540.

The E foce of G 1540.

Intrusive Ptolemaic shafts:
G 7540 0 R 8 m. 7540 south of G. 7540. No Mace of shoots Sa Y. 9-8-41 hold Kingdom

G 7540 Q, R, S, T; south of mastaba G 7540 from W to E.
G 7540 U, V, W, S, Y along the E face of G 7530+40 south of the rock cut court of Meresankh III.
G 7530 Z: was an A. shaft which cut into the roof of the rock

cut serdab(?) in the south wall of the rock cut court of G 7530. and also shoff X in front of K meriding niche G 7520: L, M, N, in street east of G 7520 and south of the rock cut tomb G 7524: G 7520 N in the rock cut court of that tomb.

G 7450: south of the line of twin mastabas which contained G 7410420 and G 74304 40: west of the south end of G 7540 and in front of G 7350. On the top of the mastaba was/fragment of a block of white limestone, h., 16.5 cm., w., 15 cm. thickness ca,, 5 cm.: 27-5-17: date incised vertically with traces of red color ha h;t sm; t;wy ibd 3 smw: and to the left, above, the letter w: this date is not necessaryly connected with 6 7450.

See Figs...... Plan a section done

See Pls.....

Mastaba: massive core of type IV-iii: 50.8 x 18.0 m.: area, 914.4 sq.m prop.1/2.8 with chapel recess towards S end of E face with offering room of type (3a) but without casing.

Chapel: interior chapel of type (3a) with single niche at S end of W walli destroyed to stone pavement and reconstructed from wall: destroyed to stone pavement and reconstructed from (construction lines scrored on floor: 4.3 x 1.6 m.: area, 6 sq.m.: prop.1/2.68:Jentered by doorway in N end of E wall: Tour walls of the chapee preserved up to 1:15 m. height, destroyed width of niche, 1.0 m.; apparently rather shallow: not trace of decoration found: floor of chapel of the shallow base of mastaba core.

and there in G 7450: two shafts on which A on north was used and B on south had no chamber.

eines preserved shaft G 7450 A: 2.05 x 2.05 m., -9.3 m. in rock: lined above with massive masonry, 5.1 m., .5.... courses. Chamber: type 3 al, on S(unfinished): 4.25 x 5.35 m. and 2.75 m. high (where finished): area, 23.74 sq.m.: capacity sa. 75.28 cu.m.: floor uneven with lump of rock near middle.

Passage: 2.25 x 1.05 m. and 1.05 m. high: blocked with good masonry set in plaster, broken through on E side: blocking type II b(1).

& Keight of The mustales 5.80 m

construction

APPENDIX B. p.83.

debris and in this was a burial pit built of num slabs: cavity, 1.85 x 0.75 m. and 0.55 m. deep: covering probably of one or more slabs not found. empty.

Shaft and part of chamber filled with disturbed debris which contained no objects (either of Refor Ptolemaic).

Shaft G 7450 B: 2.0 x 2.1 m.: ends at rock surface: lined with massive masonry, 5.1 m., type 7 X, without chamber or any trace of burial.

Later Constructions:

Built in the street E of the N half of G 7450 is a late O.K. mastaba numbered G 7451, built on the floor debris about level with the floor of the chapel of G 7450: the space be tween it and G 7540 was walled off to form an open air corridor.

South of the mastaba, is a wide area filled with small mastabas of Dyns V-VI.

North of the mastaba, is the remains of a rubble enclosing wall, about 0.6 m. wide: and about 2.1 m. from the core: about opposite the middle of the N face of the core this enclosing wall turns at a right angle and ends against the core: from there eastwards it runs parallel to the similar enclosing wall of G 7430 40 but is denuded away after a distance of 4.1m

In the Saite Ptolemaic Period was constructed a large c.b. chapel (Pt.VI) over the debris filling the street east of G 7450 north of chapel with two shafts 7450 X and Y of which X was a large communal burial place with about 30 burials and a large number of stone and faience amulets and faience xhaw shawabtis.

Other Ptolemaic structures of c.b. less well preserved were shown by frags of walls; (1) on the mastaba between shafts A and B: (2) over the street between G 7450 and G 7440.

Intrusive Ptolemaic shafts were found: G 7450 Z penetrating the S end of the mastaba, G 7451: and G 7440 X and Y, north of that mastaba.

G 7350: in alignment south of the line of twin mastabas, G 7310+20 and 7330+40:

See Figs..... Plan only done A. F.

See Pls.....

Name: No name; Hetep-heres II (?).

Mastaba: core of massive masonry of type IV-iii: 51.75 x 17.25 m.:
area, 892.68 sq.m.: prop.1/3.0: with interior chapel of
white limestone in recess in core: cased with fine white
masonry of sloping slabs (y-masonry): bonded with chapel:
cased mastaba, 55.0 x 22.5 m.: area, 1238 sq.m.: prop.1/2.4:
built on rock surface descending to south so that the height
is great at S end: average height, .52 m.

Masons and Quarry Marks:

On the backs of the white casing stones were found a number of quarry marks 11 on N and 3 on W:

The inscribed frag. 27-5-17 found on top of G 7450 warms and probably came also from G 7350 as G 7450 was not cased; treads, rapt sm;t t;wy;abd 3 smw with a w beside it: if this attraction is correct then G 7350 was built in the first year of a king not named (perhaps, Shepseskaf or Weserkaf).

Another block in the N wall bore the sign w,d with a bird to the left, perhaps W,dt-Nhbt and with illegible signs below, perhaps bity(or nswt bity).

The other marks were unintelligible.

h mathem

Chapel: interior chapel of write limestone of type (3a) and Subsidiary/ miche (monolithic) in casing: around the subsidiary/ niche:

is an exterior c.b. chapel three rooms:

Room a: interior chapel of w.lst. with plain compound nichex
in S end of W wall: 4.25 x 1.45 m.: area, 5.16/sq.m. prop.1/2.86: plain compound niche at S end of W wall: x outer recess, 0.95 x 0.3 m.: inner recess, 0.3 x 0.25 m. entered by doorway in N end of E wall opening in embrasas embrasure in casing, 3.35 x 0.3 m.: floor paved with stone on which the walls were built: this floor is, .O. 76. m. above the rock outside the doorway: behind he niche is a small serdab: chapel walls nearly destroyed but apparently decorated.

Serdab: behind niche in W wall of chapel room a: 1.9 x == m.: area, 1.71 3.04 sq.m.: built on pavement of chapel: found open and empty.

Subsidiary N niche: a monolith set back in the casing wall: outer recess, 1.15 x 0.5 m.: inner recess, 0.4 x 0.4 cm. stone floor of niche at 0.86 m. above rock.

Exterior c.b. chapel around N niche:

Exterior c.b. chapel of type (1c) resembling the old chapel of type (la) in plan: consists of four rooms lettered a-d: measures on the outside, 12.1 x 3.05 m.: area, 36.9/sq. n.

- a) offering room, 4.6 x 2.35 m.: area, 10.81/sq.m.: prop.1/1.95:/ in the niche are the remains of two bowl, stands: in front of this is a rectangular low c.b. platform on which rests a slab of alabaster (with rounded corners), measuring in the middle 1.47 x 1.35 m¹/₃ and 9.20 m. thick: the top is slightly higher than the floor of the niche: on the south between the slab and the S wall of the room is constructed a solid stone bench 1.27 x 1.05 m. and 9.39 high with top level with top of alabaster slab: on the N of the slab and between it and the N wall of the room, stands an offering table consisting of a horizontal slab resting at each end on and upright slab, 1.95 x 0.4 m. and 0.30 m. high (rising higher than (alab: slab) room a is entered from the E by a doorway in the N end of the E wall: a doorway in the E end of the S wall leads to room b and another in E end of N wall leads to room c-d.
- b) small E-W room (magazine?) south of a: 1.15 x 2.3 m.: area, 2.64 sq.m.: entered by doorway from a in E end of the N wall.
- c-d) mmalixExXxxxxxxx north of room a was a large room measuring, 3.8 x 2.4 m.: area, 9.12/sq.m.: with the W side formed by the casing of the mastaba: entered by doorway from in N end of E wall: the large room had a thin c.b. wall which ran W from just south of the entrance doorway for 1.4 m. to a zer corner where it turned south 0.6 m. to a finished end: wall, 0.35 m. wide (of brick): on the plan the space south of this wall is lettered c and the rest of the room d: it is uncertain whether the space c was a room of which the W wall south of a doorway to d had been destroyed or not: in the E end of the S wall of c-d was a doorway to room a.

Total area of rooms a-d, 22.57 sq.m. Total of interior and exterior chapels, 28.73 sq.m.

Decoration of Interior Chapel of type (3a):

No decoration was found in place but a number of fragments were recovered from the debris in the room:-27-4-951: four fitting fragments from a wall relief: white limestone: ca.0.78 m. long and 0.42 m. high with a

thickness of 11-17 mm; shows the heads of two women standing facing to right: on the right the figure is taller, and wears a lappet wig and tunic with dog collar and broad necklace: right hand hanging and left open on her breast: the smaller figure behind her shows only head and left and shoulder; bare head, tunic, dog collar and broad necklace: over her head is written horizontally (signs face to right), hmt nswt Mr(-s-cnh): this piece should probably assigned to a scene on the N wallof the room but might have come from the one of the door-jambs:

h alaboster

Least

Lbe

I consider the smaller queen to be Meresankh III and larger her mother Hetep-heres II: it is on this rex reconstruction that I assign G 7350 to Hetep-heres II, built in the reign of Shepseskaf: this relief is now in the Cairo Museum.

XXX 127-4-1086: w.lst.: 4 frags.: relief: architrave, right end: words written vertically, Inpw dy htp hnty sh ntr krs m hryt ntr imntyt nb im;h apparently from architrave over ka-door.

 $\sqrt{27-4-952}$: w.lst.: small frag. 11 x 12 cm.: in relief, bit of shoulder of figure facing to left; with part of harizontal line above hm ntr faces to left above the muds hm ntr faces to left above the muds 27-4-886: W.lst.: frag. 4 x 4.5 mm.: shows foot of chair in

relief: found a little south of the mastaba in street

Decoration of Subsidiary N niche:

The back panels of the outer recess were decorated on each side by a standing male figure facing in: destroyed to waist: on S, man standing facing to right with staff held vertically in far hand and handkerchief in near hand (right): with skirt pleated on side: on N, man standing facing to left apparently unfinished above: staff in far hand, left hand weathered but probably with hankerchief: plain short skirt.

Shafts In G 7350: three shaft in medial axis of mastaba lettered A, B, C, from N to S: A was the chief burial place but was west of the subsidiary N niche: B, in the middle, was probably unused while C on the south had two burial chambers: I assign the shaft A to Hetep-heres II.

Shaft G 7350x A: 2.05 x 2.15 m., -11.45 m. in rock: lined above with massive masonry, 3.73 cm., courses.

Chamber: type 3 am, on S: 5.2 x 6.5 m., and 4.95 m.high:

area, 33.8 sq.m.: capacity, 167.31 cu.m.: the rock cut

walls be red constructions horizontal and vertical but were not distinctly preserved: one horizontal line at a height of 0.9 m. above the floor bore the mark mh 2 ("3 ells") which indicates that the floor was not cut to the depth designed by about 12-15 cm.: on the E wall was a curious double line which bent upwards on south

(something like the sickle-sign). PassageL 2.26 x 2.06 m. and 2.62 m. high: step down, 1.6 m. from floor of passage to floor of chamber: blocking of masonry set in plaster, type II b(1) but possibly with portcullis slab: blocking partly broken away. Coffin: plained red granite box with flat lid: type d,

uninscribed: found overturned from its original place on W side of chamber in the middle of the floor: with broken broken mummy spilled on the floor: box measures, $2.32 \times 0.97 \text{ m.}$ and 0.87 m. high: cavity, $1.88 \times 0.54 \text{ m.}$ and 0.6 m. deep: flat lid with rebated under-edge and two handles at each end: the lid is 0.14 m. thick.

Canopic pit: in SE corner, 0.78 x 0.8 m., and 0.46 m. deep: with rebate in upper edge on N and W: probably contained a wooden chest of which frags. were found in the debris.

Objects Found in shaft: the shaft was filled with disturbed debris m mixed with large blocks thrown down from the casing of the shaft:

Addam 28-3-61: copper: four frags: perhaps from model tools: found wupper part of shaft, perhaps intrusive.

Found in the doorway and partly in shaft, in debris: \$\sqrt{28-3-87a}\$: WSR with discol\(\frac{1}{2}\) ored wash: 4 jars of type A-II b: broken and incomplete: h., ca.43 cm.: diam., body, 25.4

 \rightarrow 28-3-87b: RW: smaller jar also of type A-II b: h., 34 cm.: diam. body, 22.6 cm.: with potmark incised on shoulder, (two crosses one above the other of which the top upper cross has a horizontal line across the top).

APPENDIX B. p.86.

```
28-7-1 to 9: alabaster: 82 model basins of type SX...
ranging from diam. 5.0 x 42 cm birth
 Found in floor debris of chamber:-
            ranging from diam. 5.0 x 4.2 cm. high to diam. 7.0 x 5.6
            cm. hughi.
                                                of type S - Xa
     /28-8-1 to 11: alab.: 11 model basins: measuring (1)h., 5.7 cm.
            and diam., 7.1 cm.: (2) h., 6.1 x diam., 5.8 cm.:
            (3) h., 4.1 x diam., 6.7 cm.: (4) h., 6.0 x diam. 6.8 cm. (5) h., 4.1 x diam. 7.1 cm.: (6) h., 5.7 x diam. 6.0 cm.
            (7) h., 5.3 x diam., 7.1 cm.: (8) h., 6.5 x diam. 6.5 cm. (9) h., 5.6 x diam. 5.9 cm.: (10) h., 4.9 x diam. 5.3 cm.
             (11)h., 6.2 x diam., 6.3 cm.
    \sqrt{28-8-13} to 18, 20: alab.: 7 model basins of forms and sizes
             like 28-8-1 to 11.
       28-8-36: alab.: model basin as above: h., 5.6 cm.: d.top, 5.6
       cm.: d.base, 3.2 cm. June SX 19
Total alab. model basins a see examples.
       28-8-12: alab.: model jar of type S V e(special): barrel jar
            with raised belt marked with network of incised lines:
            h., 8.2 cm. d.rim, 3.0 cm.: d.belt, max., 5.2 cm.:
            d.base, 2.6 cm.
       28-8-19: alab.: model cylindrical jar of type S I d: base
             only: diam., base, 3.8 cm.: with splay foot: h., 2.6 cm.
       28-8-21: alab.: flat-topped circular table: 13 frags. from
             the top: stem not found: d.top, 35.5 cm.: thickness, 1.4
www 28-8-22: black granite: small fragment: 4.6 x 5.4 cm.
       28-8-23: lst.: unintelligibee lump.
       28-8-24: ox-bones: broken bones.
      28-8-25: RBrW: base of a necklace shoulder jar(?); type B-IW?
             d.base, 9.2 cm. h, 4.2+cm.
       28-8-26: BrW: frag. from the neck of a jar of from a ringstand
                 pe 747 a: diam. top rim, 5.2 cm.: h., 4.8; cm.
     28-8-27, 28: many broken potsherds of various types.
       28-8-29, 30: human bones (incomplete skeleton).
       28-8-31: linen: frags of decayed mummy-wrappings.
       28-8-32, 33: potsherds.
       28-8-34: limestone: nearly spherical hammer-like object with
             groove around the middle, perhaps a rubbing stone:
             31.0 \times 26.0 \times 20.4 \text{ cm}.
       28-8-38: bone of lower jam with teeth complete.
       28-8-3%: mud: two frags. of jar stopper not impressed.
       28-8-38: wood: frags. prbbably from canopic chest.
       28-8-39: linen: roll of bandage from the mummy(?): d., 2.3 cm
             length, 5.5 cm.
       28-8-40x to 42: frags. decayed wood.
       28-8-43: wood: large block of wood: 29.5 x 21.0 x 23.0 cm.
       28-8-44, 45: linen: frags. mummy Lappings.
       28-8-46: bones of legs in wrappings.
```

APPENDIX B. p.87.

d under the granite coffin:29-10-1 to 4: alab.: 4 model basins as above under 28-8-1 to Found under the granite coffin:-11. (1) h., 4.0 cm. and diam., 6.5 cm.: (2) h., 5.5 cm. diam., 6.7 cm.:,(3) h., 3.8 cm. x diam., 5.9 cm. ned fraun (4) h., 5.0 cm. x diam., 6.4 cm.

> 28-8-5; white limestone: slab. 60 x 20cm. and 10+20 cm. thick inscribed on top with part of a compartment list nearly illegible: probably brought in thieves for some purpose.

Shaft G 7350 B: 2.0 x 2.0 m., ending at rock-surface: lined above with massive masonry, 5.37 m., courses: type 7 X without chamber, or burial.

Shaft filled with mixed disturbed debris and sand: in the numper part was dirty debris andxxandxxi which contained a Tew Ptolemaic objects:-

28-3-37 to 40: faience: frags. of cup, amulets and ring:

28-3-41: copper: part of model tool heavily oxidised.

Shaft G 7350 C: 1.95 x 2.0 m., -13.65 m. in rock: lined above with massive masonry, 4.3 EMX m., coursest with two chambers, I at 8.72 m. in rock and II at the bottom. Chamber I: type 6 b(1) on S: 2.62 x 1.4 m. and 1.02 m. high: area, 3.8 sq.m.: capacity, 3.87 cu.m.: open and empty. Chamber II: main chamber: type 4 b(1), unfinished, on S: 2.4 x 3.1 m. and 1.5 m. high: area, 10.54 sq.m.: capacity, 15.81 cu.m. Passage: 2.0 x 1.64 m. and 1.82 m. high: found open and

with no objects. Shaft filled with mixed disturbed debris containing Ptolemaic objects and frags .:-Ptolemain

28-3-71 to 78: faience: frags. of cup, and amulets: 28-3-79: lst.: $3.7 \times 2.3 \text{ mm}$: unidentified object. 28-3-80: RW: half of a ball bead: d., 1.9 x 1.3 cm. 28-3-81: coldred glass: inlay, part of hieroglyph ofxc crown of lower Egypt: red glass with green patina:

h., 1.2 cm.: length, 1.7 cm. 28-3-82: stone(serpentine)?: button from end of staff or fan: pierced vertically: h., 3.5 cm.: d.top, 3.8 cm.: d.bottom, 2.3 cm.: d.of hole about 1.5 cm. decorated outside with diagonal lines.

28-3-83: copper or bronze: head of a nail: diam., 0.9 cm 28-3-92: lst.: rough bater: frag.: Ptoleman 28-3-93: copper or bronze: part of a nail: h., 4.8 cm.

w., 0.5-0.6 cm.

28-3-94P diorite (gneis s): frag. with one worked

surface: 4.7 x 3.0 x 1.5 cm. 28-3-95: frit: frag. of New Year's bottle: inscribed, wp rnpt nfr n nb-s.

28-3-96: lst.: frag. of relief: shows above a register of offerings and below a few hieroglyphs.: $14.6 \times 10.4 \text{ cm}$.

L Prencess

G 7050: south of the small pyramid G I-c and south of the wide rubble wall built south of that pyramid: with G 7060 and G 7070 west of it: identified as the tomb of queen Nefertkauw "eldest daughter of Sneferuw" and produced; queen the prince is mother of Prince Neferma'at and grandmother of "Prince" Sneferw-khaf, whose tombs stand to the west.

See Figs..... Printed in Volume I. a.F.

See Pls.....

Mastaba: filled mastaba of type V with a wall of white limestone backed by nummulitic blocks: measurements of mastaba, 26.3 x 13.25 m., area, 348.47/sq.m.: prop.1/2.

max. height as preserved 3.2 m.

Chapel: interior chapel of type (3b) bonded with white retaining wall: with exterior chapel of white limestone:

- a) type (3b) with palace facade panelling on W wall,
 4.65 x 1.57 m. area, 7.3 sq.m.: Mixxxx prop.1/2.96:
 with wide shallow door in middle of wall: entered by doorway in N end of E wall, opening in embrasure in white wall: paved with slabs of white limestone.
- b) exterior room of white limestone built against the membrasure panels of the doorway to a: outside measurements, 4.15 x 5.95 m.: area, 24.69 sq.m.: the room inside measures, 2.0 x 4x8% 5.1 mm.: area, 10.2 sq.m. in the SE corner is an 10.2 statue-platform with slope at W end: the platform measures; in the SE corner is an 10.2 sq.m. in the statue-platform with slope at W end: the platform measures; in the sloping approach on the W measures 0.8 x 0.45 m.: probably used for a standing

measures 0.8 x 0.45 m.: probably used for a standing statue facing to W: room entered by doorway in E end of N wall: doorway to room a in middle of W Wwll: paved with lst.slabs.

Total area, a-b, 17.5 sq.m.

Subsidiary N niche: monolith torn out.

Decoration of chapel: Lea the W wall shows the bottom of the panelling:
all other walls were destroyed to below the decoration both in the
interior and the exterior chapel: in the exterior chapel a palt

platform for a standing statue facing to W: a few fragments of relief
were found in the debris in the street east of the mastaba which
may belong to the decoration:-

26-2-23: found in debris north of mastaba: w.lst. painted: frag. of wall relief showing a girl standing facing to left: bare head, tunic, dog-collar, bracelets: with right hand on breast and left hanging: broken off below leaving figure from about knees to top of head: h., 20.4 % 12.4 cm. wide: body painted Kalono yellow. Pl. 67. Drawn. Fig...

- 26-1-837: found in room a: w.lst.: small frag. in relief with name of Snfrw-hc-f (grandson of Queen Nefertkauw): 11 x 5.6 cm.:
- 26-1-838 to 843: small frags. of reliefs, incised inscriptions, and colored pattern from panelling: none legible.

 found in debris of room a. Drawn Fig.
- Shafts: one shaft close NW of interior chapel: lettered B but when the N end of the mastaba was examined no other shaft was found:
- Shaft G 7050 B: 2.05 x 2.1 m., -12.65 m. in rock: lined above with massive masonry, 1.5 m., two courses and part of a third (upper part of lining destroyed).

 Chamber: type 3 bm, on S: 4.85 x 3.7 m., and 2.15 m. high: area, 17.95/sq.m.: capacity, 38.59/cu.m.: with red guiding lines on walls and ceiling: one horizontal line runs all around the chamber at a height of 1.7 m. above the floor marked at intervals with a pendant triangle one of which had the ell sign beside it(figure not legible): on the E wall are four vertical lines,

Platerus L-Shaped,

APPENDIX B. p.89.

(1) at 1.3 m. from doorway, (2) at 0.95 from (1), (3) is 0.95 from (2), and (4) is 1.05 from (3) and 0.55 (one ell) from the S wall: the fourth vertical line is continued across the ceiling: on the S wall, at 0.45 shove the horizontal line is a second horizontal line (at the height of the ceiling): this wall is marked also with three vertical lines, (1) at 1.1 m. from E wall, (2) 0.95 from (1): (3) at 1.975 from (a) and 1.2 m. from W wall: other lines are oblitemated.

Passage 1.45 x 1.55 m. and 1.5 m. high: upper edge on shaft side trimmed with sloping edge to enlarge the opening for introduction of coffin: chamber probably reused in Saite-Ptolemaic Period: mo trace of blocking, coffin, or burial.

canopic recess: in W end of S wall: 0.8 x 0.7 m. and 0.7 m. high: rebate for covering slab on E edge: size indicates wooden canopic chest.

coffin: no trace found but probably had a coffin like those in G 7060 and G 7070.

Shaft filled with dirty debris (mixed with dirty sand and dust): this debris filled the chamber nearly completely:

and was dumped in after the Ptolemaic Period.

and was dumped in after the Ptolemaic Period.

In the filling of the shaft were found a few frags. of Okkupum statues and a number of faience objects of the Ptolemaic Period:

26-2-42 to 46: faience shawabtis and frags, some inscribed.

inscribed. 26-2-47: alab.: frag. from lap of 0.K. statue: 16.4 x8.6 26-2-48: alab.: neck of small jug with one handle: h.

h., 2.2 cm.: diam., 2.4 cm.: Ptolemaic.
26-2-49: lst.: lid of canopic jar with jackali-head
(Duwamutef): crudely cut and brukket: h., 7.8; cm.
diam., 9.2 cm.:

26-2-50: haematite(?): small weight circular, with flat base, and domed top: h., 1.6 cm.: d.max., 2.4 cm.: wight, 17 grm (± 2 kdt?).

26-2-77: faience: frag. of shawabti.

The eight nummulitic mastabas of type VI: second addition to Cem. G 7000.

The second addition to the record Cem. G 7000 consisted of eight nummulitic mastabas of type VI at. Four of these are attached to the massive mastabas G 7650 and G 7530+40, standing en echelon with those mastabas and with each other,. They are numbered G 7550, G 7660, C 7750 and G 7760 and are the tombs Ka. walr of relations of Hetep-heres II and Kawa-ab. Nearly contemporary with this group of four are two mastabas north of G 7510 and probably related to queen Meresankh theat are numbered G 7810 on W and G 7820 on E:. Probably later than these six mastabas are the two mastabas G 7060 and G 7070, which lie west of G 7050 the tomb of Queen Nefertkauw and constructed for her son and grandson.

G 7550: Lepsius 58 "Prince" Duwanehor, sons of Kawa ab and Hetep-heres II: in line 5 south of G 7530 40 (Hetep-heres II and Meresankh III).

Mycerin us on Shepaeskay

See Figs..... Printed in Volume I (Fig. 11) A. F.

See Pls.....

Name:

L founded of

Mastaba: filled mastaba of type VI a, with retaining wall of sloping blocks of nummulitic limestone, dressed to a smooth sloping surface: 37.0 x 18.0 m.: area, 666.0 vsq.m.: prop.1/2.0: reset/on rock surface which slopes down to south: the N end of the mastaba, fully preserved, has a height of 3-70 m.: the southern end was about 3.35 m. higher being on lower ground but the top had been denuded: enclosed on N and W by a lower rubble wall, about 0.7 m. thick and parallel to be bottom of dressed surface of mastaba at a distance 1.25 m.: the retaining wall is dressed only to the street level which is packed with 1st. debris: the enclosing wall on the N side abutted on the back of mastaba G 7660 and a rubble ramp descended herealong the back of G 7660 from the top of the enclosing wall to the lower level of the street in front of G 7550.

Chapel: interior chapel of type (3a) with remains of exterior c.b. chapel.

a) offering room of type (3a) of nummulitic masonry(very heaw with high courses: 4.7 x 1.6 m.: area, 7.52/sq.m.: prop.1/2.94: with plain compound ka-door near S end of W wall: outer recess, 1.15 x 0.3 m.: inner recess, 0.3 x 0.2 m., out in slab: entered by doorway in N end of E wall, opening in embrasure, 3.5 x 0.3 m.: approached by flight of steps flanked by upright slabs (6 rises and 5 steps), length (E-W), 2.25 m. with steps 0.9 m. wide: width of ramp, ca., 1.0 m.: height of floor of chapel above rock, 1.50. m.

Exterior c.b. chapel: almost totally destroyed by later burial shafts (mostly Ptolemaic): between the S end of G 7660 and the NW corner of G 7670 a heavy c.b. wall 1.65 m. thick which contains a doorway opening from the E: this is probably the main doorway to chapel G 7550: at two other places are remmants of thinner walls: E of the N side of the ramp to the doorway to room a, is a late L column basis (0.85 m. in diameter: this indicates a pillared hall with roof supported by a pillar or more probably by two or more pillars.

L limestone

Subsidiary N niche: monolith recessed in sloping wall: outer recess
1.0 x 0.3 m.: inner recess, 0.5 x 0.2 m.

Decoration of chapel, room a:-

The walls of the nummulitic room were decrated in relief of the old kind (not sized reliefs) but were badly weathered:

recorded by Lepsius, LG 59+ and re-examined by W.S.Smith: tops of walls broken and all walls badly weathered.

[in place of text in this line "LG 59"] "LD, II, Pl. 82"

Ka-door: in south end of W wall:

Architrave: badly eroded: only a few signs can be made out undoubtedly an offering formula.

Tablet: prince seated facing to right in traditional attitude

at table of bread: panther skin(?) garment: under table on left, ideographic list (two lood-signs legible): above table a horizontal line of offerings (short last") and beside table on right two more horizontal lines continuing same short list(l)(arm and water), bdyt, h; tyt idmyt (second quality), sntr w.....:(2) and (3) too obliterated to read: in third line beside table, iht nb and rn with bull's head (part of ideographic list): across the top of the tablet a horizontal line with titles and name, signs facing to right, s; nswt n ht-f mry-f smr n it-f nb im;h hr it-f Dw;-n-Hr. Rest of ka-door weathered but on the back of the outer recess

APPENDIX B. p.91.

- W Wall: south of ka-door: badly obliterated, at least four regime pegisters: above, on left, two standing figures face to left (see table scene on S wall): the second man carries a goose in his arms: in the lowest register on left, is a man facing to right, holding a standar(?) and in the middle of the register a man squatting facing to left.
- N Wall: only the subregister is partly legible: three figures facing to left (probably bringing in funerary meal).
- √S Wall: table scene: man seated facing in to right at table of bread: above head two obliterated vertical lines of titles: on the right of the table, below, three squatting men, (a) faces to right: (b) faces to left and (c) faces to right: see scene on W wall south of ka-door.
- E Wall:/south end of wall a large standing figure facing to left: in short wig: at the N end of the wall, in the lowest register, rams driven by men facing to right. (See Ve...)
- N Door-jamb: destroyed.
- S Door-jamb: man and wife seated on one chair at table of bread, facing out to left: behind wife traces of illegible inscription
- N Facade Panel: only legs of figures of man and wife, standing, facing to left.
- S Facade Panel: large figure of man, standing facing in to right: short wig, chin beard, and short(?) skirt: in front of face remains of vertical inscription, wrn with; behind him stands his wife with her left arm around his back and her left hand on his right shoulder: her right laid on his right arm: behind her stands a small girl named Nbty-htp: in front of man, two naked boys holding hands with free hands hanging.

Shafts of G 7550: two shafts, A on N and B, chief shaft on S.

Shaft G 7550 A: wife's shaft: 2.15 x 2.15 m., -12.55 m. in rock: lined above with massive masonry, 3.25 m., 3 courses(top destroyed). Chamber: type 6 b(2) unfinished: on S: 3.4 x 1.15 m.:

unfinished chamber partly 1.4 m. and partly 1.75 m.high: with cutting begun in the south wall: area, 3.91 sq.m.: capacity about 5.13 cu.m.

Probably intended to be a large of type 3 or 4: no trace of blocking, coffin or burial.

Shaft filled with disturbed debris contain number of Ptolemaic objects: excavated in recent times.

28-5-108: RW: jug: h., 10.1 cm.: d., 7.9 cm.: Roman.
28-5-109: faience: uzat-eye.
28-5-107: lst.: piece of sawed stone: 19 x 9.7 cm.:th.2.7-5.5

1 my widit?

APPENDIX B. p.92.

Shaft G 7550 B: man's shaft: 2.08 x 2.0 m., -13.94 m. in rock: lined

```
with massive masonry, 4.2 m., 5 courses.

Chamber: tye 3 amx: on S: 4.75 x 5.1 m., and h., 3.75 m.:

area, 24.22 sq.m.: capacity, 80.82 cu.m..

Passage: 1.87 x 1.45 m. and 2.15 m. high: with rather
                     irregular floor sloping downwards to chamber: be
             Blocking: of type II &(1) of which two courses remain in
                     place set in plaster.
              Turning recess in N side of shaft at bottom beginning at NW
                    corner: 1.42 x 1.05 m. the part ofening on shaft is 1.85 m. high for a depth of 0.55 m.: the back part of the shaft 1.0 m. high: with horizontal roof: the bottom
                     of the shaft slopes down to the passage on the south.
              Low stone bench along the E wall of chamber.
              Canopic pit in SE corner excavated in bench: 0.55 \times 0.5 \text{ m}.
              and 0.6 m. deep: rebate for slab lid on all four sides. Coffin: No trace of coffin or burial: but a number of O'Kingow
                     objects found in debris.
              The shaft was filled with disturbed debris in which was found a few frags. of Ptolemaic faience; this debris was
                    mixed with drift sand and had run into the chamber but
                     the chamber had not been cleared out in modern times.
Objects found in chamber:
      28-5-164: frag. of RW pottery coffin of the Roman Period.
      28-5-165: faience: frag. with ram in relief.
    28-5-166: green glass: frag. of bottle, part of neck.
28-5-167 to 176: faience: amulets, frag. of cup, and two frags.
              of shawabtis.

√ 28-5-199: alab.: small flat bottomed bowl with straight sides

             spreading upwards to mouth: h., 2.5 mm.: diam. max. 14.0 cm.
      diam. base, 5.0 cm.: half preserved.

28-5-179: alab.: 9 model bowls: round bottomed h., (1) h., 1.9 cm. x 6.7 cm.: (2) h., 1.8 x 6.5 cm.: (3) h., 2.0 x 6.2 cm.:
             (4) h., 1.8 \times 5.5 cm.; (5) 1.4 \times 5.2 cm.; (6) h., 1.5 \times 5.6 cm (7) h., 1.2 \times 5.2 cm.; (8) h., 2.2 \times 6.3 cm.; (9) h., 1.2 \times 5.5 also 6 frags. of similar dishes.
   √ 28-5-180: alab.: model basin h., 2.0 cm.: d.top, 5.0 cm.: diam. base, 1.8 cm.: damaged.
   / 28-5-181: alab.: three model cylindrical jars of type I d:
             (1) h., 5.4: d.top, 2.5: d.min., 1.9: d.base, 2.5 cm.
             (2) h., 5.0 : d.rim, 2.5:: d.min., 1.8 : d.basem 2.4 cm. (3) h., 5.2 : d.rim, 2.8 : d.min., 1.8 : d.base, 2.2 cm.
      28-5-182: alab. model: long necked jar as used in magical set:
             h., 5.6 cm.: d.top, 3.5 cm.: d.neck, 1.9 cm.: diam. body, 3.7 cm.: d.base, 1.5 cm.: narrow boring. Type appear S-XV &
      28-5-183: alab. model like 182 from magical set: with top broken
             off: h., 5.2 cm.: diam. body, 3.5 cm.: d.base, 1.0 cm.
      28-5-184: alab.: model pešeškaf wand from magical set; h., 8.4 cm.
             w.top, end, 3.8 cm.: w.middle, 1.7 cm.: th., 0.8-1.0 cm.
      28-5-185: alab.: model basin from magical set: h., 2.4 cm.: d.top,
             2.8 cm.: d.base, 1.4 cm.: dummy.
      28-5-186: alab.: flat topped circular table; broken and incomplete: stem missing, apparently of separate piece: d., 39.8 cm.:
             d.flat surface which rested on stem, 10.8 cm.
      28x5x187xxx1abxxxx1atxxtoppedxcircularxxbtdlexxbrokexxxndxincomplete
             atenxniasingxxapparentlyxofxsepx ratexpicexxdx
      28-5-187: alab.: two frags. probably from model vessels.
 28-5-188: plaster: frobably from tray containing granaries or similar, with print of bottom of a jar: h., 5.5 cm.: d., 6.5
             cm.: depth of cavity, 2.5 cm.
```

28-5-189: RW potsherdsL one basket nearly full.

APPENDIX B. p.93.

fragment listed but not drawn in Vol. II

 $^{\prime}$ 28-5-190: special ware: two handled oil-jar: type B-LIV: frags. of upper part: h. neck, 5.7 cm.: d.rim, 7.8 cm.: upper part of body, d., 20 cm.: with h. 9.3 cm. also two handles preserved.

The objects include some amulets and frags. of the Ptolemaic Period but the following are undoubtedly of Dyn. IV, 28-5-178 to 187 and 190, including alab. models, alab. table and two handled oil-jar. Probably most of the potsherds in 28-5-189 are of the same period.

Later Constructions:

Along the E face of the mastaba were threein intrusive shafts apparently of the ext. Old Nongdom.

Shaft G 7550 X: north of chapel: 1.76 x 1.62 m., -3.4 m. in rock:

lined with (0.45 m., denuded. chamber: type 3 a(2) on W: 2.15 x 1.4 m.: and 1.4 m. high: area, 5.01/sq.m.: capacity, 4.21/cu.m.:/blocked parts. with rubble, type V d(3): found empty.

L remains of rubble blocking of

Shaft G 7550 Y: north of X: 1.46 x 1.4 m., -1.6 m. in rock: level

214 above 0.9 m., denuded. Chamber. type 6 a(2): on W: 1.42 x 0.8 m. and 0.94 m. high: area, 1.13 sq.m.: ca acity, 1.06/cu.m.: blocked with rough small stones, type V c(3): resting on depression in W side of shafts, 0.76 m. deep, and taking half width of shaft: found open and empty.

Shaft G 7550 Z: north of Y: 1.2 x 1.3 m., -7.1 m. in rock with lining if any destroyed: no chamber: type 7 x: no evidence of burial.

LG

For the Ptolemaic structures and shafts, see under G 7450 in xx street on E and 7540 in street on S.

In the ruins of the exterior chapel were found two Ptolemaic baria; burials Pt.LXXII-LXXIV.

On the south of mastaba the area was filled with secondary mastabas and Ptolemaic Parison burials.

Ka - wab

G 7660: "Prince"Ka-em-sekhem, son of Kawa'ab and Hetep-heres II: in line 6 south of the Merytyetes mastaba, G 7650: E of G 7550 and en echelon with it.

See Figs......Plan & Section done a. F.

See Pls.....

Name: Ka-m-sekhem,

measurement of the mostobia: 37.5 x 17.5 m.

Note 2 Mastaba: filaed mastaba of type VI a, with retaining wall of sloping x blocks of num. lst., dressed to a smooth sloping surface down to ground level: 36.5 x 18.5 m.: area, 538.0 sq.m.; prop.1/2.0 ...: height .5.20 m.

prop. 1/2.14

area, 656.2559.m. Chapel: interior chapel of type (3a) of nummulitic limestone bonded with retaining wall and exterior c.b. chapel: with subsidiary N niche:

a) interior offering room of num. 1st., type (3a) with plain compound ka-door near S end of W wall: decorated with carved reliefs (not sized technique): 4.2 x 1.47 m.: area, 6.17. sq.m.: prop.1/2.85: entered by doorway in N end of E wall: openig in embrasure in face of mastaba.

27-7-40.

APPENDIX B. p.94.

- Exterior c.b. chapel, nearly destroyed, with four rooms, b-e: covering an area of 15.37 x 10.2 m. with very heavy exterior walls, 2.6 m. thick on S, 2.25 m. on E and 2.85 m. thick on N:
- b) large pillared hall around the embrasure to room a: 5.75 x 7.95 m.: area, 46.71 sq.m.: floor paved with stone slabs but most of pavement torn up: roof supported by 6 pillars, in two E-W rows of 3 each: pillar, @xxxx 0.45 x 0.45 m., square: the inside xxx of the N wall on the room side, was decorated with palace facade paratiting panelling, with a great door in the middle of three plain compound niches on each side of it: the E and S walls may possibly have borne a similar panelling but no trace was preserved: the hall was probably entered by a doorway in the middle of the E wall but the wallx is denuded and broken by shaft G 7660 Y: in the E end of the S wall is a doorway leading to room e, the floor of which was on a lower level and this doorway was approached by a flight of three steps (4 rises): south of hall bewere three subsidiary rooms e, d, c, from E to W entered successively from one to the other; drainaby culvert under entrance on E leading to circular stone basin (diam.1.0 m.) sunk in floor 1.0 m. east of chapel.
- c) western room south of hall b: 2.8 x 1.8 m. area, 5.04 sq.m entered from d by doorway in N end of W wall with stone sill:
- d) east of c: 2.8 x 3.1 m.: area, 8.68 sq.m.: entered from room e by doorway in N end of E wall: doorway to c, opposite in N end of W wall.
- e) eastern room south of b and giving access from b to d, c: 2.85 x 1.15 m.: area, 3.27 sq.m.: entered from b by doorway in N wall which was approached by three steps (4 rises) descending from floor of b to floor of e.

Total floor area, b-e, 63.7 sq.m.
Total floor area, a-e, 69.87 sq.m.
Exterior chapel badly denuded and debris of decay together with surface debris penetrated by a number of Ptolemaic burials.

Subsidiary N niche, monolithic stela recessed in sloping wall: outer niche, 1.1 x 0.35 m.: inner niche, 0.35 x 0.3 m. not inscribed or decorated.

Decoration of Interior offering room a: nummulitic limestone: with carved reliefs (not sized).

LG 59:

Ka-door near S end of W wall:

Architrave, destroyed.

Tablet, destroyed with frag. left showing man's knee seated at table of bread facing to right: under table on left remains of ideographic list (twice a 1000-sign) and two heads of birds.

heads of birds.

Crossbar: dihnty hb nb s; nswt......

surfaces of inner niche obliterated.

Backs of outer niche: nearly destroyed but probably with standing figure facing in on each side: on the S above titles of man: r

Sides of outer recess: S side obliterated: but with traces of two figures facing in: on N side, remains of four registers each with one standing man facing in to deft:
(1) feet only visible: (2) holds up a platter with three hnm-jars; (3) seems to hold a pleated strip of linen:
(4) head and shoulders of woman, bare head, tunic.

```
W Wall, south of ka-door: badly obliterated: at least five rapinta;
           registers:
          1) Nearly obliterated: at right end there is a kneeling figure facing to right, second figure standing and the
                  third kneeling, all facing to right.
          2) figures/obliterated but an inscription reading in hm-k;.
          3) obliterated.
           4) slaughter scene.
          5) oblite rated.
  W Wall, north of ka-door: (LD II Pl.32): presentation scene:
At N end of wall, man and wife standing facing in to left:
man with staff and wand, full wig, broad necklace, short
skirt and panther-skin over it: wife wears lappet wig
                  dog collar and tunic, with right arm around shoulders
                  of man (hand on his right shoulder): her left hand rests
                  on his left arm: over their heads are ends of 7 vertical
                  lines,
                  (1) \dots \underline{\text{smr wcty n it-}f}:
                  (2) ..... <u>n lt-f hrp chE</u>
(3) .... <u>f nb</u>:
                  (6) .....(<u>K;-m</u>)<u>śhm:</u>
(7) (hmt-f mryt-f) <u>K;-cpr(?)</u>.
In front of man a small boy (nearly obliterated) holds
                  the staff with his right hand: labelled s;-f n ht-f
          Mnw-hc-f. (motion Separate plate)-
On the left of the chief scene five registers of small figure:
                  proceed to right:
                  <del>(X)</del>
                  1) figures preserved from knees down:
                          (a) standing with scribes case on ground in front of him: the other five figures are estates
                                 alternately male and female: names almost
                                 completely obliterated: the last figure (f)
                                 carries a milk-jar:
                          (b) ...........<u>mr ntrw(?) (niwt-det.):</u>
                          (c) .....t land-sign and niwt-det. : (d) .....k!(?) niwt-sign:
(e) .....niwt-sign.
                          (f) ..... and niwt-sign.
                  2) (a) standing scribe, with upper part obliterated:
                              in front of him on ground a scribe's case:
                       labelled \underline{s}:-...\underline{n} ....\underline{N}-\underline{k};-\underline{H};\underline{p}. (b-f) five estates alternately male and female:
                              (a) with basket on head and bird in right hand,
                              h-t Hwfw-nfr:

(c) woman, carries basket on head and roll(?)

in right, Hwfw-shtp:

(d) man, basket, and in right hand a bird,
hand
                                      Hwfw-n-sky:
                              (e) woman, basket, and in right hand a kindy lotus, Hwfw-imnwt:

(f) man, basket and bird in right, Hwfw-sw(t) all figures support basket with left hand.
                  3) badly obliterated: again six figures of which
(a) appears to be a scribe: the other five are
                                     estates, alternately female and male:
                              (b) woman, with basket on head, .....nm:
                              (c) man, basket and <u>niwt-sign</u> preserved: (f) woman, basket preserved.
                  4) badly obliterated: men bringing animals: an ibex is visible: over it rn (n)i; led by two men, one before it and one behind: the second man is
                              followed by three others but the animals are
                              obliterated. (not in Sepain paste)
                  5) badly obliterated: appearently men bring imals: on
                              the left end, upper part of man: across the top a horizontal lines, ..... rn iw; iry.
```

(mot in depoin plate)

APPENDIX B. p.96.

- North Wall: (LD II, Pl.32): at the top a boating scene extending the length of the wall: below these are three narrow registers leaving blank the part of the wall covered by the wooden door when it stood open: mixed scene without chief figure:
 - 1) large boat being paddled to right: upper part obliterated in middle of boat, a large figure standing: only feet and ankles remain: probably Ka-m-sekhem: facing to right in front of him only one paddle is preserved: behind him, three men paddling: then a man leaning forward without padde: A finally two steersman with steering oars.
 - 2) four women, bare head, wearing tunics, carrying personal equipment, facing to right:

(a) holding up a box and a long harrow case.

- (b) bag in left hand and jar on right shoulder.
- (c) strip of linen in left hand and jar on right shoulder (d) carries a sort of bag or bucket with loop handle
- and her right hand is obliterated.
- 3) two men cutting up a bull.
- 4) two men cutting up a bull (not in Lepsius plate(see Photo))

South Wall: destroyed.

- E Wall: at S end, large figure of man leaning on a staff, facing to left: at the N end of the wall, remains of three registers
 - 1) three standing men facing to right (not estates).
 - 2) animal facing to right.
 3) animal facing right.

Apparently a presentation scene.

- N Door-jamb: man and wife seated on one chair at table of bread: facing out to right: details obliterated.
- S Door-jamb: man and wife seated on one chair: facing out to left: rest obliterated: perhaps at table of bread.
- Facade-panels: in embrasure N and S of doorway, man and wife standing facing in (to left on N and to right on S): man with staff and wand: on the N over the wand is written Rc-wr, probably name of son standing below but now obliterated

Subsidiary N niche: not inscribed or decorated.

- Shafts In G 7660: two shafts in medial axis: A on N and B, chief shaft on S.
- Shaft G 7660 A: wife's shaft: 2.1 x 2.25 m., -12.1 m. in rock: lined

above with massive masonry, 4.75 m., ... courses: excavated by "Service" and found empty to a depth of 11 m. Chamber: type 3 cl: on S: 5.15 x 5.3 m., and 3.88 m. high:

area, 27.28 sq.m.: capacity, 105.85 cu.m.;

Passage: 2.25 x 1.0 m., and 1.02 m. high: no trace of blockin No canopic pit or recess.

No trace of coffin, burial or equipment:

- The shaft was found empty to a depth of 11 m. from the top: it had been excavated recently mand lower part of shaft and chamber contained disturbed dumped debris: in the chamber was found a frag. of inscribed stone: 29-4-322: num. lst.: h., 22.0 cm.: w., 10.5 cm.: th.
 - 10.1 cm.: incised vertical inscription, rh nswt ss pr md;t Rc-..y: with vertical, incised line of left.
- Shaft G 7660 B: chief shaft: burial place of "prince" Ka-em-sekhem: 2.0 x 2.1 m., -11.15 m. in rock: lined above with massive masonry, 1.5 m., 2 courses with much of upper part destroyed excavated by "Service" a refilled probably from debris of shaft A

Chamber: two chamber on S, the second opening from the first.

APPENDIX B. p.97.

Chamber I: type 3 afx: on S: 5.0 x 5.3 m., and 2.75 m. high: area, 26.5/sq.m.: capacity, 72.87/cu.m.

Passage: 2.2 x 1.9 m. and 1.65 m. high: with floor and roof

sloping slightly downwards to S:
Blocking: nox trace of blocking remains (probably of type
II b(1): in the S end of W wall opens a short passage leading to chamber II.

Chamber II: coffin chamber: on W of room III 2.2 x 2.6 m. and 1.5 m. high: area, 5.72/sq.m.: capacity, 8.58/cu.m.:

Passage: 1.3 x 1.6 m. and 1.2 m. high: contained granite coffin of Ka-m-sekhem, removed by the Service and now in Cairo Museum: type d, inscribed, ... x ... m. andm. high: (... m. with lid) inscribed with titles and name: coffin probably stood E-W along the N wall: high up in the W wall is a recessed edge but this is only 1.2 m. wide (N-S).

Canopic pit in SE corner in front of doorway: 0.63 x 0.63 m. and 0.5 m. deep: no rebate.

Both chambers not completely finished and therefore a little irregular in outline.

Total area, of rooms I and II, 32.22/sq.m. Total capacity of rooms I and II, 81.45 vcu.m.

Shaft found by us filled with disturbedx debris: recently excavated and refilled: in the top debris were found only a small frag. of Ptolemaic faience probably from the surface debris around the shaft.

Later Constructions:

On the N between the G 7650 and G 7660 is a small mastaba, G 7652, built against the S end of G 7650.

Around the NE corner of G 7560 is another small mastaba, G 7661. This reaches to the N side of the Subsidiary N niche of 7660. In the street E of G 7660 are the remains of two other mastabas, G 7662 and G 7663.

@ Note There is no such a 16 shaft as G. 7660 Z Rus there y G. 7660'X at SE corner of the shopel which

1 Dreised only south part of

In Ptolemaic times: a number of supperstructures were built on debris and a large number of burial chambers constructed in the debris: several of the Ptolemaic shafts penetrated all the layers of debris and descended into the rock: see in particular the shafts 7660 Y, Z and G 7661 A, of which G 7660 Y and G 7661 A have many chambers and burials.

The Ptolemaic burials continue in the space between G 7660 and 7670

corner of the ahopee which , should Z in numbered as G. 7662 Z. (See page 287) , not menthoned in this text. Should Z in numbered as G. 7662 Z. (See page 287)

G 7750: name not recovered: first mastaba in line 7, at N end of line: south of G 7510 with the E face aligned with the E face of that mastaba: E of G 7650 with its N end aligned with the N end of that mastaba but being smaller G 7750 stands en echelon with G 7650 leaving the chapel of that mastaba exposed to the east.

See Figs...... Plan a Section done a. F.

See Pls.....

Name: not recovered.

othere walls not dressed. a.F. wastaba: filled mastaba of type VI a with retaining wall of sloping blocks of mum_lst_, dressed to a smooth sloping surface 37.0 36.2 x 18.5 m.: [a.ca, 25./5q.m. prop.1/2.0: height, 5..6..m. with interior chapel and subsidiary N niche matter mich. Larea, 684. 50 sq. m.

> Chapel: interior offering room of type (3a) of nummulitic limestone bonded with retaining wall and an exterior c.b. chapel: with subsidiary *(nichemoteus)

a) interior offering room of num. livestype (3a) BRXNUMXX Istxxbondedxwithxretsiningxwallxandxanxexteriorxxxxx chapalxxwithxsibsidiaryxxxxmichex with plain compound ka-door, near S end of W wall: decorated with carved reliefs (not sized technique): 4.4 x 1.56 m.: area, 6.86 sq.m.: prop.1/2.82: with plain compound niche of which the outer niche measures, 1.02 x 0.37 m. and the inner 0.33 x 0.39 m.: entered by doorway in N end of E wall, opening in embrasure in E face of mastaba. room paved with stone slabs, partly torn up at S end. Exterior c.b. chapel of which one room and remains of another

are preserved:

- b) a hall with roof supported by one column: 4.75(?) x 3.85 m area, ca. 18.28 sq.m.: built around the embrasure of the doorway to room a: with one stone basis for a column in center of hall: diam. of basis, 0.82 m.: no trace of entrance doorway, probably on E: doorway to room a in middle of W wall, formed by the mastaba: doorway to room c toward the W end of S wall.
- c) E-W room, perhaps magazine, south of b: 1.87 x 3.85 m.: area, 7.19 sq.m.
- No trace of other rooms and chapel was probably complete with two room.
- Thickness of c.b. walls: S wall of room cm, 1.15 m.: E wall of room c and probably also b, 1.4 m.: wall separating b and c, 0.825: N wall of room b, 0.75 m.

Decoration of room a of chapel G 7750:

Decoration never completed: only the ka door and the door-jambs present evidence of decoration, and the cutting of the mak reliefs on the S doorjamb was not finished.
Ka-door: 2.62 m. high: on the backs of the outer niche, on each

side is a standing figure of a man facing in: with full wig and short skirt: with far hand on breast and near hand hanging open at side: the inner niche and the sides of the outer niche appear never to have been inscribed: tablet and crossbar, obliterated: architrave, missing.

No Door-jamb: man and wife standing facing out to right, with heads and shoulders destroyed: man wears short skirt, with hands hanging at his sides: wife, behind man, in tunic: with position of left hand obliterated (probably on deft shoulder of man) and with right hand laid on man's right forearm: on right, in front of chief figures two registers of small figures facing in to left:

1) man standing wearing short skirt and panther skin: with right hand on breast and left hanging holding shm-wand probably a son.

2) two standing men: the second figure wears a collar and holds a roll of papyrus in hanging right hand: traces of inscription in front of each, nwt r probably both labelled rh nswt and representating sons: large figures in one plane not finished: small figures

im modelled relief.

S Door-jamb: reliefs finished but upper part of seene is detroyed by weathering: large figure standing facing out to left:

Wears short skirt and panther skin with staff in far hand and shm-wand in near hand: in front of man a boy standing facing the man, wears side-lock and short skirt: with left on his own right shoulder and a roll in his hanging right hand: a vertical inscription with signs facing to right begins above the man's right arm, s;-f n ht-f and continues below over the shm wand, ss c nswt and in front of boy, rh nswt Hnw-k; behind the large figure stands a second small figure, wearing short wig and short skirt: facing to left with staff in left hand and wand in right: over his head is the lower part of three vertical lines of signs facing to right with a horizontal containing the name below the three vertical lines:

(1) r n-f prt-r-hrw rh nswt: (2) hbhb rc nb:

(3) nb bnrt (and 4 bowls on stands): (4) horizontally

 K_j -mnh.

APPENDIX B. p.99.

Shafts in G 7750: two shafts in medial axis: A, wife's shaft on N and B, man's shaft on S.

Shaft G 7750 A: wife's shaft: 1.98 x 2.0 m.:-12.55 m. in rock: lined area, 6.5 sq.m.: capacity, 19.82 cu.m.: floor of chamber

slopes up to south.

Passage:

Presspar/ 2.33 x 0.94 m.: and 1.2-1.0 m. high: Plocking: no trace of blocking which was probably of type II b(1). No trace of coffin or burial.

The shaft and part of the chamber was filled with mixed debris: the tomb had been cleared in modern times and refilled: no objects were found except a few of the Ptolemaic Period found in the top of the shaft (29-3-277 to 282).

Shaft 6 7750 B: man's shaft: 2.25 x 2.15 m. at top contracting to, 1.65 x 1.7 m., -16.48 m. in rock: lined above with massive masonry, 5.47 m.: two chambers in shaft, I unfinished at -11.18 m. in rock and II at bottom of shaft. Chamber I: at 11.18 m. in rock: unfinished cutting on S E

clearly intended to be of type 3: a passage had been cut, 1.85 x 1.05 m. and 0.9 m. high: at the S end a hole had been cut upwards to a height of 2.9 m. (irregular): being about 1.0 x 1.0 m. in horizontal section: from this hole a chamber was being cut laterally to the south and west: the work shows the method used in the excavation of chambers in order to permit the greater part of the cutting to be made with downward strokes of the tools used: two lateral layers are visible each about 1.0 m. high: the layer in the middle of the chamber had been cut first.

Chamber II: actual burial chamber: type 3 am: on south at bottom of shaftL 2.45 x 2.8 m. and 1.8 m. high: area, 6.86/sq.m.: capcity, 12.35 cu.m.: in the S wall was an unfinished cutting high up in the wall (1.0 m. above floor of chamber) level with roof 2.4 m. wide (E-W) and 0.75 m. deep: (0.86 m. high): at the back of this cutting an upwards hole had been cut to a height of 0.55 m. above the roof of the chamber: this is the same method as was being used in the unfinished chamber I? as was being used in the unlinished chamber is apparently the intention was to enlarge and heighten the chamber: this unfinished cutting had been walled off from the chamber by a masonry wall, part of which was found in place.

Passage: 2.4 x 1.1 m. and 1.1-0.95 m. no trace of blocking. No coffin or trace of burial.

Shaft was filled with disturbed debris and the chamber had a heap of the same debris around the entrance: no objects were found except two Ptolemaic frags. in upper debris of shaft (29-3-402, 403): the shaft had undoubtedly been excavated in recent times, probably by the Service.

Later Constructions:

East of the mastaba, north of the chapek began the field of small and medium mastabas which extended to the cliff containing rock cut tombs above the village: this same field of mastabas extended northwards and southwards; southwards, the mastacas stood east and south of the chapel of G 7750 and continued along the E face of G 7760: over the debris of this cemetery were built a series of chapels of the Saite-Ptolemaic Roman periods and a large number of intrusive and shafts and burials of the same period penetrated the older and later layers of debris: the mastabas near the faces of G.7750 were numbered G 7751 to G 7755.

as G. 7753 x, G. 7753 W The Ptolemaic shafts, G 7750 X, W, Z, were intruded through the N wall of the exterior c.b. chapel of G 7750.

Lold Kingdom

These shuffs G. 7750 X, W, 2 numbered

and G. 7753 Z on page 337

19-8-41 OF

APPENDIX B. p.100.

G 7760: "Prince" Mindedef and his wife: second mastaba in line 7, south of of G 7750: east of G 7660 and en echelon with G 7660: probably built before G 7750 and possibly before G 7550.

See Pigs. Plan & Section done Q.F.

See Pls.....

Owner: Mindedef,

Mastaba: filled mastaba of type VI a, with relatining retaining wall of sloping blocks of num. 1st. dressed to a smooth sloping surface: 1820 - 1800 m.: area, 697.36/sq.m.: surface: [52.0 x 18.0 m.; area, 936/sq.m.: prop.1/2.9] 8.05. m. prop. 1/1.94V with interior chapel and subsidiary iniche monther.

11-3-40

Q.F.

Chapel: interior chapel of type (3a) of nummulitic limestone: bonded with retaining wall and an exterior c.b. chapel: with subsidiary N niche.

a) interior offering room of type (3a) with plain compound ka-door near S end of W wall: decorated with carved reliefs (not sized technique): 4.52 x 1.53 m.: area, 6.91/sq.m.: prop.1/2.95: /plain compound niche of which the outer niche measures, 1.14. x 9.33 m. and the inner, 9.34 x 9.32 m.: entered by doorway in N end of E wall opening in embrasure in face of mastaba: room paved with stone slabs: with floor 1.33 m. above rock: approached by ramp by six narrow steps (7 rises) flanked on each side by vertical slabs: ramp, 1.7 m. long (E-W) and 1.15 m. wide (N-S): the steps are 19-3 m. wide (N-S) height of ramp, m.: ascends from floor of room b to floor of room a.

mammalitic linestone

LH 0.93

- Exterior c.b. chapel badl y destroyed by intrusive structures and shafts: consisted certainly of a pillared hall ((cf. 7660) and other rooms the mutsid outline of which are confused by later c.b. structures.
- b) pillared hall around the doorway embrasure to room a: estimated at about 8.8 x 5.25 m.: area, ca. 46.2/sq.m. with stone pavedfloor: roof supported by square pillars (evidence of one south of ramp to a): to be reconstructed with at least four pillars in two N-S rows of two pillars each: apparently entered by doorway in E wall opposite doorway to room a: probably other doorways N and S leading to subsidiary rooms.
- Subsidiary rooms north of room b: the remains of heavy c.b. extended along the east face of the mastaba to near the NE corner: although overbuilt and penetrated by later structures, it is obvious that the exterior c.b. chapel covered practically the whole E face of the mastaba: in and over these rooms to the north was built the mastaba G 7766:

inscribed or decorated.

Decoration of room a of chapel G 7760:
"Prince" Mindedef: see LG 60. LDII, pl. 33

Ka-door:

Architrave: found displaced on floor of chapel: with frags of wall above and to left adhering to it: On the left end of the architrave, seated man holding staff in left hand and handkerchief in right, facing to right: long full wig, broad necklace, short skirt, and hry hb sash: in front of him inscriptions written in short vertical columns (not separated by lines), signs right:

APPENDIX B. p.101.

.... htphnty sh ntrkrś...... smyt imnt.t nfr nb im;h (hr) ntr c; pr n-f....

wp rnpt Dhwty (tp rnpt) w;ghb......

prt Mnw s; monthly and half monthly feasts m hb nb rc nb

iry pety (dist) bity hity-c iry Nhn s; nswt n ht-f

spct Mnw-dd-f.

Tablet: destroyed.

Crossbar: badly weathered but recorded by Lepsius, words written vertically to form horizontal line of signs facing right, s; nswt n ht-f (mr)y-f...n it-f(hry) sst; nb nt nswt iswt-f nb Mnw-dd-f.

Drum: s; nswt n ht-f Mnw-dd-f.

Back of inner niche and the two back panels of the outer niche decorated with palace facade: on inner niche, four doors and five panels with four rectangular bands above: on the backs of the outer niche, three and four panels respectively with paired papyrus flowers above niches. Sides of inner niche, not decorated.

Sides of outer niche: on each registers of estates facing in: N side: three and perhaps four registers, each with one estate facing in:

(1) at top as preserved, woman, labelled Hwfw-w;-

(2) woman with basket on head and object in left hand obliterated, Ht-(K;?) (det. two n signs):
(3) nearly obliterated but two large bird-heads with two looo-signs beneath.

S side: same number of registers with estates facing in to right:

(1) woman with basket on head steadied by left hand:

milk jar in right, Hwfw-mn-(?)-htpwt:
(2) man with basket on head, Hwfw
(3) figure obliterated (wmman?),iwt.

W Wall, south of ka-door: from the upper part of the wall(attached to architravem small male figure bending over to the left: on the wall below are at least three registers each with three estates facing in to right:

1) only feet of three registers figures, man, woman, man: in front of the first is visible a niwt-sign.

2) three estates facing to right, man, woman, man: Andreadentax all with baskets on head and right hand obliterated:

labelled (a)(cartouche)-c;-df;:
(b)woman,sh(t):
(c) man, men, (Hw) F(B) (cartouche)-df;(?).

W Wall: over ka-door: attached to the architrave is a fragment of the wall above which shows part of a picture list of offerings horizontal row of round cakes, bread in pans, etc.

W Wall, north of ka-door: on the right (N) end of the wall stands Mindedef with his wife behind him: man wears full wig, panther skin and short skirt: holds staff and wand: wife has hermen right arm linked around his right to upper arm and have left hand on his left forearm: between man and staff, a small naked boy grasping the staff with his right hand, s !- f Rc-...: in front to the S are the remains of four regs/iters (originally five) of small figures facing to right: 1) obliterated except for the legs of the first man

(probably a scribem).

2) five men bringing birds and animals to right:(a) holding two birds in left hand and one in right hand grasping them by their necks.

(b) carrying goose in arms:(c) carrying crane in his arms:

(d-e) apparently carrying small animals in their arms.

I my notes have

APPENDIX B. p.102.

- 3) continuation of reg.2:
 - (a) holds up goose in left hand and carries another in right hand hanging at kis side:
 - (b) holds up a haunch of beef: (d-d) two mon cutting up a bull.
- 4) men bringing in animals to right:
 - (a) pulling and (b) pushing an oryx: (c) leads in an animal (d) following animal.
- N and S Walls: obliterated completely or not decorated:
- E Wall: only south end of wall preserved showing parts of three registers: the chief figure or figures must have been at the N end of the wall facing in to right (cf. seated figure in G 7140):
 - 1) obliterated except for base line.
 - 2) from left to right, edge of skirt held by man facing to left: two men bearing a second garment, facing to left (see again E wall of G 7140): above garment is written horizontally.....m;st.
 - 3) four rectangular tables with jars set in holes in tops.
- N door-jamb: Mindedef and wife seated on one chair facing out to right: man holds staff in left hand: other details, whiterate obliterated: over wife's head is written rht nswt Hwfw-cnh.
- S Doorjamb: destroyed.
- Shafts in G 7760: two shafts in medial axis: A, wife's shaft on N and B, man's shaft on S. [10.95 crossed out] 6.40 m.
- Shaft G 7760 A: wife's shaft: Vexcavated December 1929.
 - $2.1 \times 2.06 \text{ m., -10.95 m.}$ in rock: lined above with massive masonry, 4.65 m., 5 courses.
 - Chamber: type 3 bfx: on S: 3.3 x 2.65 m. and 1.75 m. high:
 area, 8.75 sq.m. capacity, 15.31 cu.m.: chamber
 unfinished with even floor and cutting begun in S wall.
 - passage: 1.5 x 1.0 m. and 1.2 m. high: no trace of blocking preserved, probably of type II b(1).
 - No trace of coffin or burial.
 - Shaft found filled with disturbed debris: in the upper part was found an Arabic lamp of green galled pottery (29-12-123): the complete clearing is indicative of modern plundering (Reis Ibrahim Faid said that they had the shafts in G 7750 and G 7760 had not been excavated in his time).
- Shaft G 7760 B: man's shaft: 1.95 x 1.95 m.: -11.4 m. in rock: lined with massive masonry, 5.15 m., 6 courses.
 - Turning recess in N wall of shaft: 1.55 m. wide (E-W), 0.9 m. deep and 1.5 m. high: floor of recess is 0.78 m. ak above bottom of shaft.
 - Chambers: two connecting chambers, I south of shaft and II a coffin chamber, opening in S end of W wall of I. cf. G 7660 shaft B.
 - chamber I: type 3 al: on S: 4.65 x 5.3 mm. and 3.65 m. high
 - area, 24.65 sq.m. capacity, 87.51 cu.m. Passage: 2.1 x 1.25 m. and 1.65-1.8 m. high: blocked with masonry set in plaster, type II b(1) removed along the w side.
 - Chamber II: coffin chamber, E-W chamber entered by passage opening in S end of W wall of room I: on W: 4.4 x 3.65 m. and 2.2 m. high: area, 16.06 sq.m.: capacity, 35.33 cu.m.
 - Passage: 1.7 m. long (E-W) \times 1.4 m. wide(N-S) and 1.77 m. high: the opening of the passage in room B, at floor level, is 1.45 m. high: step down, 0.32 m. from floor of room I to floor of passage: the passage enters room II at roof level with step down, 0.43 m., from floor of

APPENDIX B. p. 103.

passage to floor of room II: probably blocked with masonry set in plaster, broken away but the blocks were found scattered partly in SW corner of room I and partly on the floor of room II.

Coffin: red granite sarcophagus of type d, inscribed, stood N-S along W wall of room III 2.3 x 0.95 m. and 0.85 m. high: (1.04 m. high with lid): cavity, 1.78 x 0.55 m. and 0.6 m. deep: flat lid with two rough projecting kx handles on each end, partlt sawed off on S: inscribed on E side only with a horizontal (signs facing to N), nswt dy Inpw htp hnty sh ntr krs m smyt imntyt m nb i im;h hr ntr c; iry pcty d,ty bity iry Nhn s; nswt Mnw-

dd-f: now in Boston Msuem. Canopic pit in SW corner of room II, south of coffin: 0.65 x 0.5 m. and 0.5 m. deep: with rebate on all four

top edges for slab lid.

- Objects found: on the lid of the coffin was a damaged skull: around lay a few broken bones: but no objects were found either in shaft or chambers.
- The shafthm was filled with disturbed debris which had run into room I around the doorway: the facts are explicate and in particular the presence of the granite coffin and the absence of all trace of burial equipment.

M in explicable

Later Constructions:

The field of small and medium mastabas east of G 7750 also runs along the E face of G 7760 and had been partly overbuilt and partly penetrated by structures and shafts of the Prolemaic Roman Period. Against the E face of the mastaba towards the N end, is an x-shaft

which appears to be of the and begins at rock level: probably subsidiary to G 7760.

Shaft G 7760 X: 1.64 x 1.54 m., -9.85 m. in rock: not lined above. Chamber: type 4 a(1) on W: 2.5 x 2.13 m. and 1.1 m. high: χ area, 5.4/sq.m.: capacity, 5.95 cu.m.: chamber unfinished with floor on south not cut down and with four harisonta: horizontal grooves cut in W wall in process of enlarging

the chamber westwards.
Passage: 1.3(N-S) x 1.08 m.(E-W), and 1.1 m. high: no biasking blocking.

No objects found in debris but shaft is broken into by the chamber of G 7752 W.

Old Kingdom South of the mastaba, the field of mastabas and Pfolemaic burial continues southwards.

Lold Kingdom

There are two toms cord made a roced for shafts G. 7760 W. G. 7760 V

6-12-42

Zaty

G 7810: Prince Zati: in old Cheops quarry north of G 7510: mastaba western of two of which the eastern mastaba is G 7820: probably built in order of numeration: exavated by Tewfik Eff. Boulos for the Service in 1923-4(details not recorded).

Note. Section of 67810

could not be made

See Pls.....

because the western side of the mostali

Owner: Zaty,

is burried a. i.

prop. 1/1.92

Mastaba: filled mastaba of type VI a with retaining wall of sloping blocks of nummulitic limestone dressed to a smooth sloping surface: \$38.5 x 19.5 m.: area, 750.75 sq.m. prop.1/2.0: X height, 5.38. m.: with interior chapel and subsidiary N niche

> Chapel: interior chapel of type (3a) of numulitic limestone, bonded with resaining wall: and exterior c.b. chapel. with subsidiar

> > a) interior offering room of type (3a) with plain compound ka-door near S end of W wall: decorated with carved reliefs (not sized technique): 4.2 x 1.5 m.: area, 6.3 V sq.m.: propx. 1/2.8:/ plain compound ka-door of which the outer niche measures, 1.12 x 0.4 m.: inner niche measures, 0.35 x 0.35 m.: entered by doorway in N end of E wall, opening in embrasure in face of mastaba: room paved with stone with floor ?: ?? m. above rock: entered exterior chapel on same floor level.

Exterior c.b. chapel partly destroyed: but consisting of at least three rooms:

- b) hall around embrasure of doorway to a: 4.45 x 2.3 m.: area, 10.32 sq.m.: with doorway in E end \times of N wall and another opposite in E end of S wall: area of room and under walls, paved with stone: in the SW corner is a rectangular offering basin, the c.b. wall on the E is 1.0 m. thick but being built against the slope of the back of G 7820 probably widened upwards: the pavemnt extends to an E-W line 3.0 m. north of the N side of room b and either the north was very thick (3.0 m) or a small room lay north of room b.
- c) south of b: the c.b. wall on the east against G 7820 is preserved but the walls against the face of G 7810 area destroyed the two door jambs in the E wall indicate that room c was 3.2 m. long. the opposite side is so obliterated that it cannot be startmined whether c was a N-S corridor or a room.
- d) the east wall again indicates a room south of c with a length 4.4 m. long: the structures on the W appear to be intrusive.

Total area, a-ba, 16.62 sq.m.: but total of b-d, cannot be accurately estimated.

Subsidiary N niche: monolith recessed in sloping face of mastaba: outer recess, 1.1 x 0.37 m.: inner niche, 0.4 x 0.35 m.: not inscribed.

Decoration of room a of the interior chapel: Ka-door: near S end of wall:

Architrave: missing.

Tablet: man seated facing to right at table of bread in the traditional attitude: wearing later form of panther skin over a short skirt (not the early long robe): table and chair raised on platform (mat?): opposite man, his wife seated at a separate table of offerings facing to left: with both hands half extended towards offering which is heaped with rounded mass of meat(?) and cakes(?): wearing lappet wig and tunic: under the two tables is an ideographic list (bread and beer under wife's table

L determined

on right and ointment and linen underneath between the two tables): over the wife's table, three cuts of meat on a long platter: above both tables a horizontal line giving a short list of offerings mw with hand, ewer and basin: nswt htp: nnt(?swt?): h;w: hst ht....
....rt(iht nb nfrt?): across the top of the table the horizontal line giving titles and name is nearly obliterated: over the man can be read (signs facing to right)(imy-r!) mscw D!ty.

right)(imy-r;) mscw D;ty.

Crossbar: horizontal inscription with signs facing to right,
broken at both ends: (nswt) s; n ht-f imy-r; mscw D;(ty)

Drum: s; nswt D!ty.

Inner recess: not decorated.

Outer recess: two back panels and two sides decorated with palace facade panelling.

W Wall, south of ka-ddor: three registers of offering bearers facing to left and attached to table scene on S wall:

- 1) three men standing facing to left: (a) censing with double bell-censer: (b) hold birds: (c) carries a long box over his shoulder.
- 2) three figures, standing: (a) carries x: (b) a goose in his arms: (c) a piece of linen held out in each hand.

1) about 6 figures, estates bearing offering to right:
(a) a woman with the end of a namegrgt(det. town

sign.
2) estates, probably six, bearing offerings to right:
 (a) label facing to left, Hnm-spss....grgt (town sign det.): (b) label facing to right, dh;-sn-grgt (det. town sign): other details obliterated.

3) two slaughter scenes, with illegible labels above.

3

2

vertically: the top lines each contained the word h; tyt: the second horizontal line shows in word case (thn) nw and contained the names of the six ointments L the third horizontal line contained the determinative, a stone vessel in each case.

E Wall: presentation scene: at S end, a large figure of man, what standing with staff and wand, facing to out to left: in front of the chief figure were 5-6 registers of small figures of which only parts of two lowest registers remain:

1) feet and hooves indicate man bringing in animals or

cattle to right.

2) small cattle (goats or sheep) facing to right: behind them two standing men with arms crossed on breast, one clad in mat-skirt (obviously herdsman): label over men, & illegible.

North door-jamb: obliterated.

S doorjamb: also obliterated but a vertical line of the outer edge appears to end with the name Dity.

N facade-panel: in doorway embrasure: man and wife standing, facing in to left: man with hands hanging at sides: wife with right arm around his left and left hand resting es the also on the left arm of the man: vertical line of signs facing to left on left edge of panel,(imy-r;) mscw imy-r; kit nb n (t nswt)...... on the right behind the pair, stands the son facing also to left, hold papyrus roll against his breast with right, hand, and left hand is hanging at side: over his head, s;-f smw(?) mry-f wr md smcwy imy-r; k;t nt nswt Dity.

S Facade Panel: man standing facing in to right, with hands hanging

preserved, standing facing in to right:

1) two men, (a) carrying scribe's case: (b) a staff and bag. 2) a single standing man, facing to right, with shirt wig and probably short skirt: with right hand hanging and left obliterated: Over him a horizontal inscription, s;-f smsw Dity: before him a vertical inscription, wr md Smcw imy-(r;)......

Shafts in G 7810: two shafts in mastaba, A(wife's shaft) on N and B (man's shaft) on S: in medial axis of mastaba.

Shaft G 7810 A: Excavated by Tewfik Boulos for the Service, 1923-4, wife's shaft: 1.93 x 2.05 m. at top and 1.9 x 1.78 m. at bottom: -14.85 m. in rock: lined with massive masonry above,

4.5 m., 7 courses.
Turning recess in N wall of shaft: 1.25 m.(N-S) x 1.77 m.(E-W and 1.0 m. hilling with horizontal roof and floor at 1.3 m. above floor of shaft which is cut in steps on N side .

Chamber: type 3 afx, with low roof: on S: 3.9 x 4.65 m. and 2.5 m. high: area, 18.13 sq.m.: capacity, 46.32 cu.m.: roof only 0.2 m. above roof of passage.

Passage: 1.5 x 1.45 m. and 2.0-2.3 m. high: roof horizontal

but floor irregular and sloping down from floor of shaft to floor of chamber: no trace of blocking, but probably of type II b(1).

coffin pit: along W wall of chamber a coffin-pit: 2.5 x 1.17 m., and 0.5 m. deep: no trace of coffin found by us. canopic pit: in SE corner, 0.62 x 0.62 m. and 0.55 m. deep:

no rebate. Excavated by us in January, 1936: found filled with disturbed debris dumped in by Tewfik Eff. Boulos containing only a few intrusive fragments.

My Note have: our

Note: There is some confusion in the numbering between the two versions of the manuscript concerning 7810 and 7820.

APPENDIX B% p.107.

Shaft G 7810 B: excavated by Tewfik Eff. Boulos for the Service: man's wife shaft: 2.1 x 2.1 m. at top and 1.95 x 2.0 m. at bottom :-14.6 m. in rock: lined above with massive masonry, 4.3 m., 6 courses. Furning recess in N wall of shaft, 1.95 (N-S) x 2.05 (E-W)m. and 1.77 m. high, with horizontal roof: opens at level of passage bottom of shaft. Chamber: type 3 bf, with high roof: on S: 4.6 x 4.3 m. and 3.2 m. high: area, 19.78 sq.m. capacity, 63.29 cu.m.: roof of chamber, 2.0 m. above roof of passage. Passage: 1.5 x 1.3 m. and 1.3 m. high: no remains of blocking probably of type II b(1). No trace of coffin, but stone coffin indicated by turning recess and size of passage. canopic pit: in SE corner, 0.75×0.7 m. and 0.55 m. deep. Excavated by us in January 1936: found refilled with disturbed dumped debris containing some intrusive object: 36-1-8, 38: faience: frags. of amulets of Ptolemaic period. 36-1-10: alab.: frag. of flat topped circular table: diam.18 36-1-11: alab.: frag. of stand of table, perhaps from above. 36-1-12, 13: alab. 4 frags.: of which one has a flat dressed surface (5.8 x 4.4 x 2.6 cm.): probably from statue. 36-1-14: diorite: frag. XXXXX probably from statue: with part of an incised sign(?) on dressed surface: 5.5 x 8.0 x2.8 36-1-15: 1st.: frag. apparently from basis of servant statuette: painted red on top and sides: round object(basket of basin): h., 2.2 cm.: d., 4.6 cm. 36-1-16: faience, frag. of bowl, Ptolemaic. 36-1-17: alab.: model basing dummy: h., 3.6 cm.: d.top, 5.0cm d.base, 2.4 cm.

Later Constructions:

Three intrusive shafts against E face of mastaba and one against N face.

G 7820: Iy-nefer and his wife Princess Nefertkauw: in old Cheops quarry east of 7810, with the southern ends of the two mastabas aligne: the rock basis falls away to E and N and probably for this reason G 7820 is longer and wider than G 7810.

See Figs..... Plan & Section done. A. F.

See Pls.....

Owner: Iy-nefer,

[crossed out and replaced with]

"44.50 x 21.0 m. area 934.5 sq. m."

Mastaba: filled mastaba of type VI a with retaining wall of sloping
blocks of num. lst., dressed to a smooth sloping surface:

43.0 x 24.0 m., area, 1032 sq.m.: prop.1/1.8: height, 6.10 .:

with interior chapel and subsidiary N niche.

Chapel: interior chapel of type (3a) of nummulitic limes tone, bonded with retaining wall: remains of exterior c.b. chapel: with subsidiary N niche.

a) interior offering room of type (3a) with plain compound ka-door near S end of W wall. decorated with carved reliefs (not sixed) technique): 4.25 x 1.57 m.,: area, 6.67 sq.m.: prop.1/2.7: plain compound ka-door of which the outer niche measures 1.15 x 0.3 m. and the inner niche, 0.33 x 0.25 m.: entered by doorway in N end of E wall. opening in embrasure in face of mastaba: room paved with stone with floor..247 m. above rock probably entered from exterior chapel on same floor level.

Exterior c.b. chapel: in front of doorway is a hole in the rock probably arising from the olf quarrying of Cheops: in this hole has been constructed a high c.b. structure found on rock and reaching nearly the floor level of room a: this structure had been excavated to rock by Tewfik Boulos and it excat character could not be determined: it had a doorway in its N wall opening to N where it had been block by stone wall (mastaba?):
I cannot accept thia as part of the original c.b. chapel bacause it is too low down, is not symmetrically in relation to the doorway of room a: and was not connected with a room(c) on the south which appeared to be part of the exterior c.b. chapel: if it was of the 0%K and represented a reconstruction of the c.b. chapel then it must have contained a long flight of steps leading from its floor to the level of the doorway of room a.

b) hall around the doorway of room a: now entirely destroyed: probably originally at least 3.3 m. long by at least 3.7 m. wide (E-W).

c) at the S end of the mastaba face is an E-W room which appear to be part of the original chapel: 1.55 x 3.3 m. area > 5.11 sq.m. the S wall was 1.6 m. thick: the E wall is not completelt preserved: the N wall which separated c from b or from d, is 1.1 m. thick: entered by doorway in E end of N wall: the space north of this wall was obviously part of room which was wider in the E-W direction and may have been another subsidiary room room or part of the hall b: thus there hall b appears to have wider than 3.3 m. E-W and to have had at least two other rooms, one east of c and another between these two rooms and b.

Subsidiary N Niche:... in sloping face of mastaba outer recess, 1.10 x 0.36m.: inner niche 0.39 x 0.29m

Decoration of room a of chapel of G 7820: All reliefs obliterated except on small part of ka-door: Ka-door:

Architrave: missing.

Tablet: obliterated except for lower right hand corner: showing bird head and animal head(oryx?) with a raised horizontal line above: apparently there were other horizontal lines of offerings (short list).

crossbar: inscription with signs facing to right:
.....dy Inpw hnty sh ntr prt-r-hrw n-f (det. beer and bread) re nb monthly and half monthly feasts m w;g.

TO SECURE Drum: apparently two horizontal lines: (1) illegible titles (2) <u>Ity-nefer(t)</u> (det. man seated).

Inner niche: not decorated.

Back of outer recess! on the N standing figure of woman facing in to right: above her head 4 vertical lines with signs facing to right: (1) (s!t nswt) nt ht-f?....
(2) im;h hr it-s: (3) mt hm ntr Nt (4) Nfrt-k;w

- N Doorjamb: on left, legs of woman standing facing out to right: rest obliterated: probably standing behind her husband.
- S Doorjamb: obliterated.
- N Facade Panel: man and wife standing facing in to left: man with shm wand: in front of man is a boy: between the man and wife is a small girl labelled s; t s; - f Nfrt-(k;w).
- S Facade Panel: man standing with staff and wand facing in to right: in front of him two children: behind him a larger f figure with roll in left hand held on breast and right hand hanging, probably his eldest som.

[crossed out and replaced with] "5.73 sq. m."

Should be

APPENDIX B. p.109.

- Shafts in G 7820: two shafts in medial axis L A, on N and B, on S: the wife is a princess and may therefore have been buried in the chief shaft B, with her husband buried in shaft A.
- Shaft G 7820 A: 2.1 x 2.25 m.: at top and 1.8 x 1.9 m. at bottom:
 -11.0 m. in rock: lined with massive masonry above, 3.9 m.,
 4 courses.
 - Chamber: type 4 b(1) with unfinished roof(probably designed as type 3): on S: 2.7 x 2.55 m.: and 1.75 m. high: area, 6.88 sq.m.: capacity, 12.04 cu.m.
 - Passage: 1.35 x 1.2 m. and 1.4 m. high: blocking, remains of rough masonry wall, type II c(2?).

 No trace of coffin: no canopic pit or recess.
 - Shaft and chamber found filled with dumped debris but to a height of doorway: excavated by Tewfik Boulos in 1923-4 reexcavated by us in January, 1936.
- Shaft G 7820 B: 2.12 x 2.0 m. at top and 1.92 x 1.85 m. at bottom:
 -16.55 xxxxx m. in rock: lined with massive masonry, 3.42 m.,
 4 courses.
 - Chamber: type 3 af: on S: 4.1 x 4.0 m. and 2.9 m. high: area, 16.4 sq.m.: capacity, 47.56 su.m.: ceiling marked with red construction lines on W side and on western side of N and S sides: the lines are 0.5 m. from the walls on N and W but only 0.2 m. on the S: the wall line is marked mh 1: the S line is marked mh 1 rsy: these lines seems to indicate an intention at one time to line the chamber with masonry: but the canopic pit is close to the SE corner and was made after the intention (if it ever existed) had been abandoned.
 - ever existed) had been abandoned.

 Passage: 2. 5 x 1.2 m. and 1.2 m. high: no trace of blocking:

 probably of type II b(1).

No coffin pitmor trace of coffin.

- Canopic pit: in SE corner: 0.55 x 0.6 m. and 0.55 m. deep: no rebate.
- Shaft excavated by Tewfik Boulos in 1925-4 and refilled with dumped debris: re-excavated by us in Feb. 1936: several objects and frags, of the O.K. and the Ptolemaic period were found in the debris:-
 - 36-2-4: w.lst.: block from a wall scene in relief but only small part of the worked surface preserved:
 44 x 33 cm. and 24 cm. thick: on the preserved part is an inscription in two horizontal lines in relief with signs facing to right: (1) (s;)-f smsw mry-f (2) im; h hsy-f
 - 36-2-5: faience: uzat eye: Ptol.
 - 36-2-6: alab. frag. with rounded surface, from statue or statuette: 8.0 x 5.0 cm. and 3.8 cm. thick.
 - 36-2-8: dark colored hard stone (granit?): hammer stone, much worn: 12.6 x 7.0 cm. and 6.6 cm. thick with groove near butt end.
 - 36-2-9: sand stone (hard): used as whetstone for copper tools: green copper stains on four sides: 12.2 x 12.2 x 7.1 x 5.5 cm.

Later Constructions:

Note
This rock cut tomb
has not been numbered
& measured. We have
plan & section of this
tomb made by T. Baulos Eff. (see his drawings)

The field of small mastabas east of G 7760, 7750, and G 7510 continues northwards east of G 7820, here also with Ptolemaic structures and intruded burials: see also the exterior chapel of G 7820 described above: under the N part of the exterior chapel, the rock is broken through into a rock cut chamber of type 9, entered from the S (G 7....).

16 - 1 - 43 A. F.

APPENDIX B. p.110.

G 7060: Prince Nefermatat, son of Queen Nefertkauw (a daughter of Sneferuw) and Cheops: mastaba immediately W of G 7050 assigned to Case.

Run Cuss Nefertkauw: with its N and S ends aligned with N and S ends

See Figs...... Plan & Section done a.f.

See Pls.....

Owner: Nefermaiat,

@ height - 4. 40 m.

wastaba: filled mastaba of type VI a with retaining wall of sloping nummulitic slabs, dressed to a smooth sloping surface / (not finished on N and W): 26.25 x 11.9 m.: area, 312.37/sq.m. prop.1/2.2: with interior nummulitic chapel and paved exterior corridor.

Chapel: interior offering room of type (3b) with palace facade door and exterior corridor.

a) interior nummulitic chapel of type (3b) with palace facade in the middle of W wall: 4.25 x 1.6 m.: area, 6.8/sq.m.: prop.1/2.65: √palace facade door in middle of W wall, .1.99.. m. wide with shallow niche in middle of door: entered from E by doorway in N end of E wall room paved with stone: at inner end of N doorjamb, is a socket for the wooden doorpost which a groove to introduce the post into the socket: doorway opens in embrasure in E face of mastaba, 3.05 x 0.45 m.

~ with

b) exterior open corridor between face of G 7060 and back of G 7050: paved with well dressed slabs; of num lst.: N end of corridor closed with nummulitic wall not bonded with mastaba but built against the sloping surface of both mastabas: wall, 1.57 m.(E-W) at bottom and east mogs, wide, with slightly sloping face on N: built befire pavement: corridor b measures x 1.53(S end) to 1.6 at N end: area, ca. 40-85 sq.m.: no trace of doorway on S nor of roofing. 39.72

1 25.30 x 1.53 m.

Subsidiary N niche in corridor b towards the N: Lower niche, is broken away and measurements cannot necessarements connot pecoration of room a of chapel G 7060: Prince Neferma at:

Nummulitic chapel of type (3b): carved reliefs (not sized technique

5-3-40.

Architra ve of ka-door: inscription of two horizontal lines in relief, with signs facing to right: on the left is the prince seated with staff, full wig, and short skirt:

facing to right: Lepsius LG 57:

(1) nswt bity Snfrw s;-t-f nt ht-f smswt Nfrt-k;w s; n-s

smr[wity].

(2) not small (?) hat - take start starting

W Wall, north of ka-door: large figure of Neferma'at, standing facing to left with staff and handkerchief: wears necklace, Hed Snfrw-hc-f.

full wig, and panther skin over short skirt, holding staff of man with right hand and with left hand hanging at side: over his head is written vertically, s;-f smsw disty bity mdw snfrw-hc-f.

W Wall, south of ka-door: largexfigure man and wife standing facing to right: man with staff and handkerchief, full wig, broad necklace and short skirt: wife behind him, wears lappet wig and long tunic: her arm around his shoulders with left hand

- (3)wr pr-Dhwtyt.
- (4)(Nfr-m;;t.

(6).hm ntr Mr-s-cnh.

Wall: nearly obliterated: a subregister shows traces of more than five figures proceeding to left.

/six

APPENDIX B. p.111.

under the chair lies a hunting dog named cbw. In front of man, above the remains of a picture list of offering, parts of three registers:-

(1) at right end, two trussed birds on circular table and small pan with bread(?) on ground below.

(2) at right end, three tall jars in ring stands (two with spout).

(3) at the right end, at top of register, top of a large bowl with cover.

Beneath the whole scene ran a subregister of dancers of which only two women clapping hands are preserved at the right end: possibly musicians and dancers to left.

E Wall: presentation scene:

At S end of wall, man and wife standing facing to left: man with staff and skirt: wife, only feet remain. in front of of man, a vertical line of inscription, m;; (ndt) hr innt m niwt-(f)nt pr-f nt dt.

1) top as preserved: three standing figures facing to right: (a) holds roll before him. reading scribe: (b) standing facing to right in respectful attitude with arms eross ?) on breast: (c) also standing but broken away above the waist?

broken away above the waist?
2) men bringing cattle: (a) carrying hunch of beef in left arm and leads bull by halter with right hand: (b) places his left hand on bull's back and reaches back with his right to lead in another animal: rest broken away.

3) men bringing two oryxes: (a) a tethered oryx, labelled rnn m;hd: (b) two men bringing a second oryx which resists; the first man pulls and the second pushes the oryx: labelled rnn m;hd: rest broken away.

4) a provession of large birds: (a) axtatheradxoryxy ixbelladxrmxxmihdxxxbxxxxmenxmmxmingxaxxecond oxyxx a crane d;t: (b) a second crane, d;t: (c) a third crane, wd;w (d) fourth crane, w......

Door-jambs: obliterated.

Facade panels: not decorated.

Shafts of G 7060: two shafts in medial axis, A, wife's shaft on N and B, man's shaft on S.

Shaft A: wife's shaft: 1.75 x 1.75 m., lined with small masonry, 2.6 m. ends at rock, type 7 X: no chamber or trace of burial: perhaps unused.

APPENDIX B. p.112

Shaft G 7060 B: man's shaft: 2.1 x 2.08 m., -12.8 m. in bock: lined

```
above with massive masonry, 5.0 m., 5 courses.
           Chamber: type 4 b(4)x: on S: 4.75 x 3.7 m. and 2.0 m. high: area, 17.88 sq.m.: capacity, 35.76 cu.m.
                 red construction line on the ceiling E-W lines and four
                N-S lines: the E-W lines measured from N wall of the
                chamber are at distances of 0.5 m., 1.0, 3.2, and 4.15 m.: the N-S lines measured from the east wall at
                distances of 0.52 m., 1.25 (medial axis of passage),
                 2.4 \text{ m}, and 3.15 \text{ m}. from the E wall.
           Passage: 1.47 x 1.7-1.95 m. and with minimum height of 1.55 m.
                floor sloping slightly: roof horizontal but with edge on shaft side cut away to introduce coffin: blocking of
                 large block of stone set in plaster, type II b(1):
                 tipper part of blocking removed.
          Coffin: krst coffin of fine white limestone smoothly dressed:
                 type e, uninscribed: standing along W wall of chamber
                 set N-S: 2.65 x 1.3 m. and 0.8 m. high: (1.185 m. with
                 lid): cavity, 1.83 x 0.6 m. and 0.575 m. deep: heavy
                 krst lid slightly vaulted with heavy end bars and two
                 rough projecting handles at each end: red nfr sign pain-
                 ted on S end (foot end) of both lid and coffin.
           canopic recess in W wax end of Sw wall: 0.8(E-W), 0.8 m. deep
                and 0.85 m, high: no rebate.
           Burial: inside the coffin five frags. of limb bones, one k
                broken rib.
     Shaft found open to a depth 10 m.: but rest of shaft and chamber
           filled with disturbed fairly clean debris: apparently the
           recent excavation of the chamber had been abandoned or was
           made by illigit excavators.
Objects found in shaft:
26-2-60: lst. frag. of faience cornice of false door stela: two
           fitting frags.: carved and painted.
   \sqrt{26-2-61}: 1st. two fitting frags. of large basin: h., 20+ cm.
    diam. base. 13.4 cm.: incomplete. 26-2-62: and 62: two frags. of alabaster, one from a vessel and
           the other from slab or table.
   \sqrt{26-2-64}: coarse RW: tray: h., 3.0 cm.: diam. top, 32 cm.: d.base,
           27 cm.
     26-2-65 to 67: faience: frags. shawabti: amulet: cyl. bead:Ptol.
     26-2-68, 69: bronze(?): frags. Ptolemaic.
Objects fund in chamber:
   1 26-4-87: RW (red wash): bentsided bowl, type C-XXX (with plain rim)
           h., 11.2 cm.: diam. rim, 42.4 cm.: h. of top, 5.6 cm.:
           diam. bend line, 39.2 cm.
   \sqrt{26-4-88} to 90: w.lst.: three domed lids from canopic jars:
           88) h.m 4.0 cm.: h. dome, 3.6 cm.: max., diam. 14.4 cm.
           89) h., 4 cm.: h. dome, 3.6 cm.: max. diam., 16 cm.
           90) h., 7.4 cm.: h. dome, 5.3 cm.: max. diam., 18.4 cm.
   \sqrt{26-4-92}: RW: jar of type II b(1): frag. from top part: h., 6.8 cm.
   (probably ca. 30 cm.): d.rim, 9.4 cm.: d.neck, 9.2 cm.:
d.max., as preserved, 16 cm. (probably about 23 cm.).

26-4-93: RW: frag. of bowl, flat* bottom, contracted mouth and lip
           spout: type LXXI ..... h., 4.5 cm.: d.top, 8.6 cm.:
           d.max., 9.2 cm.: d.base, 6.2 cm.: large model.
Later Constructions:
     At the NW corner of G 7060 ended all tracex of thw wide rubble
           wall which ran from there eastwards to a point south of the
           SE corner of G 7140 and was filled in south of Pyr. G I-c
           and south of street 7000, to bring the level of the area
           north of the wall up to the base of Pyr. G I-c: like G 7050
```

South of G 7060 and G 7050 was an open passage from which thexest chapels of the three mastabas G 7050, 7060, and 7070 were entered: south of G 7060 was a rubble lined structure, apparently a construction plan for some structure further

times by an enclosure marked by a curving wall.

the mastaba G 7060, later than the rubble wall was built outside and close to this wall: the area between these mastabas and G I-c* had been occupied in Saite-Ptolemaic

west: it measured 16.1 m. long (E-W) and 7.0 m. wide (N-S): westwards it was continued but by a filled structure with retaining walls of c.b. which was built against the W end of the rubble structure beginning opposite SE corner of 7070: the c.b. place could not be followed westwards because of the tourist pe th to the Sphinx: this composite structure or at least the c.b. part appears to have been constructed after G 7070 which closes the E-W passage giving access to the chapels of G 7060 and G 7070 at its Western end.

South of the area in question, the rock surface slopes SSE and is covered a deposit of mason's and quarrymen's debris about 3-4 m. deep: this layer decreases from towards the south and southeast owing to weathering: on the surface of this debris stood in the O.K., a number of small mastabas with rubble lined shafts but the mastabas have been completely denuded away leaving only the denuded shafts.

Under the layer of debris which bore the O.K. mastabas was a wide inclined construction plane (with two heavy retaining walls of rubble (mud plastered on outside): which lead up to the north and appeared to have been used during the construction of Pyr. I or the nucleus mastabas: there we were unable to establish a connection between this old plane and the later

plane south of G 7060.

Later the whole area, called by us G 7000 SW, was covered with ptolemaic structures, denuded away, and filled with intrusive burial shafts of the same period.

G 7070: Sneferuw-khaf: son of prince Neferma at west of G 7060 but shifted 3.7 m. to South, but not enough to give the chapel an open view to the east.

See Figs..... Plan a Section done a.F.

See Pls.....

Owner: Sneferuw-khaf,

wastaba: so similar to G 7060 that the two were probably constructed A not far apart in time: filled mastaba of type VI a with retaining wall of sloping num. 1st. dressed to a sloping surface (not completely finished on S, W and N): 26.0 x 12.85 m.: area, 334.1/sq.m. prop.1/2.02./h., 5.40 m. with interior chapel and subsidiary N niche.

Chapel: interior nummulitic offering room of type (3b) with palace facade ka-door in middle of W wall and serdah on South:

- a) interior offering room of type (3b) with palace facade ka-door in middle of W wall: 4.25 x 1.6 m.: area, 6.8 $\sqrt{}$ sq.m.: prop.1/2.65: $\sqrt{}$ exactly same size as chapel G 7060): palace facade door in middle of W wall, 1:79.. m. wide, with shallow niche in middle of door: entered from E, by doorway in N end of E wall: opening in embrasure in face of mastaba 3.05 m. wide (N-S) and 0.33 m. deep: room paved with stone partly torn up in recent times: serdab south of S wall.
 - b) Exterior open passage between face of G 7070 and back of G 7060, not paved, but closed at N end with wall(as G 7060), 2.7 m. long (E-W) at bottom but widening upwards following the slopes of the two mastabas which it km connects: the wall is 1.25 m. thick (N-S) at bottom but being battered on both faces decreases to 0.85 m. thick at top: the open passage from this wall to the SW corner of 3 7030 is 21.25 m. long: the width at base of dressing is 2.7 m.: the floor apparently of packed 1st.debris has been denuded particularly at the S end to a little

below the level of the chapel: it opens at the south without doorjambs into the E-W passage south of G 7060, which is about 5.0 m. wide.

- Serdab: E-W serdab, south of S wall with window opening in vertical slot in middle of wall and about 1.2 m. above the floor: serdab measures, 1.25 x 2.77 m.: and 3.4. m. high, area, 3.46 sq.m.: capacity, 11.76. cu.m.: entered from chamber by widening window slot and broken into from Exambar south through S wall: found filled with debris: no objects.
- Decoration of room a of chapel G 7070: Sneferuw-haf:
 Offering room of type (3b) partial decorated with carved relief
 (not sized technique):

lines with signs facing to right separated by raised lines:
(1) nswt bity Snfrw s;-t-f nt ht-f Nfrt k;w s; n-s d;sty bity

- Nfr mjet.
 (2) sj-f djsty bity mdw H;p smr wety h;ty-e iry Nhn iry Pinb Snfrw-he-f.
- W, N, and S walls otherwise undecorated: in middle of S wall, wx window slot of serdab.
- N Doorjamb: nearly completely obliterated: on base line of scene feet of large figure of man facing to right with staff in left hand: ehind him another slightly smaller figure of man also facing to right, probably eldest son: between man and staff, feet 6f small boy also facing to right.
- S Doorjamb: recorded by Lepsius, L G

 Large figure of man standing facing out to left with staff in right hand and handkerchief in left: behind him stands a slightly smaller figure probably his eldest son with two vertical lines of inscription partly preserved (1) traces only: (2) hm ntr Hwfw hry sst;(K;-m)nfrt; in front of man's staff a small figure of a man facing to right, perhaps a funerary priest.
- Entrance doorway: Architrave: found thrown down in debris of street passage b: in relief: at left end seated man facing to right with staff in left hand and right half extended: wears short wig, broad necklace and short skirt: in front of him his name is written vertically, Snfrw-hc-f: to the right three horizontal lines with signs facing to right, separated by raised lines:

(1) dy newt htp dy Inpw htp hnty sh ntr krs-t-f m hryt ntr smyt imntyt i(w nfr wrt im;hw hr ntr c;:

(2) prt-r-hrw wp rnpt Dhwty tp rnpt Wjb hb wr hb nb rc nb iry pcty s; nswt d;sty bity h;ty (-c).
 (3) Nswt bity Snfrw s;t-f Nfrt-k;w s;-s pw iry pcty d;sty

(3) Nswt bity Snfrw s;t-f Nfrt-k;w s;-s pw iry pcty d;sty bity Nfr-m;ct s;-f iry pcty d;sty bity and then the name written vertically Snfrw-hc-f.

- Shafts in G 7070: two shafts in medial axis: A, unused, on N and B, man's shaft on S.
- Shaft 6 7070 A: 1.75 x 1.75 m., lined with small masonry, 3.85 m., ending at rock surface: type 7 X: no chamber: no trace of burial, probably unused.
- 2.25 2.45
 Shaft 0 7070 B: man's shaft: 1.85 x 2.05 m.: -11.2 m. in rock: lined above with massive masonry, 5.5 m., 5 courses.
 Chamber: type 4 b(1): on S: 4.55 x 4.15 m., and 2.15 m. high!
 area, 18.88/sq.m.: capacity, 38.59 cu.m.
 Passage: 1.65 x 1.75 m. and 1.5 m. high: floor sloping down
 - passage: 1.65 x 1.75 m. and 1.5 m. high: floor sloping down to south: roof horizontal with outer edge cut away to admit coffin (as G 7060 B): blocked with three courses of dressed block laid in plaster and resting on a layer of rubble: blocking type II b(1) with top course removed

APPENDIX B. p.115.

lid): cavity, 1.98 x 0.59 m. and 0.35 m. deep: heavy krst lid slightly vaulted with heavy end bars and two rough projecting handles at each end: on the foot end, of the content of sandals.

Canopic recess: in W end of S wall: 0.7 x 0.7 x 0.7 m.: W without rebate.

Shaft found empty to a depth of 12.8 m. from top: the rest was filled with disturbed debris which had run into chamber:

Objects found in floor debris of chamber:

29-10-6: alab. model of round bottomed saucer: one and a half exmples: h., 1.4 cm.: d., 5.6 cm; Wes S-X

29-10-7: alab.: model jar: shoulder jar with flat rim on body, possibly with two horizontal handles: on a ring stand: h., 7 cm.: d.rim, 2.2 cm.: d.body, 3.1 cm.:

d.base, of ring stand, 2.1 cm.

29-10-8: alab.: model one handled jug: dummy and dummy handle: h., 7.3 cm.: d.rim, 2.8 cm.: d.body, 4.8 cm.: d.base, 2.8 cm. Mes S XIV

Coffin: krst-coffin of fine white limestone, smoothly dressed type 5 e, uninscribed: standing N-S along W wall of Ex chamber: 2.69 x 1.29 m. and 0.84 m. high (1.155 m. with

Later Constructions:

w. max., 2.4 cm.

The area immediately west of G 7070 could not be excavated because of the tourist road to the Sphinx: further away to the WSW stands the mastaba of Dyn.VI: G I S 12.

h., 2.1 cm.: d.rim, 5.4 cm.: d.base, 2.6 cm: type 5-XA

√ 29-10-11: copper (patinated): model of flat bottomed basin:

h., 2.1 cm.: d.rim, 5.4 cm.: d.base, 2.6 cm.

29-10-12: bronze(?) twisted object (Ptolemaic): h., 3.3 cm.:

h., 22.0 cm.: d.body, 20.8 cm.: d.base, 12.8 cm.

√ 29-10-13: w.lst.: canopic jar broken in xxx ll frags.:

South of the mastaba is the construction fully described under G 7060 (q.v.): there was no passage between this plane and the south end of G 7070 and the plane was built after that mastaba has been dressed.

North of the mastaba G 7070, no trace was found of the rubble wall running eastwards from the NW corner of G 7060: at a distance of 2.77 m. on the E and 3.05 m. on the W stood a massive c.b. chapel of four rooms which formed the eastern part of the exterior c.b. chapel of G I S-10: the N wall of this chapel was in contract with Pyvamid G I-c in front of this chapel and partly built over its eastern end was a rubble structure, the exact character and date of which could not be determined: between this structure and the N wall of G 7070 had been inserted a small mastaba, G 7073: west of G 7073, between G 7070 and the c.b. chapel had been inserted another small mastaba B 7071.

Appendix B p. 116.

12) The Mastabas built in the Period from The Accession of Mycerinus to the end of the reign of Neferirkara of Dyn. V

In succession to the eight nummulitic mastabas, two mastabas of the same type stand, one of them G 7560 in line 5 south of G 7550, and the other G 7670 south of G 7660. South of G 7670 is a third mastaba of different type, the massive stone mastaba G 7690. The surface of the rock under these three mastabas slopes rather more steeply down to the SSE, and probably as a result the faces of the three are set eastwards, not in alignment with the older

mastabas of lines 5 and 6.

Shepseskaf or

G 7560: immediately south of G 7550 on sloping ground and set forward with its See Figs done as in this line; name not found; in form and size (mastaba, skapet and c.b See Pls. --- Name: not recovered. chapel

MASTABA: mastaba of type VI a with retaining wall of sloping slabs of num. 1st. dressed to a sloping surface; 38.0 x 20.5 m.; area 779.0 684.5 Height of the sq.m.; prop. 1/1.85; with interior chapel and subsidiary N. niche.

preserved. 3.88 m. CHAPEL: interior chapel of type (3 a) of white limestone; exterior c.b. chapel; subsidiary N niche; outer niche (0.8 x 0.25 m), inner niche

O.2 x 0.1 ml; recessed monlith.

© Remeasurements a) interior offering room of type (3 a) with plain compound ka-door near S end of W wall; fully decorated with carved reliefs but destroyed to a level just above reliefs on 5.5 me W and N wall and just below reliefs on S and E; 4.4 x 1.55 m; area 6.82/sq.m.; prop. 1/2.84; ka-door destroyed; entered by doorway in N end of E wall; opening in embrasure in face of mastaba; room paved with stone; floor % 35 m. above rock; doorway approached by four stone steps ascending from floor 60 to a lo

floor of the G. Exterior c.b. chapel of four rooms (b-e); measuring on outside 12-35 x 8.7 m.; area 107-44 sq.m./
b) E-W pillared hall set symmetrically around doorway to room a; 4.2

x 7.0 m.; area 29.4/sq.m.; with two round column bases in an E-W row; diam. of bases 0.9 m.; the W column is close in front of the steps to room a; built on the floor a flight of 4 steps with a total length(E-W) of 1.1 m. and a width(N-S) of 0.75 m, height in the NE corner of the hall stands a rectangular basin stone basin, 0.75 x 0.67 m.; uninscribed; enclosed on W and S by a c.b. wall, 0.3 m. thick; entered from vestibule c by doorway in E end of S wall, with recess for wooden door on inside; south

c) vestibule room 2.6 x 1.55 m., area 2.25 sq.m.; entered by doorway in S end of E wall, opening in an embrasure in the E face of the E wall of the chapel; indication of wooden door on the inside doorway to room d with indication of wooden door on inside of d.
d) N-S room W of c; 3.7 x 2.25 m., area 8.32/sq.m.; entered by doorway from c, in N end of E wall(door in d); with doorway to e in S end of W wall, obstructed by later wall.
e) N-S room W of d and against face of mastaba; 3.7 x 1.3 m., area 4.81/sq.m.; entered by doorway(?) in S end of E wall; possibly

4.81/sq.m.; entered by doorway(?) in S end of E wall; possibly a closed space, a serdab(?).

Total floor area , b-e, 46.78 sq.m. 46.56 sq.m. Total area, a-e, 53.6 sq.m. 53.38 17.m.

SUBSIDIARY N NICHE: m sloping face of mostaba

outer recess 0.86 x 0.8 m.: inner niche 0.25 x 0.8 m.

乂

DECORATION OF ROOM & OF CHAPEL:

Offering room of type (3 a) of white limestone with carved reliefs in good style: walls so destroyed that decoration was preserved only on W wall north of ka-door and on N wall; a few fragments

Mycerinus

see below.

Q 4.03

were found in the debris of the chapel. KA-DOOR: only the N side of the outer niche is partly preserved: two lower registers - the remain: men bringing funerary meal.

1) two tables of food one above the other and a standing man facing to left holding up a third table of food.

2) man standing facing left holding out a wine jar in right hand and a table cake or loaf of bread in basin in his left hand.

WEST WALL: north of ka-door: presentation scene with sub-register; the wall is to be reconstructed with a large figure at the A end of the wall , standing facing to left with his feet on the base of register 1 as preserved: in front of him a number of registers of which only one is preserved:

1) (a) on the right, scribe squatting, writing, facing to right; b) part of a judgement scene, man grasping and beating another man leaning over to right; c) herd of goats being driven to

right by one herdsman with stick. Fragment 29-7-16 showing a squatting scribe may have come from this wall in front of (a), above.

2) Subregister: nine men presenting offerings: a-b) two men standing holding out two strips of linen(one on each side of man);
c) man standing facing right, holding out in each hand, on each side of him, a cylindrical jar; d) carrying staff over his shoulder, left hand not clear; e) man with sandals in left hand and a roll of papyrus in his right hand against his breast; f) carrying two bags, a long clothes bag against his body in right hand and a smaller bag hanging from his left hand; g) two men bringing a bull, one leading and the other driving with a stick, labelled iw; pr mdt; h) man holding up

a bunch of three papyrus stalks on each side. Fragment 20-7-14 probably came from the back of the outer niche onx the south side, showing parts of three vertical lines with signs facing to right, with a border down the outer edge: 1).....shm-hs(?)-km(hm ntr) widt, 2)....hry wdb..(vertical sign) ht-'nh m...; 3) broken away; evidently titles and name over standing man facing to right(probably the owner).

NORTH WALL: consisting of chief scene, a swamp scene, above and one register below; upper scene nearly destroyed. There remains a small part of the swamp at top, clearly seen in a rectangle of rippled water extending from the west wall to above the inscriptof the second figure from the E in the subregister. The scene may be reconstructed with a swamp on which the owner appears on a papyrus raft hunting or fishing, against the usual representation of a papyrus swamp. The space on the right(about 1/6 of the length of the wall) may have contained registers of small figures engaged in mat-weaving or similar occupations.

Fagment 29-7-15 perhaps comes from this scene. It shows two men standing with long paddles, probably steering a boat to the right; to the right of them is part of a squatting man. If this is correct then the owner in the middle of the boat faced to the right.

The subregister across the whole wall below the swamp scene : six men proceeding to the right carrying animals birds and parts of a trap, inscribed above with signs widely separated is the label: pri m sht wh' ;pdw ("coming forth from the field of the bird swamp"(?)): a) runs to right with gazelle in his arms held against his body; b) carries yoke from which hangs two boxes containing ducks; c) man carrying two boxes on yoke but contents not visible, with papyrus flowers over right arm; d) carrying over his shoulder an object made of sticks and ropes, probably a bird trap; e) carrying live crane in his arms, holding its bill with one hand, in front of him is written vertically: wh's! (fisherman's boat and

goose); f) carries a live goose in his arms.
Frags. found in the chapel: in addition to the three frags. mentioned above, 13 other fragments were found:

 \checkmark 29-7- 16 d: feet of female figure facing to right.

√ 29-7-16 h: feet of man facing to right with unidentified obect at feet.

29-7-16 b: man holding goose, afcing to right.

Prolon ou Nobem The other fragments are small or obscure: 29-7-16 k: Seet of autobar (northern)

"20-7-14" mentioned here is a typographical error, most likely for "29-7-14."

> The object Reisner refers to as "29-7-16b" was recorded as "29-7-16l."

- SHAFTS IN G 7560: Two shafts in medial axis, A on N and B(chief shaft) on S.
- Shaft A: $2.05 \times 2.1 \text{ m.}$ at top and $1.95 \times 1.925 \text{ m.}$ at bottom; 14.8 m. in rock; lined above with masonry, 1.35 m., 5 courses; unfinished cutting in bottom; not chamber; type 7 X: completely plundered or unused.
- Shaft B: Chief shaft, 2.05 x 20.75 m. at top and 1.875 x 1.9 m. at bottom;
 16.32 m. in rock; lined above with course of rubble on rock, a low course of masonry (0.6 m.) and two courses of heavy masonry(1.275 m), total height of lining above, 1.875 m.
 - Chamber: type 4 b(1) x, with low ramp extending into chamber; a degeneration of type 2(unlined) and probably intended to be of type 3 but roof left uncut; 3.65 x 3.45 -3.6 m. and 2.82 - 3.05 m. high, with roof sloping unpwards to S; area 12.84 sq.m.; capacity 37.71 cu.m. Passage: 1.5 x 1.65 m. and 2.05 m. high on shaft side and 2.25 m. high at
 - top of interior ramp; the roof is horizontal but the floor slopes gently downwards from shaft to chamber and inside the chamber is continued by a ramp.
 - Ramp: inside chamber: 1.85 x 1.65 1.55 m.; height at passage side 0. 26 m. Canopic pit: in SE corner against the rock-cut walls, 0.635 x 0.575 m and o.5 m. deep; without rebate.
 - Coffin: white limestone, type d, with flat lid; 1.93 x 0.73 m. and 6.62 m. high; cavity 1. 75 x 0.52 and 0. 53 m. deep; thickness of lid 5 cms.; around the outer edge of the box runs a rebate (5 cms. wide and 3 cms. deep); the under edge of the lid has a moulding fitting into this rebate; the lid has two long handles at each end.
 - Blocking: interior wall of good masonry bound with plaster; type III b(2); upper part broken away.
 - Objects of the original equipment found in the chamber:
 - 36-12-4: white limestone, fragments of coffin, nearly complete; ; see coffin, above; fragment of lower part of corner marked with signs
 - in red paint; Photo B 8772. 26-12-5: white limestone "reserve head", broken in 8 fragments, nearly complete; h. 27.0 cm., w. 16.0 cms.; front to back 21.0 cms. Pl. 73.
 - 26-12-6; white limestone "reserve head", lower part of face with 15 small fitting fragments, incomplete; h. 27.7 cm., w. 15.3 cm., front to back, 24.0 cm.; Pl. 73.
 36-12-7: flint, black; flake with rhomboidal section, rounded butt
 - and pinted end; 1. 9.5 cm., w. 1. 15 cm., th. 0.3 cm., Rt.
 Photo. C 13949-13950(No. 1).

 36-12-8: flint, half of flake(butt end), rhomboidal section; 1. 6.4 + cm.,
 w. 3.1 cm., th. 0.9 cm.; Photo C 13949-13950(2).

 36-12-9: flint, part of flake(pointed end), rhomboidal section; 1. 11.6
 cm., w. 3.0 cm., th. 0.7 cm., Photo C 13949-13950(M. 2)

 - cm., w. 3.0 cm, th. 0.7 cm.; Photo. C 13949 13950(No. 3) 36-12-10: RP, frags. forming half a bowl with round bottom and recurved rim; type C XXXII a; h. 13 cm.; d. rim 25 cm.; d. body 26 cm. P1. 78 d(1/5).
 - 36-12-11: RP frags. of over half a flaring bowl with flat bottom and moulded rim(flat on top); type D XXXIX b; h. 16 cm., diam. rim 28 cm.; diam. base 15 cm.; Pl. 74 d(1/4).
 36-12-12: RP frags of over half of basin with flat bottom, roll-rim and
 - short xxxxx tubular spout; type D-XXXV a; h. 24 cms., diam. rim 25 cm.; diam. max. 31.6 cm.; length with spout, 34 . 2 cm. diam.
 - base 10 cm.; Pl. 74 d(2/4).
 36-12-13: DbW frags. of upper part of small jar; probably type XX A-VI c; h.10.4 +cm.; diam. rim 9.4 cm., diam. body 14.0 cm.; Pl. 74 d (1/1).
 - 36-12-14: RW frag. bottom of jar of type A-V or VI, with turning ridges on inside; h. 11.0 + cm., diam. body 14.4 cm.; Pl. 74 d(1/2). 36-12-15: special ware: frags. of three or four two-handled oil-jars,
 - type B-LIV; two examples reconstructed(a)h. ca. 44 cm., diam. rim 8 cm., diam. neck 5.6 cm., diam. body 21.2 cm., diam. base 12.2 cm., w. with handles 28.8 cms. Pl. 74 a(1/2). b) h. ca 38 cms., diam.rim 7.4 cm., diam. neck 4.8 cm., diam. body 20.8 cm., diam. base 10.0 cm., w. with handles 27.6 cm.; Pl. 74 a(1/3).
 - 36-12-17: RW: large wine jar, broken and incomplete, type A-II b; h. 36.8 cm., diam. rim 10.8 cm., diam. short neck 9.4 cm., diam.

all drawn -

max. 26.0 cm.; Pl. 74 a(1/1).

36-12-18: RW: farag. top of large jar, type A-II b; h. 9.0 cm, diam.
rim. 11.2 cm., diam. neck 9.8 cm., diam. max. 24+ cm.

36-12-19: RW: frags. of large jar(incomplete), type A-II b; h. ca.
38 cms., diam. rim 11.2 cm., diam. max. 26 cms. Pl. 74 d(2/4);
incised potter's mark.

36-12-20: RW: five frags. from bottom of another jar of type A-II b; h. ca. 23+ cm.; potter's mark; Pl. 74 &(2/1).

36-12-21: RW beaker, almost complete, type.....; h. 12.0 cm.; diam. rim 13,6 cm., diam. base, 6.8 cms; with foot stand like a goblet; Pl. 74 d(1/3).

36-12-22: Mud ware; frags. from upper part of tub, type D-LXXI a; h. 11+ cm., diam. ca. 60 cm.; Pl. 74 d(2/2).

Alabaster2models:

MAGICAL SET: The magical set usually consists of a pesheshkaf wand and two basins, but is sometimes larger. The five pieces represented by 26-12-29, 25 and 26 certainly belong to such a magical set. Probably the other alabaster models were not included in this set. The board with emplacement for the pieces was not found and may have been of wood.

36-12-23: Alab.: small model jar of type S-V a; oval body, narrow base,

roll rim on mouth(no neck); h. 5.8 cm., diam. rim 3.0 cm.,

diam. max. 4.2 cm., diam. base 1.2 cm. ×b

36-12-24: alab.: 8 small models of basins, type S-X a(2); h. 2.2-3.1 cm.,
diam. 3.0 - 4.5; diam. base 1.5 - 2.7 cm.; Pl. 74 c (1/8, 5, 2/3,5) 3/1,2,3,5.

3/1,2,3,5).

36-12-25: alab.: 2 model basins of type S-X a(2), probably from magical set; h. 4.0 - 4.3 cm.; diam. 4.6 - 4.8 cm.; diam. base.

2.1 - 2.4; Pl. 74 d (4/2,3).

36-12-26: alab.: 2 model jarswith neck of type S-XV a(1); h. 6.1 -6.2cm. diam. rim 3.6 - 3.8 cm., diam. body 3.9 - 4.2 cm., diam. base 1.7 - 1.8 cm.; Pl. 74 c(4/5,6).

36-12-27: alab.: model of tall shoulder jar with rudimentary neck and splay foot, type S-V a-m; h. 9.0 cm., diam. rim 3.5 cm., diam. short neck 2.8 cm., diam. shoulder 3.6 cm., diam. min. 1.8 cm., diam. short neck 2.8 cm., diam. shoulder 3.6 cm., diam. min. 1.8 cm., diam. base 2.8 cm.: perhaps from magical set; Pl. MXXXXXXX diam. base 2.8 cm.; perhaps from magical set; Pl.

74 c(1/2). 36-12-28: alab.: small shallow dish with plain rim and round bottom,

type S-IX a; h. 1.8 cm., diam. ll. cm.; Pl. 74 c(1/1). 36-12-29: alab.: pesheshkaf -wand from magical set; l. 12.5 cm., w. divided top 4.8 cm., w. of butt end 2.8 cm., th. 0.7 cm;

P1. 74 c(4/5). 36-12-30: alab: model of maxe metal adze blade showing an emplacement for on one side of the butt end for attachment to the wooden handle; the other end has a well marked chisel edge; unique example, possibly from magical set: 1. 9.7 cm., w. of cutting edge 3.4 cm., w. in middle 2.6 cm., w. of butt 3.2 cm., th. of blade increases from cutting edge to 8 mm. thick; th. at emplacement of handle 6 mm.; length of emplacement 3.8 cms. Pl. 74 c (1/4).

Copper:

36-12-31: copper: model axe head, broken but complete; h. 6.6 cm., width from butt to edge 5.8 cm., th. 4 mm.; in corroded state; P1. 74 b(1/1).

36-12-32: copper: 2 model adze blades with two straight ends; 1. 6.9 cm., w. edge, 1.5 cm., w. in middle 1.2 cm., w. butt 1.25 cm.; P_1 . 74 b(1/2, 2/2).

36-12-33: copper: 2 model adze blades with bulbous butts, broken but *mcomplete; 1. 8.3 - 8.44, w. 1.5 - 1.7, cm., th. 4 mm. P1. 74 c(3/2, 4/2).

Pottery:

36-12-34: RW: model basin, type D LXXIX a; h. 2.7 cm., diam. rim 7.6 cm., diam. base 4.4 cm.;

36-12-35: mmx RW; model neckless shoulder jar, type B-LV-m; h. 6.0 cm., diam. rim 3.6 cm., diam. shoulder 6.0 cm., diam. base 3.6 cm. (splay foot).

36-12-36: RW: model collar jar, type B-LVI a(splay foot); h. 9.4 cm., diam. top 3.2 cm.; diam collar, 4.4 cm., diam. shoulder 5.0 cm., diam. base 4.0 cm.

APPENDIX B, p. 120.

Gold:

36-12-37: gold; two small scraps of gold leaf, one with traces of white plaster on back; 1.8 x 0.8 cm.; 2.0 x 1.0 cm. Secondary structures and intrusive shafts:

South of the mastabas of Dyn. IV, the ground is covered by complexes of mastabas of Dyns. V-VI, and this in fact continued along the east side of the cemetery. This field on the south of G 7560 and its chapel was covered by debris which contained remains of Ptolemaic structures as well as intrusive Ptolemaic shafts; see G 7563-7569.

In the street east of the mastaba, north of the c.b. chapel, is a long c.b. mastaba which leaves a narrow passage along the E face of G 7560. his is numbered G 7561.

mast of the c.b. chapel is the small mastaba G 7562.

he whole area immediately around the mastaba, including the c.b. chapel has been obstructed and penetrated by Ptolemaic tombs.

G 7670: name not recovered; in line 6, south of G 7660, but with its eastern face forward to the east about five meters. The rock surface slopes

See Plan & Section Lone Q.F.

See Figs....

Mastaba: Type VI a, with retaining walls of sloping blocks of num ulitic limestone. Street to a smooth sloping surface: 38.0 x 18.0 m.; area 684.0/sq.m., prop. 1/2.11; height. 3.0.m.; with interior chapel and subsidiary N niche.

CHAPEL: interior chapel of type (3 a) of white plastered c.b.; also exterior c.b. chapel.

a) Interior offering room of type (3a) of white plastered c.b., bonded with exterior c.b. chapel; compound ka-door toward s end of W wall; not decorated; 4.1 x 1.5 m., area 6.15/aq.m prop. 1/2.73 ; plain compound niche with outer niche 1.0 x 0.30 m. and inner niche 0.25 x 0.25 m.; in the outer recess was a low c.b. wall on N , S and outside on E which was 0.1 m. thick and was probably added later as an offering platform or enclosure; north of the ka-door had been a slab-table against the W. wall, a slab supported on two upright end slabs of which there remined in place the two end slabs: these of which there remined in place the two end slabs; these slabs indicated a table 1. 4 m. long(N-S) and at least 0.4 m wide(E-W); on the floor were cound two tall pottery bowlstands(type E-XXII a) broken and incomplete but probably these had stood on each side of the niche; entered by c.b. doorway in N end of E wall, opening in embrasure in c.b. wal 2.45 x 0.2 m.; the doorway has on the W a threshold slab, 0.75 x 0.57 m. and east of this three stone steps(four rises) descending through the doorway and embrasure to the floor of room b: 0.8 x 0.8 m.; height of four rises 0.43 m. from floor of room b to floor of room a; mud plastered floor in rooms a and b; in the end of the embrasure stood the lower part of another pottery bowl stand(type E-XXII a).

Exterior c.b. chapel badly destroyed by Ptolegaic intrusions and another distance proves a columned hall and indicates

evidence proves a columned hall and indicates other rooms but these coul not be accurately reconstructed.

b) columned hall symmetrically placed around doorway embrasure to room a: 10.2 x 3.9 m.; area 39.78/aq.m.; roof supported by three columns (rood?) standing in a N-S row; of these the stone bases of the two northern columns were found in place and had a diameter of 0.55 m.; thickness of N wall, 1.1 m., and E wall, 1.1 m., doorway opening northwards in W end of N wall, later block with a thin c.b. wall; another doorway opened to g, apparently in S end of N wall.

Two dressing of the mostoba: is preserved

L blocked

*

c) E of the N half of b, north of the E doorway were traces of another room which could not be measured but Extinted estimated at 3.7 x 1.8 m.; area ca. 6.66 ? sq.m.; connections not determinable.

Other rooms not determinable, if any.

Total floor area of b-c: 46.44 sq.m., minimum size.
Total floor area, a-c: 52-59 sq.m., certainly a minimum.

SUBSIDIARY N. Niche: outer recess:

DECORATION OF CHAPEL: the walls were coated with white plaster laid over mud plaster and might have borne paintings but no trace of such decoration was found.

SHAFTS in G 7670: two shafts, A, wife's shaft on N and B, man's shaft on S.

SHAFT &: wife's shaft: 1.8 x 1.8 m., - 14.4 m. in rock; lined above with massive masonry, 1. 75 m., 2 courses.

Chamber: type 4 b(1) unfinished and probably intended as a larger chamber; at the S end of the W wall an unfinished cutting to enlarge the chamber westwards; on S, 2.7 x 1.95 m. and 0.85 m. high; area 5.26 sq.m.; capacity 4.49 cu. m. Passage: 2.0 x 1.1 m. and 0.85 m. high; no trace of blocking.

No trace of coffin or burial.
No canopic pit or recess.
Completely plundered; see Diary, 1930, Dec. 29 to Jan. 8, 1931.

SHAFT B: man's shaft: 20 2.07 x 2.1 m; - 25.85 m. in rock; lined with masonry 2.8 m., 4 courses; unfinished cutting in bottom of shaft.

Chamber: at 21.87 m. in rock; type 3 bf; on S, 3.5 x 3.27 m.; and 1.95 m. high; area 11. 34 sq.m.; capacity 22.11 cu. m.

Passage: nearly as wide as shaft on shaft side, narrows southwards to chamber: 2.57 x 1.75 m. on shaft side and 1.35 m. on chamber side; height on shaft side 1.55 m. and on chamber side 1.3 m.

Blocking: the doorway was contracted by masonry built on W side of passage to a width of 0.75 m.; this masonry remained in place to a height of 0.45 m. (one course) on shaft side and 6.38 m. on chamber side. Behind the first two stones on the shaft side, the masonry was filled with small stones. This narrowed passage was certainly blocked with masonry and suggests that a coffin was placed in the chamber long before the burial. Blocked of type II b(1). If the coffin was a stone coffin and removed recently its height would have been limited to 0.9 m.

Canopic Pit: in SE corner against the rock walls: 0.5 x 0.475 m. and 0.45 m. deep; no rebate.

Flundered: pottery models in debris of chamber. [See Diary, Jan. 12 to Feb. 4, 1931.]

Objects: 31-1-896, 500: RW: model neckless shoulder jar, Type LV b-m. 8 examples: 496) h. 7.9, diam. rim 5.6; diam. max. 8.2, base 5.1 cm. 500) h. 5x8x5x6 5.3 - 6.3, diam. max. 2x2 6.3

500) h. 5x8x5x6 5.3 - 6.3, diam. max. 2x2 6.3 - 7.0, base 4.0 cm.

31-1-497: RW: 5 model collar jars, type B-LVI a-m:
h. 9.4 - 11.0 cm.: a) 9.5 cm., diam. top 4.0 cm.,
diam. collar, 4.8 cm.; diam. shoulder 5.1 cm.; diam
base 3.8.

31-1-498: RW: one model belted barrel-jar, type B-LVIII, with belt indicated by groove: h. 9.5 cm., diam.top 3.5

See of the see of the

cm., diam. rim3.8 cm., diam. max., 4.6 cm., diam. base3.4(slightly splayed), h. groove 4.9 cm. 31-1-499: RW: 2 model basins, type D-LXXIX a(2); h. 3.1 cm. diam. max. 5.2 cm., diam. base 2.8. cm.

OBJECTS FOUND IN THE DEBRIS EAST OF MASTABA:

cm., th. 12 cm.; from a carrying chair scene, front part, foot of owner and five bearers: Photo B 7612. 30-1-65, 70 to 80: Ptolemaic fragments.

√ 31-1-81: white limestone fragment of relief, colored: h. 2.5 x 8.5 x 1.6 cm.; mnexsign with part of an inscription : one sign, biw with vertical green border. Style of relief like that of Ankh-haf and merytyetes. Possibly

intrusive here from last mastaba. Pl....

31-1-82: white limestone: fragment of unfinished relief: h. 28 cm. x 15 x 21 cm.: part of a sweet come. cm. x 15 x 21 cm.; part of a swamp scene with birds. Photo B 7609.

31-1-83: alabaster boring core. / 31-1-84: white limestone painted relief, h. 12 cms x 10.7 x 4.7 from the top of a figure of woman bearing a basket probably from procession of estates. Photo B 7619.

SECONDARY

SYNCHARY STRUCTURES AND INTRUSIVE SHAFTS.

he field of small mastabas east of the field of royal mastabas continues southwards in front of G 7670 and has been overbuilt or penetrated by Ptolemaic structures or shafts as the rest of this field. All these later structures of Dyna V-VI appear to bear no connection with G 7670.

767690: south of G 7670 with the N end close to the S end of G 7670 but with its E face set forward 9.5 m. east of the face of G 7670: ends line 6 on the south: no large mastabas of earlier types east of line 6, G 7670 and G 7690, or of line 7, G 7750 and G 7760.

See Figs.... Plan only done A. F.

See Pls.....

No Name:

Mastaba: uncased core of massive blocks, type IV-iii: 52.0 x 19.25 m.: area, 1001 sq.m.: prop.1/2.7: with chapel recess, 6.4 x 7.2 m. containing a destroyed interior chapel: no trace of casing but intended to be cased with white limestone bonded with interior chapel: no subsidiary N niche but one certainly designed for casing,

Chapel: interior chapel of type (3a?), totally destroyed: exterior c.b. chapel: subsidiary N niche not constructed.

a) interior offering room destroyed except for lines of doorway: built in recess in core, which shows on N remains of the packing: the room was probably of type (3a) but may have been alternatively of type (4a): the space available indicates a chapel similar in size to those of the eight nummulitic mastabas and G 7670: entered by doorway in N end of E wall opening in embrasure in face of casing, 3.1 x 0.25 m approached by three steps (4 rises) ascending from floor of b to floor of a: the top step is wider and measures 0.55 x 0.34 m.; the three steps measure, 0.55 x 0.7 m.; height of threshold of a above floor of b, .0.45 m.

[3.1 crossed out] 2.85

Exterior c.b. chape tof four (?) rooms cut by a number of Ptolemaic burials and also badly denuded: the whole chapel measures outside, 13.1 x 4.9 m.: area. 64.19 sq.m.

APPENDIX B. p.123.

- b) Hall, symmetrically set around the embrasure to room a:

 3.1 x 3.65 m; orea 11.34 sq.m. 4.1 x 3.75 m.: area; 15.37/sq.m.: probably with roof supported by columns but no trace found: entered from N from vestibule room d, by doorway in E end of N wall: probably a doorway to c in E end of S wall, but all traces destroyed: possibly also a doorway from E.
 - c) E-W room south of b: 2.0 x 2.75 m.: area, 7.30/mq.m.: lines of doorway not found: possibly a serdab: an addition built against the S face of room b.
 - d) badly destroyed vestibule(?): room possibly 3.2 x 1.05 m. area, 3.36 sq.m.: doorway to b in S wall and doorway to e in S end of W wall: the part occupied by rooms d and e was an addition built against the N face of room b: room d was divided from e by a thinner c.b. wall built later than the main addition.
 - e) a room north of b (against the mastaba) and west of d (q.v.): 3.15 x 2.05 m.: area, 6.45 sq.m.: with doorway to d in S end of E wall: possibly a doorway from N in W end of N wall.

Total floor area of b-e, 38.42 sq.m. Total floor area, a-e, about 39-38 sq. m.

Decoration of room a of chapel G 7690:

The offering room was totally destroyed but appears to have heen of white limestone and may have been fully decorated: fragments of relief in w. lst. were found, 3 frags. in debris on E, I frag. in debris on top of mastaba, and two frags. in debris of shaft (G 7690 K, outside mastaba on S)x which may have come from this chapel:-

28-4-97: w.lst.: relief, badly worn: head of a man facing to right ax9.0 x 6.5 cm.: from a minor figure.

28-4-98: w.lst.: frag. relief: legs of two standing figures facing to left: 21 x 19 cm.

28-4-99: w.lst.: relief, badly worn: head and figure of a standing man facing to right: right arm gone: left arm hanging at side: 19 x 18 cm.

on top of mastaba:

29-3-23: w.lst. in relief: parts of two registers of a picture list of offerings with border on left side: 67.0 x 43.0 cm. and 13.0 cm. thick.

In shaft K outside mastaba on Sessuth! 28-3-98: w.lst.: relief: two fitting pieces: parts of two register s: 106 x 43-48 cm.:

1) man standing facing to left, with staff in right hand and markings handkerchief in left: full wig, broad necklace and short skirt: label in from of his face, shd hm k; Iwi: between man and staff on raised line. A naked boy holding staff with right hand, facing to left: his head is broken away: his left hand hangs open at side.
2) three men facing to left, standing: all with with full

wig, broad necklace and short skirt: each has the left hand ranging at side and right on breast holding a hankerchief(?)*

Shafts in G 7690: two shafts in meddal axis of mastaba: A wife's shaft on N and B man's shaft on S.

Shaft G 7690 A: wife's shaft: 1.79 x 1.72 m., -15.85 m. in rock: lined with massive masonry above, 0.25 m., 1 course: Chamber: type 3 af: on S: 3.4 x 3.7 m. and 1.52 m. high: area, $12.58\sqrt{\text{sq.m.}}$: capacity, $19.12\sqrt{\text{cu.m.}}$ Passage: $1.92 \times 1.25 \text{ m.}$ and 1.55-1.4 m. high: blocking not preserved. No trace og coffin or burial. No canopic pit or recess: no objects.

Position of pit B is shown an the Praced plan of this mostatus damp of dutch over it aproximately, because there is a Big damp of dutch over it.

MFA 30.206

Shoft ploan.

Portin on 1941.

Parish 1941.

APPENDIX B. p.124.

Shaft G 7690 B: man's shaft: 1.7 x 1.75 m., -13.15 m. in rock: lined above with masonry, 0.45 m., 2 courses.

Chamber: type 4 a(1): on S: 2.65 x 3.1 m. and 2.1 m. high:

area, 8.21 sq.m.: capacity, 17.24 cu.m.

Passage: 1.5 x 1.25 m.: h. of shaft side, 1.37 m. and on chamber side 2.1 m.: roof at roof level of chamber but cut in steps from bottom of shaft to floor of chamber, three rises (0.73 m. in total descent): blocked with xmasonry laid in plaster, type II b(1).

Coffin pit: sunk in floor along W side of chamber: 2.2 x 0.95 and 1.05 m. deep:

The shaft was filled with disturbed debris which had run into the chamber: this debris contained only two frags.; a piece of ivory (29-3-216) and a faience pendant (29-3-217) both of indeterminable date but intrusive.

Secondary Structures and Intrusive Shafts:

On the east the field of small mastabas extends eastwards and south-eastwards over a rock ridge considerably less in a elevation to the north: this was taken in Dyn.V-VI for small mastabas while the eastern declivity had a few small rock cut tombs: all these tombs had as usual been oevrbuilt or penetrated by tombs of the Ptolemaic-Roman Period.

The same field of small mastabas of Dyns.V-VI continued westwards across the whole southern end of Cem. # 7000 as far as left vacant and was again overbuilt with Ptolemaic intrusions.

South of the mastaba, the rock had been cut away by quarrying and on this side were eight burial shafts, mostly of type 8 (built in debris) of various dates (O'Krijand Ptolemaic) but the superstructures had been destroyed: for these shafts and mastabas G 7691-7693 see after G 7789, mss PS.I.

These large mastabas were certainly the last large mastabas built, south of line 2-7. G 7560 was the first of these and was probably not later than the end of the reign of Mycerinus. It was in its form and size closely related to the mastaba G 7550 except that the chapel was of white instead of unit with most of 670 hours a smile detribute. The type forms of the interior, the exterior chapels and nummulitic limestone. of the shafts showed a similar relation to the interior one-niched chapel was of c.b., the only stone masaba with an interior c.b. chapel recorded by our expedition. By position and the use of c.b. in the interior chapel, this mastaba is a little later than G 7560, but still of the reign of Mycerinus. G 7690 belongs to a different type and size. Unfortunately its casing was never built and its interior chapel was destroyed so that it is impossible to state whether it had a one-niched or two-niched offering room. In costruction it is to be correlated with G 5110 and G 2220 in the Western Field. Thus it is still probably of Dyn. IV but by position later than G 7670. Its size is similar to that of the large massive core mastabas, G 7650, 7530+7540, 7450 and G 7350.

Only two large mastabas were constructed in this field after the three mastabas last described. One of these is the composite mastaba G 7510 of "Prince" Khufuw haf II built immediately south of G 7130 17140 with its enlarged form built on the Wagainst the sloping mustbe of G 7140. The second mastaba is G 7152, Ptah-sekhem-ankh built on an independent site east of G 7050 and some what south of G 7150. These two are obviously of Dyn.V and will be described later.

T Cem. 7000	EN	ors. Appe	ndix	(B)	(Correc	led by	Durnd.
1 1	pages		High	area	cap.	P	Prop.
G-7210.	ר	36.0 \$ 17.0		612.0			1/2.11
G.7220.	7	36.0 X17.0		612.0			1/2.11
G.7320.	7	35.0 X16.5		577.5			12.12
G-7410.	7	35.7 X16.5		589.05			1/2.16
G-7420.	۲ _	35.7 X16.5		589.05			12.16
G-7140.	7	28.5 X 17.0		484.5			11.67
G-7340	ר	29.0 X 16.25		471.25			V1-78
G. 7410. B. Total area tow clambe	(30	26.83+15.15		4 41.98	12)		
G-7410.B. total cap.	30	96.59+25.0			121.59		
G-7130+40.B. the lined	1 38 6	2.4 X 3.15	1.9	7.56	14.36		
chamber meas	ured (
G.7110.B	15	4.5 X 5.0	3.5	22.5	78.75		
G-7210+7220	16	81. X 17.		1377. 0			14.76
		83.2 X19.35		1609.92			14.29
G.7110+7120	27	99.9 X16.5		1318,35			V4.84
0		84.2 X 22.		1852.4			V 3.82
G.7410.B,		4.95X 5.42			96.59		7 3 0 2
G-7230+7240	40	65.5 X 15.5		1015.25			14.22
G. 7230.A.	41	4.0 X 5.4	310	21.6	64.8		17-66
G. 7330+7430.B.	43	4-3 x 3.6	3 - 4	15.48	52.63		
G-7430, A.	49	4.8 X 5.16					
G-7430.B	50	4. 15 X 4.6	3.35	19.09	63.00		
G-7520+7530+7540	64	36.7 X16.25		596.37	3.73		12.26
		47-5 X16.88		801.8			12.26
G-7530 +7540	64	47.5 X16.88		801.8			12.22
		6					

G-7660.A. 96 5.15×5.3 3.88 27.3 105.92	Cem. 7000. Err	ors	Appendix ((B)	(Co	recteo	thy s	mms.)
G. 7530. A. 78 4.66X3.12 1.98 14.54 28.79 G. 7520. A. 81 4.7 X4.85 3.6 22.79 82.04 G. 7450. A 82 4.25X 5.35 2-75 22.74 62.54 G. 7450. A 82 4.25X 5.35 2-75 22.74 62.54 G. 7050. A 83 26.3 X13.25 348.47 7.244 G. 7050. A 91 3.4 X 1.15 1.16 3.91 6.13 G. 7050. A 91 3.4 X 1.15 1.16 3.91 6.13 G. 7550. B 92 4.75X 5.1 3.15 24.22 90.82 G. 7660. A 93 36.5 X18.5 6.75.25 10.5.92 12.42 10.5.92 G. 7660. A 96 5.15X 5.3 3.88 27.3 10.5.92 12.42 G. 7750. B 97 2.44 X 2.8 1.8 6.86 12.33 12.33 G. 7810. A 104 38.5 X19.5 150.15 19.79 150.15 19.79 G. 7820. L 107 43.0 X24.0 10.32 10.32 10.32	1 7 -	pages		High	area	cap.	prof.	Prop.
G-7450. G-7450. G-7450. G-7450. G-7450. B2 4-25x 5.35 2-75 2-74 G-7050. B3 55.0 x22.5 1237.5 3-15 G-7050. G-7550. G-7550. G-7550. G-7660.	G 7530.A.	78	4.66X3.12	1.98	14.54	28.79		
G. 7450. A 82 4.25x 5.35 2.75 22.14 62.54 G. 7350. 83 55.0 x22.5 1237.5 4.7050. 88 2.6.3 x13.25 3.48.47 4.7550. B. 92 4.75x 5.1 3.15 3.15 4.7550. B. 92 4.75x 5.1 3.15 3.15 4.7550. B. 93 36.5 x18.5 4.7550. A. 96 5.15x 5.3 3.88 2.73 105.92 4.7750. 97 36.0 x18.5 6.7750. B. clamberti 99 2.44x 2.8 6.7750. A. 99 2.44x 2.8 6.7810. A 104 38.5 x19.5 150.75 6.7810. A 104 3.9 x 4.65 1032. 9.7050. B 114 4.75x 3.7 105.75 107 43.0 x24.0 108 3.65 x3.45 108 3.65 x3.	G 7520. A.	81	4-7 X4-85			82.04		
G.7450. A G.7350. G.7050. 83 55.0 X22.5 1237.6 1237.6 1	G-7450.	82	50.8 X18.0		914.4			V2.82
G. 7350. G. 7050. 88 26.3 X13.25 348.47 V1. 98 G. 7550. A G. 7550. B G. 7550. B G. 7660. G. 7660.	G-7450. A	82	4-25X 5.35			62.54		12.02
G. 7050. G. 7550. A G. 7550. A G. 7550. B G. 7660. G. 7750. G. 775	G-7350.	83	55.0 X22.5				p.:	1/2 //1
G. 7550. A 91 3.4 X 1.15 1.5 3.91 6.13 G. 7550. B. 92 4.75 X 5.1 3.15 24.22 90.82 G. 7660. 93 36.5 X 18.5 675.25 meaning. G. 7660. A. 96 5.15 X 5.3 3.88 27.3 105.92 G. 7750. 97 36.0 X 18.5 624.5 G. 7750. B. efamber II 99 2.44 X 2.8 1.8 6.86 12.33 G. 7850. A. 99 2.65 X 2.45 3.05 6.49 19.79 G. 7810. A 106 3.9 X 4.65 2.5 18.13 45.32 G. 7820. 107 43.0 X 24.0 G. 700. B 112 4.75 X 3.7 2.0 17.58 35.16 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59	G-7050.	8 8	26.3 X13.25					
G. 7550. B. 92 4.75 X 5.1 3.15 24.27 90.82 G. 7660. 93 36.5 X 18.5 675.25 means mouth. G. 7660. 94 36.5 X 18.5 675.25 means mouth. G. 7660. 97 36.0 X 18.5 624.5 G. 7750. 97 36.0 X 18.5 624.5 G. 7750. B. clamber 99 2.44 X 2.8 1.8 6.86 12.33 G. 7850. A. 99 2.65 X 2.45 3.05 6.49 19.79 G. 7810. A 106 3.9 X 4.65 2.5 18.13 45.32 G. 7820. 107 43.0 X 24.0 10.32. 10.32. G. 7820. 107 43.0 X 24.0 10.58 35.16 G. 700. B 114 4.75 X 3.7 2.0 17.58 35.16 G. 700. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 7560. B 118 3.65 X 3.45 2.82 12.84 37.62 -3.6 5.87	G.7550.A	91		1175		6.13		71, 10
G. 7660. G. 7660. G. 7660. G. 7660. G. 7660. G. 7660. G. 7750. G. 7810. G. 7810. G. 7810. G. 7810. G. 7820. G. 782	G. 7550.B.	92		3.15				
G. 7750. G. 7810. G. 7810. G. 7810. G. 7820. G. 782				3.15	24.22		rell's	
G. 7 6 60. A. 96 5.15 x 5.3 3.88 27.3 105.92 G. 7750. 97 36.0 x 18.5 624.5 666. G. 7750. B. clamber 11 99 2.44 x 2.8 1.8 6.86 12.33 G. 7810. A. 99 2.65 x 2.45 3.05 6.49 19.79 G. 7810. A 106 3.9 x 4.65 2.5 18.13 45.32 G. 7820. 107 43.0 x 24.0 1032. G. 70 60. B 112 4.75 x 3.7 2.0 17.58 35.16 G. 7 5 60. B 114 4.55 x 4.15 2.15 18.88 40.59 G. 7 5 60. B 118 3.65 x 3.45 (2.82 12.84 37.62 3.05 5.87)	**	93	36.5 X18.5		675.25	- mana-	1	X1.97)
G. 7750. B. clamber II 99 G. 7810. A. 99 G. 7810. 104 38.5 X19.5 G. 7810. A. 106 3.9 X 4.65 2.5 18.13 45.32 Y1.97 G. 7820. 107 43.0 X24.0 G. 7060. B. 112 4.75 X 3.7 G. 7070. B. 114 4.55 X 4.15 2.15 18.88 4.0.59 G. 7560. B. 118 3.65 X 3.45 2.82 12.84 37.62		96		3.88	27.3	105.92	lest ale	
G. 7750. B. clamber II 99 2.44 X 2.8 1.8 6.86 12.33 G. 7850. A. 99 2.65 X 2.45 3.05 6.49 19.79 G. 7810. A 104 38.5 X 19.5 750.75 V 1.97 G. 7810. A 106 3.9 X 4.65 2.5 18.13 45.32 G. 7820. 107 43.0 X 24.0 1032. V 1.79 G. 7060. B 112 4.75 X 3.7 2.0 17.58 35.16 G. 7070. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 7560. B 118 3.65 X 3.45 2.82 12.84 37.62 -3.6 3.05 5.87			37.0 X18.5		684.5			1/2.0
G. 7810. G. 7810. G. 7810. A 106 3.9 X 4.65 2.5 18.13 45.32 G. 7820. 107 43.0 X24.0 1032. Y1.79 G. 7060. B 112 4.75 X 3.7 2.0 17.58 35.16 G. 7070. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 7560. B 3.65 X 3.45 (2.82 12.84 37.62 30.65) - 3.6 (3.05) - 3.6 (3.05) - 3.6		erli 99	2,44 X 2,8	1.8	6.86	12.33		
G. 7810. A 106 3.9 X 4.65 2.5 18.13 45.32 71.97 G. 7820. 107 43.0 X24.0 1032. 71.99 G. 7060. B 112 4.75 X 3.7 2.0 17.58 35.16 G. 7070. B 114 4.55 X 4.15 2.15 18.88 40.59 G. 7560. B (118 3.65 X 3.45 2.82 12.84 37.62	G-7750. A.	99	2.65 X 2.45	3.05	6.49	19.79		
G. 7810. A G. 7820. G. 7820. G. 7060. B H. 75x 3.7 G. 7070. B H. 55x4.15 G. 7560. B H. 55x4.15 G. 7560. B H. 55x4.15 G. 7560. B H. 55x4.15 J. 82 J. 82 J. 84 J. 65 J. 82 J. 62 J. 65 J. 6	G. 7810.	104	38.5 X19.5		750.75			V 1.97
G. 7820. 107 43.0 X24.0 1032.	G-7810.A	106	3.9 X 4.65	2.5	18.13	45.32		
$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	G. 7820.	107						V 1.70
G-7070.B 114 4.55 x 4.15 2.15 18.88 40.59 G-7560.B 118 3.65 x 3.45 (2.82 12.84 37.62 3.05 5.87	G. 7060. B	112				35.14		
G. 7 5 60 · B {118 3 · 65 × 3 · 45 { 2 · 82 12 · 84 37 · 62 } - 3 · 6 { 5 · 87 }	G-7070.B	114						
3.05								
		}		3.05	1 2184	31.62		
	G. 7670.A	121				4.47		
			81				2	
			R					
		, ,					,	
				1				

Cem. 7000 AT	endi	V(B) (COV	ecled	-by Di	my.)	All of the second
	pages		High	area	cap.		Prop.
G. I. b. chapel	4	10.5 X 2.05		21.52		V-5-12	15.12
G.7120, room. C	8	2.5 X 4.25		10.62			
G-7210. , .d.	18	2.1 X 1.5		3.15			
G. 7210. Total Floor	18	22-18+2-28+3-15	ſ	500			
area b-G	1	+ 6.86+3.06+1.92	-	39.45			
G.7210. total area	(18	6.88+39.45	`	46.33			
Floor a and b	<u>a)</u>						
G-7420. Chapel 2	27	4·25×1·55		6.58			12.74
G. 7650. room. b.	58	4.0 X 3.5		14.0			
G-7530+7540clap	64	4.75x 1.5		7.12			V 3.16
G. 7530. room. b.	67	5.5 X 2.4	2.18	-	30.1		V2-29
G. 7530. room. C	67	2·55X4·65		11.86	24.31		2-29
GX 47 \$ 504 X X X X X X X X X X X X X X X X X X X	XXXXX		Contract Con			·~~~	OCIONALINA.
G-7210.b.			***		~~~~~~	, X 	XXXXXXXXXX
	18	1.9 X 1.75		3.32			
G. 7350. C Chamber I	\	2.62 X 1.4	1.62	3.67	3.74		
G - 7350.0 = II	87	2-4 X3.1	1.5	7,44	11.16		
G-7760.X	103	2-5 X2.16	1.1	5,4	5.94		
G. 7350. chap.	84	4.25 X 1.45		6.16			1/2.93
G-7550. =	90	4.7 X 1.6		7.52			12.93
G. 7660. room.b	94	5.75 X7.95		45.71			
G. 7660. total area	(94	45.71+5.04	(
. rooms b. E	}	8.68+3.27	1	627			- /-
G. 7660. total area	94	6.17 +45.71+	(\	381 - 6		
rooms. a. E		5.04+ 8.68). ()			
G1 / 8 / 10 / 100/		+ 3.27=		68.87			
G.7810 room. b	104	4.45X2.3		10.24			
G-7810 room. 2.b	104	6.3+10.24		16.54			
G-7560 Chap.	116	4.4 X 1.55		6-82			¥2.83
G. 7560, roomie	W 12 W	2.6 X 1.55		4.03			
G-7560.total.fl	1166	29.4+4.03+8.32		46.56	,	,	
(b-e) G. 7560, total a-e	1		1	5330			
4.7560. total a_P) [6.82+46.56=		53.38		1 2 1	

Heights of mastabas 7110-4.32~ These notes were written 7120 - 5.18-4 on the back of the index 7130 - 6.61 page. 7210-4.274 7220 - 5.40 V 7230 - 5.25 7310-5.32~ 7320 - 5.45-7330 - 385/ 7410-5.00-V 7420-6.000 7430-4.70 7440-5.950 7140-5.18-1 7240-5.952 7340-5.702 7760-8.05 7070 - 5.40-7670 - 3.90 7510 -8.100 7560 - 383-7650-6.30-1 7750-5.80 7350 - 5.20 - average 7450 - 5.80 7660-5.20r 7810-5.38 7820-6.10 7060 - 4.40

Pages 1-124 Pages 1-124

Illustrations ready for the print:

Big mostoles:

G. 7690 - Plean only (not yet finished points of the pits ment of the pits ment

7210+20-11 "

{7310+20}-Plan & section (one sheet)

7130+40 - " "

7230 +40 - " "

7520+30+40-11 "

7450 - Peon a section

7350 - Plan only

7750 - Plan & section

7760 - "

7810 -- Plan only

7800 - Plan & Section

7820 - 12011 2 11

7070 - " "

"

7560 - "

7670 - "