


Exhibit A

# Fast Start vs Full Launch

***Fast Start path utilizes existing mobile fixtures with a Sprint branded space for launch beginning (April 10).***



***Full SWAS model complete with co-branded signage and full launch support systems in ~1500 stores.***






©2014 Sprint. This information is subject to Sprint policies regarding use and is the property of Sprint and/or its relevant affiliates and may contain restricted, confidential or privileged materials intended for the sole use of the intended recipient. Any review, use, distribution or disclosure is prohibited without authorization.


# Exterior Branding

- Sprint and Radio Shack brand signs will be on the front of the store  
Pending branding approval from both companies




# Proposed layouts





- ① INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND 554862-1 TRANSITION BLOCK FOR UNDER CARPET POWER WIRING CONNECTION. PROVIDE WIRING AND (3) 20 AMP CIRCUITS FOR TRANSITION TO UNDER CARPET WIRING. CUT BOTTOM TRACK BELOW WALL BOX FOR FLATWIRE INTO SALES AREA
- ② INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND #2111682-1 TRANSITION BLOCK FOR DATA CABLING. PROVIDE 1" CONDUIT WITH PULL STRING STUBBED TO ACCESSIBLE CEILING SPACE FROM TRANSITION BOX FOR DATA CABLING. TERMINATE WITH BUSHINGS.
- ③ UNDER CARPET FLATWIRE LOCATION FOR DIMENSIONAL REFERENCE ONLY.
- ④ INSTALL "AMP" #554181-1 (5) CONDUCTOR WHIP KIT FOR FIXTURE POWER. TWO CIRCUITS TO QUADPLEX AT POS AND ONE CIRCUIT FOR OEM TABLES
- ⑤ DIMENSIONS FOR FLATWIRE DATA TERMINATION POINTS ARE APPROXIMATE AND SHALL BE FIELD VERIFIED TO COORDINATE WITH SPRINT FIXTURE AND CARPET SEAM LOCATIONS. PROVIDE 3'-0" OF EXCESS CABLE EXTENDED FROM NEAREST CARPET SEAM, INSTALL SPRINT FIXTURE. CUT A SLIT IN CARPET FOR CABLE UNDER FIXTURE AS REQUIRED, RE-INSTALL CARPET, WIRE CABLE INTO TERMINATION BOX, AND MOUNT IN SPRINT FIXTURE WITH DOUBLE-SIDED TAPE OR HOOK AND LOOP STRIP. PROVIDE (2) DATA JACKS MOUNTED IN (1) #1479489-3 TWO PORT FITTING.
- ⑥ QUADPLEX OUTLETS. PROVIDE (1) SINGLE 20 AMP CIRCUIT TO POWER ALL.
- ⑦ INSTALL NEW CARPET, SUPPLIED BY OWNER, IN AREA SHOWN. PROVIDE JOHNSONITE LS-48-F, UNDER-CARPET LEVELER SYSTEM, AND JOHNSONITE 4" WALL BASE COLOR: #63 BURNT UMBER
- ⑧ PAINT (BENJAMIN MOORE, AURA WATERBORNE INTERIOR, SATIN [526], WINTER GATES, AC-30) EXISTING WALL TO WIDTH INDICATED. TAPE-OFF EDGE. ASSUME 10' CEILING HEIGHT.
- ⑨ HANDSET DISPLAY FIXTURE. PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑩ POINT OF SALES COUNTER. PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑪ HANDSET TABLE. PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑫ SECURITY CAMERA PROVIDED AND INSTALLED BY OTHERS. PROVIDE MINIMUM OF 130' OF CABLE W/ 15' COILED ON END CLOSEST TO CAMERA AND REMAINDER COILED AT OTHER END BY TERMINATION POINT TO BE DETERMINED. SECOND CAMERA LOCATION TO BE DETERMINED IN BACK OF HOUSE. PROVIDE MINIMUM OF 50' OF CABLE. ALSO PROVIDE SURFACE-MOUNTED DUPLEX OUTLET ON A NEW 20 AMP CIRCUIT. DATA OUTLET, MINIMUM OF 50' OF CABLE FROM DVR TO MAIN SWITCH AND 12" X 18" LAMINATE SHELF WITH WALL BRACKETS AT LOCATION TO BE DETERMINED IN BACK OF HOUSE.
- ⑬ PROVIDE DUPLEX OUTLET AT SAFE. LOCATION TO BE FIELD DETERMINED. SAFE BY OTHERS. CIRCUIT TO EXISTING OUTLETS.




**RMTA**  
 908 BROADWAY 6TH FLOOR  
 KANSAS CITY MISSOURI 64105  
 816 842 1232 F 816 842 1078

PROJECT  
**STORE WITHIN A STORE**  
 RADIOSHACK



SCALE 1/4" = 1'-0"  
 OPTION 01 (432 SQ. FT.)

PROJECT NUMBER 2015015.001	© 2015 Mass Wireless Enterprise LLC All rights reserved. No part of this document may be reproduced or utilized in any form without the prior written consent of Mass Wireless Enterprise LLC.
DESIGNER R. BURDINE	SHEET NUMBER <b>A01</b>
DATE MARCH 11, 2015	RMTA, BIZ



- ① INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND 554862-1 TRANSITION BLOCK FOR UNDER CARPET POWER WIRING CONNECTION. PROVIDE WIRING AND (2) 20 AMP CIRCUITS FOR TRANSITION TO UNDER CARPET WIRING. CUT BOTTOM TRACK BELOW WALL BOX FOR FLATWIRE INTO SALES AREA
- ② INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND #2111682-1 TRANSITION BLOCK FOR VOICE/DATA CABLING. PROVIDE 1" CONDUIT WITH PULL STRING STUBBED TO ACCESSIBLE CEILING SPACE FROM TRANSITION BOX FOR VOICE/DATA CABLING. TERMINATE WITH BUSHINGS.
- ③ UNDER CARPET FLATWIRE LOCATION FOR DIMENSIONAL REFERENCE ONLY.
- ④ INSTALL "AMP" #554181-1 (S) CONDUCTOR WHIP KIT FOR FIXTURE POWER. TWO CIRCUITS TO QUADPLEX AT POS
- ⑤ DIMENSIONS FOR FLATWIRE DATA TERMINATION POINTS ARE APPROXIMATE AND SHALL BE FIELD VERIFIED TO COORDINATE WITH SPRINT FIXTURE AND CARPET SEAM LOCATIONS. PROVIDE 3'-0" OF EXCESS CABLE EXTENDED FROM NEAREST CARPET SEAM. INSTALL SPRINT FIXTURE. CUT A SLIT IN CARPET FOR CABLE UNDER FIXTURE AS REQUIRED. RE-INSTALL CARPET. WIRE CABLE INTO TERMINATION BOX, AND MOUNT IN SPRINT FIXTURE WITH DOUBLE-SIDED TAPE OR HOOK AND LOOP STRIP. PROVIDE (2) DATA JACKS MOUNTED IN (1) #1479489-3 TWO PORT FITTING.
- ⑥ QUADPLEX OUTLETS. PROVIDE (1) SINGLE 20 AMP CIRCUIT TO POWER ALL.
- ⑦ INSTALL NEW CARPET, SUPPLIED BY OWNER, IN AREA SHOWN. PROVIDE JOHNSONITE LS-40-F, UNDER-CARPET LEVELER SYSTEM, AND JOHNSONITE 4" WALL BASE COLOR: #63 BURNT UMBER
- ⑧ PAINT (BENJAMIN MOORE, AURA WATERBORNE INTERIOR, SATIN (526), WINTER GATES, AC-30) EXISTING WALL TO WIDTH INDICATED. TAPE-OFF EDGE. ASSUME 10' CEILING HEIGHT.
- ⑨ HANDSET DISPLAY FIXTURE, PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑩ POINT OF SALES COUNTER, PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑪ NOT USED
- ⑫ SECURITY CAMERA PROVIDED AND INSTALLED BY OTHERS. PROVIDE MINIMUM OF 130' OF CABLE W/ 15' COILED ON END CLOSEST TO CAMERA AND REMAINDER COILED AT OTHER END BY TERMINATION POINT TO BE DETERMINED. SECOND CAMERA LOCATION TO BE DETERMINED IN BACK OF HOUSE. PROVIDE MINIMUM OF 50' OF CABLE. ALSO PROVIDE SURFACE-MOUNTED DUPLEX OUTLET ON A NEW 20 AMP CIRCUIT, DATA OUTLET, MINIMUM OF 50' OF CABLE FROM DVR TO MAIN SWITCH AND 12" X 18" LAMINATE SHELF WITH WALL BRACKETS AT LOCATION TO BE DETERMINED IN BACK OF HOUSE.
- ⑬ PROVIDE DUPLEX OUTLET AT SAFE, LOCATION TO BE FIELD DETERMINED. SAFE BY OTHERS. CIRCUIT TO EXISTING OUTLETS.


**RMTA**  
 908 BROADWAY 6TH FLOOR  
 KANSAS CITY MISSOURI 64005  
 816 842 1292 F 816 842 1878

PROJECT  
**STORE WITHIN A STORE**  
 RADIOSHACK



SCALE 1/4" = 1'-0"  
 OPTION 02 (324 SQ. FT.)

PROJECT NUMBER: 2015015.001	© 2015 Sprint Nextel. All rights reserved. This document is the property of Sprint Nextel. All other trademarks are the property of their respective owners.
SHEET NUMBER: R. BURDINE	SHEET NUMBER: <b>A02</b>
DATE: MARCH 11, 2015	RMTA/BIZ



- ① INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND #54862-1 TRANSITION BLOCK FOR UNDER CARPET POWER WIRING CONNECTION. PROVIDE WIRING AND (3) 20 AMP CIRCUITS FOR TRANSITION TO UNDER CARPET WIRING. CUT BOTTOM TRACK BELOW WALL BOX FOR FLATWIRE INTO SALES AREA
- ② INSTALL "AMP" #554805 RECESSED WALL BOX AT 10" AFF WITH #553292-1 (GREY) COVER PLATE AND #2111682-1 TRANSITION BLOCK FOR DATA CABLING. PROVIDE CATEGORY 5e CABLE TERMINATED ON "AMP" #406372-6 RJ-45 FOR EACH DATA AT SWITCH. LABEL ALL CABLES AND OUTLETS
- ③ UNDER CARPET FLATWIRE LOCATION FOR DIMENSIONAL REFERENCE ONLY
- ④ INSTALL "AMP" #554181-1 (5) CONDUCTOR WHIP KIT FOR FIXTURE POWER. TWO CIRCUITS TO QUADPLEX AT POS AND ONE CIRCUIT FOR OEM TABLES
- ⑤ DIMENSIONS FOR FLATWIRE DATA TERMINATION POINTS ARE APPROXIMATE AND SHALL BE FIELD VERIFIED TO COORDINATE WITH SPRINT FIXTURE AND CARPET SEAM LOCATIONS. PROVIDE 3'-0" OF EXCESS CABLE EXTENDED FROM NEAREST CARPET SEAM, INSTALL SPRINT FIXTURE, CUT A SLIT IN CARPET FOR CABLE UNDER FIXTURE AS REQUIRED. RE-INSTALL CARPET, WIRE CABLE INTO TERMINATION BOX, AND MOUNT IN SPRINT FIXTURE WITH DOUBLE-SIDED TAPE OR HOOK AND LOOP STRIP. PROVIDE (2) DATA JACKS MOUNTED IN (1) #1479489-3 TWO PORT FITTING.
- ⑥ QUADPLEX OUTLETS. PROVIDE (1) SINGLE 20 AMP CIRCUIT TO POWER ALL.
- ⑦ INSTALL NEW CARPET, SUPPLIED BY OWNER, IN AREA SHOWN. PROVIDE JOHNSONITE LS-40-F, UNDER-CARPET LEVELER SYSTEM, AND JOHNSONITE 4" WALL BASE COLOR: #63 BURNT UMBER
- ⑧ PAINT (BENJAMIN MOORE, AURA WATERBORNE INTERIOR, SATIN (526), WINTER GATES, AC-30) EXISTING WALL TO WIDTH INDICATED. TAPE-OFF EDGE. ASSUME 10' CEILING HEIGHT.
- ⑨ HANDSET DISPLAY FIXTURE, PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑩ POINT OF SALES COUNTER, PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑪ HANDSET TABLE, PROVIDED BY FIXTURE MANUFACTURER, ASSEMBLED AND INSTALLED BY GENERAL CONTRACTOR. RE: MANUFACTURER'S INSTRUCTIONS
- ⑫ SECURITY CAMERA PROVIDED AND INSTALLED BY OTHERS. PROVIDE MINIMUM OF 130' OF CABLE W/ 15' COILED ON END CLOSEST TO CAMERA AND REMAINDER COILED AT OTHER END BY TERMINATION POINT TO BE DETERMINED. SECOND CAMERA LOCATION TO BE DETERMINED IN BACK OF HOUSE. PROVIDE MINIMUM OF 50' OF CABLE. ALSO PROVIDE SURFACE-MOUNTED DUPLEX OUTLET ON A NEW 20 AMP CIRCUIT, DATA OUTLET, MINIMUM OF 50' OF CABLE FROM DVR TO MAIN SWITCH AND 12" X 18" LAMINATE SHELF WITH WALL BRACKETS AT LOCATION TO BE DETERMINED IN BACK OF HOUSE.
- ⑬ PROVIDE DUPLEX OUTLET AT SAFE, LOCATION TO BE FIELD DETERMINED. SAFE BY OTHERS. CIRCUIT TO EXISTING OUTLETS.

<b>RMTA</b>	905 BROADWAY 6TH FLOOR KANSAS CITY MISSOURI 64105 816 842 1292 F 816 842 1878	<b>PROJECT</b> <b>STORE WITHIN A STORE</b>	<b>Sprint</b>	PROJECT NUMBER: 2015075.001	© 2015 Sprint Nextel Intellectual Property Corporation LLC All rights reserved. No part of this document may be reproduced or copied in any form without the prior written authorization of Sprint Nextel Intellectual Property Corporation LLC.
		<b>RADIO SHACK</b>		SCALE 1/4" = 1'-0"	SHEET NUMBER: R. BURDINE

OPTION 03 (360 SQ. FT.)

- SYMBOLS LEGEND**
- ⊠ DATA/VOICE WALL BOX
  - ⊕ DUPLEX ELECTRICAL OUTLET
  - ⊕ 4-PLEX ELECTRICAL OUTLET
  - FLAT WIRE WALL TRANSITION BOX
  - ⊠ FLAT WIRE FLOOR DATA TRANSITION
  - ⊠ FLAT WIRE FLOOR POWER TRANSITION
  - Ⓞ CAMERA LOCATION (BY SPRINT VENDOR)

**RADIO SHACK (LANDLORD) SCOPE OF DEMOLITION WORK**

1. REMOVE ALL FLOOR DISPLAY FIXTURES
2. REMOVE ALL WALL DISPLAY FIXTURES
3. REMOVE ALL WALL GRAPHICS, POSTERS AND PROMOTIONAL DISPLAY ITEMS
4. REMOVE ALL CEILING HUNG PROMOTIONAL ITEMS
5. ALL DAMAGED OR DIRTY CEILING TILES TO BE REPLACED
6. ALL LIGHT FIXTURES TO BE IN WORKING ORDER AND RE-LAMPED AS REQUIRED.
7. ALL DAMAGED OR DIRTY HVAC DIFFUSERS TO BE CLEANED OR REPLACED.

**SPRINT GC SCOPE OF DEMOLITION WORK**


8. REMOVE ALL FLOORING MATERIALS (INCLUDING BUT NOT LIMITED TO: CARPET, VINYL FLOORING, WOOD FLOORING, CERAMIC TILE)
9. REMOVE ALL WALL SURFACE MOUNT BLOCKING, BASE AND COVE MATERIALS (INCLUDING BUT NOT LIMITED TO: VINYL/RUBBER BASE, WOOD OR TILE BASE)
10. FLOOR TO BE CLEAN, FULLY PREPARED AND READY TO INSTALL CARPET- INCLUDING REMOVAL OF ALL ADHESIVES AND REPAIR OF SUBFLOOR IMPERFECTIONS CAUSED BY FLOORING REMOVAL.
11. ALL DAMAGE TO WALLS TO BE COMPLETELY REPAIRED, PATCHED AND PRIMED READY FOR PAINT.
12. IF APPLICABLE REMOVE ALL SURFACE MOUNT WALL OR IN FLOOR ELECTRICAL (FLOOR BOXES AND CONDUIT) AND REPAIR FLOOR SURFACE TO BE READY FOR CARPET INSTALLATION.

\* NOTES APPLY TO AREA OF WORK ONLY

**CONTACT INFORMATION**


**UNDERCARPET FLAT WIRE:**

BILL NEUSTADT - ELECTRONICS SUPPLY COMPANY  
PH. 336-727-5824



1/8" = 1'-0"

**PARTIAL RELECTED CEILING PLAN**



<b>RMTA</b>	905 BROADWAY 6TH FLOOR KANSAS CITY MISSOURI 64105 816 842 1292 F 816 842 1878	<b>PROJECT</b> <b>STORE WITHIN A STORE</b>		PROJECT NUMBER 2015015.001	© 2015 Radio Shack Telecommunications LLC. All other trademarks are the property of their respective owners. All other trademarks are the property of their respective owners.
	RADIO SHACK	SHEET NUMBER <b>A04</b>		DATE MARCH 11, 2015	RMTA/BIZ

DEMOLITION NOTES, GENERAL NOTES, AND PARTIAL RCP