(1) SCREWS AS REQUIRED, TO TOP AND
BOTTOM FLANGE AT EACH JOIST

LONG LEG OF RIM MUST BE
POSITIONED ON TOP OF JOIST
FOR PROPER TAB ALIGNMENT

SCREWS AS REQ'D THROUGH
RIM AT EACH JOIST LOCATION

ClarkDietrich BUILDING SYSTEMS
TradeReady® RIM TRACK
SECURED PER JOIST END
BEARING CONDITION DETAIL

ClarkDietrich BUILDING SYSTEMS
TradeReady® JOIST PER PLAN

ClarkDietrich BUILDING SYSTEMS
TradeReady® RIM TRACK,
PER PLAN 16ga.(MIN)

SCREWS AS REQ'D THROUGH
TAB TO EACH JOIST

3-1/2"(MIN)
BEARING

BEARING SUPPORT
BY OTHERS

(3) SCREWS AS REQUIRED, THROUGH
TAB TO EACH JOIST

F1221 INT. JOIST BEARING – RIM-TO-RIM
ClarkDietrich TradeReady Floor Joist System