
WESTMINSTER ABBEY



The organ was built by Harrison & Harrison in 1937, with four manuals and 84 speaking stops, and was used for the first time at the Coronation of King George VI. Some pipework from the previous five-manual Hill organ was revoiced and incorporated in the new scheme.



Photographs by CRA Davies

The two organ cases, designed in the late nineteenth century by J.L. Pearson, were reinstated and coloured in 1959 under the direction of Stephen Dykes Bower. The north case contains the Choir Organ and Pedal Open Diapason; the south case contains the Great Organ and the other screen Pedal stops. The Swell and Solo Organs are in the south triforium; the console is placed centrally on the east side of the screen.

In 1982 and 1987 the organ was restored and enlarged. Additions included the unenclosed Choir Organ, and the console was rebuilt with a fifth manual for the Bombarde Organ. The primary purpose of this department is to give the organ an extra dimension for great occasions, especially when there is a large congregation in the nave. The Bombarde flue chorus is placed in the north triforium immediately above the organ case; the three reeds, which are celebratory trumpets on ten-inch wind pressure, are placed one bay further west.

WESTMINSTER ABBEY

PEDAL ORGAN		GREAT ORGAN		SOLO ORGAN (81-96 enclosed)
On the screen		45. Double Geigen	16	81. Contre Viole 16
1. Open Diapason	16	46. Bourdon	16	82. Viole d'Orchestre 8
2. Geigen (from 45)	16	47. Open Diapason I	8	83. Viole Céleste 8
3. Bourdon (from 46)	16	48. Open Diapason II	8	84. Viole Octaviante 4
* 4. Principal	8	49. Geigen	8	85. Cornet de Violes 10.12.15 III
5. Octave Geigen (from 45)	8	50. Hohl Flute	8	86. Harmonic Flute 8
6. Bass Flute (from 46)	8	* 51. Stopped Diapason	8	87. Concert Flute 4
* 7. Fifteenth	4	52. Octave	4	88. Harmonic Piccolo 2
* 8. Rohr Flute	4	53. Geigen Principal	4	89. Double Clarinet (from 90) 16
* 9. Open Flute	2	* 54. Wald Flute	4	90. Clarinet 8
10. Mixture 19.22.26.29	IV	55. Octave Quint	$2^{2}/_{3}$	91. Cor Anglais 8
11. Contra Posaune (from 60)	16	56. Super Octave	2	92. Orchestral Hautboy 8
12. Posaune (from 61)	8	57. Mixture 15.19.22.26.29	V	XX Tremulant
13. Octave Posaune (from 62)	4	* 58. Sharp Mixture 29.33.36	III	93. Contra Tuba (from 94) 16
		59. Harmonics 17.19.21.22	IV	94. Tuba 8
In the triforium		60. Contra Posaune	16	95. Orchestral Trumpet 8
14. Double Open Wood (from 16)) 32	61. Posaune	8	96. French Horn 8
15. Open Wood I	16	62. Octave Posaune	4	97. Tuba Mirabilis 8
16. Open Wood II	16			
†17. Violone (from 98) 16 XIII Choir to Great XIV Swell to Great XV Solo to Great XVI Bombarde to Great				XXI Lower Choir on Solo (rocking tablet)
18. Viole (from 81)	16	III Solo lo Great IIII Bomourue i	o Great	XXII Octave XXIII Sub Octave XXIV Unison Off XXV Bombarde to Solo
19. Double Ophicleide (from 20)	32			AAIV Unison Ojj AAV Bomourue to Soto
20. Ophicleide	16			
21. Tuba (from 93)	16			DOMBARDE ORGANI
22. Clarinet (from 89)	16			BOMBARDE ORGAN
*23. Trumpet	8	SWELL ORGAN		† 98. Violone 16
*24. Clarion (from 23)	4	63. Quintaton	16	* 99. Open Diapason 8
I Choir to Pedal II Choir Octave to Pe	edal	64. Open Diapason	8	*100. Principal 4
III Great to Pedal IV Swell to Pedal		65. Lieblich Gedeckt	8	*101. Fifteenth 2
V Solo to Pedal VI Bombarde to Pe	edal	66. Viole d'Amour	8	*102. Mixture 19.22.26.29 IV-VI
		67. Salicional	8	*103. Grand Cornet 1.8.12.15.17 III-V
CHOIR ORGAN		68. Vox Angelica (tenor c)	8	*104. Bombarde 16
		69. Principal	4	*105. Trumpet 8
Upper Division (enclosed)	0	70. Lieblich Flute	4	*106. Clarion 4
25. Claribel Flute	8	† 71. Harmonic Flute	4	107. Contra Posaune (from 60) 16
26. Stopped Flute	8	† 72. Twelfth	$2^{2}/_{3}$	108. Posaune (from 61) 8
27. Viola da Gamba	8	73. Fifteenth	2	109. Octave Posaune (from 62) 4
28. Gemshorn	4	74. Mixture 15.19.22.26.29	V	110. Tuba Mirabilis (from 97) 8
29. Flauto Traverso	4	75. Contra Oboe	16	XXVI Bombarde Chorus (98-103) on Great
30. Nason	4	76. Oboe	8	AAVI Bomourue Chorus (90-103) on Great
31. Gemshorn Fifteenth	2	* 77. Vox Humana	8	
32. Mixture 19.22	II	XVI Tremulant		A CCTOS OPYTO
33. Cornopean	8	78. Double Trumpet	16	ACCESSORIES (2019)
VII Upper Choir on Swell (rocking tal	blet)	79. Trumpet	8	Additional couplers (rocking tablets):
Lower Division (unenclosed)		80. Clarion	4	Manuals I and II Exchange
34. Bourdon (prepared for)	16			Upper Choir shutters on Swell
35. Open Diapason	8	XVII Octave XVIII Sub Octo XIX Unison off XX Solo to Swe		Great and Pedal combinations coupled
*36. Rohr Flute	8	AIA Chison ojj AA Solo lo Swe		Pedal to Swell pistons (with separate Pedal combinations)
*37. Principal	4			Generals on Swell foot pistons
*38. Open Flute	4			Ten foot pistons to the Pedal Organ
*39. Nazard	$2^{2}/_{3}$	999 general and 16 divisiona	ıl	Ten pistons to the Choir Organ
*40. Fifteenth	2 /3	piston memories		Ten pistons to the Great Organ
*40. Fineenth 2				Ten pistons to the Swell Organ
12.		atia	(duplicated by foot pistons) Ten pistons to the Solo organ	
*43. Mixture 22.26.29.33		The actions are electro-pneumatic		Six pistons to the Bombarde Organ
*44. Cremona	8			Ten general pistons and general cancel
		The manual compass is 61 notes;		Stepper, operating general pistons in sequence Reversible pistons: <i>I, III-VI, X, XI, XIII-XVI, XX</i> ; 14, 19
VIII Lower Choir on Great (rocking tablet) VIIIa Lower Choir on Solo (rocking tablet)		the pedal compass is 32 notes		Reversible foot pistons: <i>III-VI</i> , <i>X</i> , <i>XI</i> , <i>XIII-XVI</i> , <i>XX</i> ; 14, 19 Reversible foot pistons: <i>III</i> , <i>XIV</i> ; 14, 19
IX Tremulant X Swell to Choir		- •		Balanced expression pedals
XI Solo to Choir XII Bombarde to Choir		* 1982 / 87 † 2009 † 2017	7	to the Upper Choir, Swell and Solo Organs